

**... THE  
FORMATIVE  
PERIOD IN  
ALABAMA,  
1815-1828**

---

Thomas Perkins Abernethy



ALDERMAN LIBRARY  
UNIVERSITY OF VIRGINIA  
C







PUBLICATION OF  
THE ALABAMA STATE DEPARTMENT OF ARCHIVES AND HISTORY  
HISTORICAL AND PATRIOTIC SERIES  
NO. 6

---

354  
Mo. 1.11.11

# THE FORMATIVE PERIOD IN ALABAMA

1815-1828

BY  
THOMAS PERKINS ABERNETHY, Ph. D.  
Professor of History, University of Chattanooga

copy


PUBLICATION OF  
THE ALABAMA STATE DEPARTMENT OF ARCHIVES AND HISTORY  
HISTORICAL AND PATRIOTIC SERIES  
NO. 6

---

# THE FORMATIVE PERIOD IN ALABAMA

1815-1828

BY  
THOMAS PERKINS ABERNETHY, Ph. D.  
Professor of History, University of Chattanooga



MONTGOMERY, ALA.  
THE BROWN PRINTING COMPANY  
1922

F  
321  
A14  
no. 6  
Copy 2

338102

Y. T. RADVIL,  
ALBANY 10

## TABLE OF CONTENTS

Chapter	Page
<u>Letter of Transmittal</u>	<u>5</u>
<u>Preface</u>	<u>7-8</u>
<u>I. The Mississippi Territory</u>	<u>9-19</u>
<u>II. The New Country</u>	<u>20-23</u>
<u>III. The Immigrants</u>	<u>24-32</u>
<u>IV. The Division of the Territory</u>	<u>33-40</u>
<u>V. Alabama Becomes a State</u>	<u>41-49</u>
<u>VI. The Public Lands</u>	<u>50-56</u>
<u>VII. Agriculture</u>	<u>57-72</u>
<u>VIII. Rivers and Roads</u>	<u>73-85</u>
<u>IX. The Commercial Situation</u>	<u>86-92</u>
<u>X. The Bank Question</u>	<u>93-101</u>
<u>XI. Politics and the Election of 1824</u>	<u>102-109</u>
<u>XII. Politics and Federal Relations, 1824-1828</u>	<u>110-121</u>
<u>XIII. Religion, Education, and the Press</u>	<u>122-130</u>
<u>XIV. Social Conditions and Slavery</u>	<u>131-138</u>
<u>XV. Conclusion</u>	<u>139-146</u>
<u>Bibliography</u>	<u>147-159</u>
<u>Maps and Illustrations</u>	<u>161-192</u>

## LIST OF ILLUSTRATIONS

Note: Maps, charts, and illustrations, grouped together at the back of this book, are listed below under the chapters which have reference to them.

Plate	Page
Chapter I.	
1. Indian Cessions in Mississippi Territory.....	161
Chapter II.	
2. Geological Map of Alabama.....	162
Chapter III.	
3. Road Map, 1818.....	163
4. Origin of Population.....	164
Chapter V.	
5. Vote for Governor, 1819.....	165
6. Vote to Disapprove Censuring of Jackson, 1819.....	166
7. Melish Map of Alabama, 1820.....	167
8. Vote to Reduce Judicial Tenure.....	168
9. Vote Concerning Establishment of Branch Banks.....	169
Chapter VI.	
10. Indian Cessions in Alabama.....	170
11. Value of Lands Sold in Alabama.....	171
Chapter VII.	
12. Average Yearly Price of Middling Upland Cotton.....	172
13. Average Valuation of Slaves in Mobile.....	173
14. Cotton Crop of South Alabama.....	174
15. Slave Population, 1818.....	175
16. Slave Population, 1824.....	176
17. Slave Population, 1830.....	177
Chapter VIII.	
18. River Map.....	178
Chapter IX.	
19. Imports and Exports at Mobile.....	179
Chapter XI.	
20. Presidential Election of 1824.....	180
21. Senate Vote on Motion Proposing Jackson for Presidency.....	181
22. House Vote on Motion Proposing Jackson for Presidency.....	182
23. Election of U. S. Senator, 1822, (King and Crawford).....	183
24. Election of U. S. Senator, 1822, (Kelly and McKinley).....	184
25. Election of U. S. Senator, 1824.....	185
Chapter XII.	
26. Vote on Bill to Extend Jurisdiction of State Over Creeks.....	186
27. House Vote in Election of U. S. Senator, 1826.....	187
28. State House, Tuscaloosa.....	188
29. Vote on Bill Fixing State Capital at Tuscaloosa.....	189
30. Vote on Lewis Report Proposing Jackson for Presidency.....	190
Chapter XIII.	
31. University of the State of Alabama.....	191
Chapter XIV.	
32. Vote on Bill to Prohibit Import of Slaves to State.....	192

## LETTER OF TRANSMITTAL.

---

*To His Excellency,  
Governor Thomas E. Kilby,  
Montgomery, Ala.*

SIR:

I have the honor to transmit, herewith, recommending that it be published as bulletin No. 6 of the Historical and Patriotic Series of the State Department of Archives and History, a manuscript entitled "The Formative Period in Alabama, 1815-1828." The author, Dr. Thomas Perkins Abernethy, is a native Alabamian, at present, Professor of History at the University of Chattanooga. It was upon this thesis that he received his Ph. D. degree from Harvard University.

In his preface, Dr. Abernethy has set forth the sources from which he derived the information presented in his thesis. It will be seen that exhaustive research has been made.

Copies of this bulletin will be placed, with the compliments of this Department, in all public libraries in Alabama and in the college and high school libraries of the State. As long as the issue lasts, it will be subject to call by any student in the State with the hope that a perusal of these pages will inspire in the heart of the reader a love and veneration for our past and a renewed dedication of loyal service to our future.

Very respectfully,

MARIE BANKHEAD OWEN,  
*Director.*





## PREFACE

---

Dr. A. C. Cole begins his study of *The Whig Party in the South* with the year 1830, but necessarily, the basis for the confusing political alignments of the Southern Whigs lay largely in the years that had gone before the actual formation of the party. Alabama received her first great influx of population and underwent the formative period of her development during the apparently quiet administration of Monroe, when party lines were not recognized as existing. The new conditions of the frontier are sure to change old habits and old views, but the absolute lack of avowed partisan division during the period when Alabama was receiving her first wave of population gives us an especially good chance to study a society where men's political views are almost certain to be based directly on economic interest or individual conviction. With this in mind, it has been with the double purpose of obtaining an understanding of the conditions under which the cotton kingdom was planted on the Gulf Coast, and of trying to discover the process by which fixed party principles were crystallized out of the solution of social and economic elements which existed in Alabama during the period of settlement which followed the War of 1812, that the present work was undertaken.

A substantial body of material, principally in the Library of Congress, the Public Library of New York City, the Alabama Department of Archives and History, the Mississippi Department of Archives and History, and the Young Men's Christian Association Library of Mobile, has been searched, but there are important gaps in the body of information collected. This is especially the case in connection with the subjects of agriculture and slave-management, but, as the discovery of local peculiarities was the principal object of the study, it has seemed best not to fill in these blanks from general accounts. Only such information as deals particularly with Alabama has been used.

In connection with questions of politics, there also has been difficulty. In a period of settlement and of political uncertainty, there are few established lines of policy to guide the student on his way. But, on the other hand, there

is added interest in discovering from among the various problems which confront the community, the ones which develop sufficient significance to shape the course of events and to become solidified into partisan principles. Thus the study of the formative period has afforded an opportunity to find the principal questions upon which the people were divided, and hence to gain some understanding of the basis of later alignments. But, even so, many points upon which we would like to have information are left in comparative and tantalizing obscurity. The principal cause for this, as it appears to the writer, is that the questions which agitated the men of these early years were largely local matters, and the political leaders had not yet gained sufficient importance outside their own State to enable them to make a lasting impression. One of the politicians who grew up with Alabama was William R. King, but, though he later came to be Vice-President of the United States, we have few records to reveal his mind during the interesting time when his career was taking shape. And so it is for most of the others.

This work, submitted as a doctoral dissertation to the Faculty of the Graduate School of Arts and Sciences of Harvard University, was prepared under the stimulating direction of Professor Frederick Jackson Turner. The materials collected by the late Dr. Thomas M. Owen, of the Alabama State Department of Archives and History, made the research possible. Each of these men has been of inestimable aid and encouragement in my work.

I am indebted also to Dr. Dunbar Rowland, of the Mississippi State Department of Archives and History, and to Mr. J. C. Fitzpatrick, of the Manuscript Division of the Library of Congress, for aid in the collection of materials. Professor L. C. Gray, of the U. S. Department of Agriculture, office of Farm Management, kindly read the chapter dealing with agriculture; and Dr. Roland M. Harper, of the Alabama Geological Survey, gave me valuable aid in connection with geographical questions, but of course the writer is responsible for the treatment of these subjects given herein.

THOS. P. ABERNETHY.

## CHAPTER I.

---

### THE MISSISSIPPI TERRITORY

When England received West Florida from Spain at the close of the Seven Years' War, its northern boundary was the thirty-first parallel; but England later, for administrative purposes, changed the line so that it ran from the Chattahoochee due westward along the parallel of thirty-two degrees, twenty-eight minutes to the point where the Yazoo flows into the Mississippi. When Spain recovered the Floridas at the close of the American Revolution, she insisted on the northern boundary as fixed by England, but the United States protested, and finally won the point when the treaty of 1795 fixed the thirty-first parallel as the international boundary.

The disputed territory which extended from the Mississippi to the Chattahoochee was finally evacuated by Spain in 1797, and the next year, the United States, with the acquiescence of Georgia, which also laid claim to the land, established a territorial form of government for the district.<sup>1</sup> This was the original Mississippi Territory. In 1800 an elective assembly was authorized,<sup>2</sup> and in 1802 Georgia relinquished her claim.<sup>3</sup> After two more years, the boundary was extended northward to the Tennessee line,<sup>4</sup> and thus the Territory came to include all that land which is embraced by the present states of Alabama and Mississippi, except such as lies below the thirty-first degree of latitude.

Within this extensive area there were but two white settlements: one upon the lower Mississippi, and the other upon the lower Tombigbee River. Those who lived upon the Tombigbee had filtered through the Indian country from the time of the Revolution onward; some were Tory refugees, some were patriots who had left their old homes to seek new ones, and some were traders with the Indians. The blood of these men was various: English and Scottish traders mingled with

---

<sup>1</sup> Statutes at Large, II, 229-235.

<sup>2</sup> Ibid., II, 455-456.

<sup>3</sup> American State Papers, Lands, V, 384-385.

<sup>4</sup> Statutes at Large, II, 445-446.

Yankee frontiersmen, and many of them had taken native wives. The half-breeds were often men of wealth, and no distinction of race seems to have been made in the rugged life of the frontier.<sup>5</sup>

St. Stephens, a struggling village of log cabins, was the principal settlement in the Tombigbee region, and here the Government established a post for trading with the Choctaw Indians, and, as soon as Georgia gave up her claim to the soil, a land office. The act arranging for the disposal of the public domain was passed in 1803.<sup>6</sup> It provided for the validation of claims under the British and Spanish grants; quieted claims under the act of Georgia establishing Bourbon County in 1785;<sup>7</sup> granted tracts of 640 acres to actual settlers at the time of the Spanish evacuation in 1797; and gave preemption rights to settlers occupying land at the time the act was passed. Settling on public lands was forbidden, but squatters continued to come in and an act of 1807 extended preemption rights to those who had already come in, but once more prohibited entries upon government lands for the future. Lands not otherwise appropriated were to be surveyed and put on sale at public auction according to the provisions which had already been adopted for the Northwest Territory. Accordingly in 1807 the first sales took place at St. Stephens.<sup>8</sup>

In 1806 the Government acquired from the Indians a small triangle of land lying between the Tennessee border and the great bend in the Tennessee River. In 1809 this tract, the original Madison County, was offered for sale and readily taken up by cotton planters from Georgia. Here Huntsville was built about a great spring, and soon came to be the commercial center of the new region.<sup>9</sup>

Cotton was raised in the Alabama-Tombigbee region as early as 1772;<sup>10</sup> the manufacture of cotton cloth was begun by the Cherokees in 1796-97;<sup>11</sup> and Colonel Benjamin Hawkins, who was for many years agent for the Creeks, states in his *Sketch of the Creek Country for 1798 and 1799* that a Scottish trader, who had made his home among the Indians and had taken a native woman for his wife, first raised a quantity of

---

<sup>5</sup> Pickett, *History of Alabama*, Chap. XXXI.

<sup>6</sup> Statutes at Large, II, 229-235.

<sup>7</sup> E.C. Burnett in *American Historical Review*, XV, 66-111, 297-353.

<sup>8</sup> American State Papers, Misc., II, 417.

<sup>9</sup> Betts, *History of Huntsville*, 23-24.

<sup>10</sup> Pickett, *History of Alabama*, 326.

<sup>11</sup> Morse, *Report on Indian Affairs*, 167.

green seed cotton for the market, but, finding it more profitable to manufacture his own staple, employed eleven hands, besides his own family, in the industry.<sup>12</sup> In 1802 the first cotton gins were introduced into the Alabama country, two of the three of them being set up among the Indians.<sup>13</sup> By 1808 the staple had come to be the leading agricultural product of the region.<sup>14</sup>

From the very first its culture among the whites seems to have been associated with negro labor, for in 1810 slaves made up nearly forty per cent. of the population upon the lower Tombigbee; and ten years later, after the cotton regime was well begun, the proportion of slaves in this early-settled region remained abnormally high. The men who entered Madison County in 1809 were largely Georgia planters of considerable means. They came especially for the purpose of raising cotton, and their slaves were numerous. Their entrance into Mississippi Territory at this time indicates that the cotton regime might have begun earlier than it did had not the War of 1812 intervened to delay it.

But the culture of cotton was still in its infancy in 1812. Scrawny hogs, whose ancestors are supposed to have been left by DeSoto, and whose descendants are said to be the modern razor-back, roamed the woods; and in the cane-break region near the Gulf, large herds of cattle, sometimes numbering many hundreds, found their own forage summer and winter alike.

Aside from the fur trade with the natives and the growing cotton industry, there seems to have been little commerce carried on during these years in the Alabama country, and the reason is not far to seek. Mobile, the only accessible outlet, was in the hands of the Spanish, and the duties which they charged were almost prohibitive. In order to avoid the payment of them, Gaines, the agent at St. Stephens for the Choc-taws, brought his supplies down the Tennessee River to Colbert's Ferry, above Muscle Shoals, carried them over a portage, which came to be known as Gaines' Trace, to the head of navigation on the Tombigbee at Cotton Gin Port; and thence floated them down to St. Stephens.<sup>15</sup> This was the route by which a number of the early Tombigbee settlers reached their

---

<sup>12</sup> Hawkins, *Sketch of the Creek Country*, 44, 55.

<sup>13</sup> Pickett, *History of Alabama*, 469-470.

<sup>14</sup> Jack, *Sectionalism and Party Politics in Alabama*, 7.

<sup>15</sup> Pickett, *History of Alabama*, 506.

destination,<sup>16</sup> and it long remained an important route of travel for the pioneer.

Until 1806, rivers and Indian trails were the only means of communication in the Alabama region, but in that year Congress provided for the construction of the first two roads.<sup>17</sup> One was to connect Nashville, Tennessee, with Natchez upon the Mississippi, crossing the Tennessee River at Muscle Shoals. It was known as the "Natchez Trace" and came to be a highway of no little importance in the western country. The other was to follow the route from Athens, Georgia, to New Orleans, passing through the settlement on the Tombigbee. It came to be known as the "Federal Road" and along it thousands of settlers later found their way to Alabama.

Such were the slender bands of communication which tied the frontier settlements of eastern Mississippi Territory to the world from which they were separated by hundreds of miles of Indian wilderness. Between the Tombigbee clearings and the settled part of Georgia lay the confederacy of the Creeks extending its boundaries northward well toward the Tennessee line. Adjoining the Creeks on the north lay the territory of the Cherokees, extending eastward into Georgia and northward into Tennessee. Between the Tombigbee and the settlements upon the lower Mississippi lay the lands of the Choctaws, and northward of them the country of the Chickasaws took in the northwestern corner of the future Alabama and extended across western Tennessee.

These Indian tribes of the South were further advanced toward civilization than were most of their North American kinsmen, and, though the westward migration of the whites was still in its infancy, they saw clearly the problem which confronted them. They had two alternatives compatible with peace,—to perfect themselves in the arts of civilization, so as to compete with the new-comers, or to be driven off the land which had been theirs from generation to generation. There was but one other possibility,—to fight.

Already game had become too scarce to be relied upon as the only source of food supply,<sup>18</sup> and all the Southern Indians engaged in a crude method of agriculture. They dwelt in villages with fields adjacent, and maize, beans, and melons

---

<sup>16</sup> Ibid., 466-469.

<sup>17</sup> Statutes at Large, II, 397.

<sup>18</sup> Indian Office files, R. J. Meigs to Geo. Graham, May 6, 1817.

were the principal crops which they cultivated. Their methods of culture were primitive and they rarely produced more than sufficed for their own needs.<sup>19</sup>

The more the natives resorted to agriculture, the less ground they needed for the purpose of hunting. This consideration may partly account for the interest which the Government of the United States took in the civilization of the Red Man, but such interest was good policy on general principles, for a civilized Indian afforded a less pressing problem than did one in his native simplicity.

During Washington's administration the system of appointing an agent to each of the different tribes was adopted. The agent acted as intermediary between the Government and the Indians; attempted to protect them from corruption by supervising their relations with the whites; and tried to promote their civilization by instructing them in agriculture and craftsmanship. The Indians were not allowed to buy whisky from the whites and the whites were not allowed to live among them except by permission from the agents. Such permits were granted to blacksmiths, carpenters, wheelwrights, and other craftsmen who were needed, but natives were instructed in the crafts and sometimes were able to supply a large part of the demand for skilled workmen.<sup>20</sup>

The Indians were encouraged by the agents to keep domesticated animals and a few of them came to own large herds. They were also instructed in the use of the plow and furnished with seed for planting. The culture of cotton was introduced among them, and they were taught the use of the spinning wheel and the loom. Indeed, some of the native craftsmen learned to make the wheels and looms and turned them out in large numbers.

Of all the Indians, the Cherokees most readily took to the ways of civilization. Realizing the uselessness of resistance, they wished to adjust themselves to the inevitable, and through education and industry to fit themselves for citizenship. They took up agriculture so seriously that some of them quit their villages for the purpose of living upon their farms. They kept large numbers of domesticated animals, and learned to spin and weave. They built roads and erected saw mills and

<sup>19</sup> Good accounts are given in Hawkins, *Sketch of the Creek Country*; and Morse, *Report on Indian Affairs*, 167 *et seq.*

<sup>20</sup> Indian Office files, R. J. Meigs to Sect'y of War, Nov. 4, 1816; Silas Dinsmore to Jno. McKee, Oct. 28, 1815.





cotton gins. Sequoya, a native Cherokee, invented an alphabet for the use of his people and they set about diligently to learn to read and write. They even drew up a constitution and instituted a representative government.<sup>21</sup> A census of 1825 shows them, with a population of fifteen thousand, to have possessed thirteen hundred slaves, twenty-two thousand cattle, over seven hundred looms, more than two thousand spinning wheels, nearly three thousand plows, ten saw mills, thirty-one grist mills, eight cotton gins, eighteen ferries, and eighteen schools.<sup>22</sup>

The Chickasaws and Choctaws, though somewhat less advanced than the Cherokees, followed their policy of absorbing what civilization they could, and of remaining friendly with the whites. The Creeks, on the contrary, were warlike and not inclined to adapt themselves to the new situation. The strength of their confederacy and the fact that their lands bordered upon Spanish Florida may help to explain their relatively independent attitude.

Just before the War of 1812 broke out, and Tecumseh undertook to unite all the western Indians against the United States, he visited the Creeks at one of their great councils, and the younger warriors were incited to hostility against the whites. Though the older chiefs remained peaceful, the war or *red stick* party was powerful and presently took matters into its own hands.<sup>23</sup>

Florida was still legally in the possession of Spain, but the Napoleonic wars had so shaken the position of the ancient kingdom that her government had fallen prey to French and British armies. The future possession and control of the province became doubtful and Madison, fearful for our southern frontier, issued a proclamation in 1810 calling for the occupation of West Florida. It was at that time, however, taken over only as far as Pearl River. Three years later Mobile was occupied, but Pensacola remained in Spanish hands. Thither a band of the hostile Creeks repaired in 1813 for the purpose of securing munitions of war. The settlers upon the Tombigbee, learning of the expedition, mustered their military strength and marched to meet the Indians as they returned. In the battle of Burnt Corn which followed, the whites

---

<sup>21</sup> Nineteenth Annual Report, Bureau of American Ethnology, Part I, 104-113.

<sup>22</sup> *Southern Advocate*, April 21, 1826.

<sup>23</sup> McMaster, *History of the United States*, III, 535-6.

drove the Indians from the field, but while the victors collected the booty, the Indians rallied, set upon them, and routed their little band.<sup>24</sup>

The isolated Tombigbee settlers recognized this skirmish as the prelude to a bloody Indian war. Seeing no prospect of adequate military assistance, they hurriedly gathered at convenient houses, surrounded them with stockades, and anxiously awaited the movements of the savage warriors. Several hundred men and women were gathered at the home of a half-breed named Mims. A stockade was constructed and the place came to be known as Fort Mims, but of military discipline there was little or none. Warned of the presence of Indians, they took no heed, and when the savages attacked, were utterly unprepared. The defense was desperate but hopeless; and when the day was over, there remained but the smoldering ruins and the bodies of the dead. Of all that had been gathered in the fort, only a handful escaped.

Appeals for aid were quickly sent to Georgia, Louisiana, and Tennessee; and Andrew Jackson, Major-General of the Tennessee militia, collected a force for an expedition. Marching through Huntsville, and crossing the Tennessee River where he established Fort Deposit, he entered the country of the Creeks and established Fort Strother upon the upper waters of the Coosa. Often forced to the last extremity by the difficulty of getting supplies and by the restiveness of militia enlisted for short terms of service, Jackson nevertheless cut a road through the wilderness, fought several minor engagements with the savages, and finally reached their principal stronghold at Horseshoe Bend, in the Tallapoosa River. Here the Indians had erected a breastwork across the neck of the peninsula formed by the bend of the river. Jackson attacked this work in front while his lieutenant, General Coffee, approached the bend from the other side of the stream. Here the Indians had collected a large number of canoes in which to make their escape if it should become necessary; but taking these, Coffee crossed the river and attacked the defenders from the rear. Thus trapped, the stubborn resistance of the natives was ineffectual. Some escaped across the river, others were drowned while attempting to get away; and several hundred were left dead upon the field.<sup>25</sup>

<sup>24</sup> Henry Adams, *History of U. S.*, VII, 228-229; Pickett, *History of Alabama*, 523-524.

<sup>25</sup> McMaster, *History of the United States*, IX, 162-170. Bassett, J. S., *Andrew Jackson*, I, 91-92, 116-117.

The battle of Horseshoe Bend broke the power of the hostile Creeks. Many were dead, and others fled across the Spanish line into Florida. In 1814 the chiefs who remained met Jackson at the confluence of the Coosa and Tallapoosa, where Fort Jackson was erected, and were forced to surrender a broad strip of their land running along the Florida border, and all that which lay west of the Coosa River. Thus practically the entire Alabama-Tombigbee basin was cleared of the Indian title and secured for settlement by the whites. Mississippi Territory was indebted to Jackson not only for safety, but also for room in which to grow.

That the Southwest was to become a cotton kingdom was foreshadowed by the early history of Madison County. When the old tobacco-growing districts of the Southern seaboard began to overflow into the piedmont region, a number of Virginia immigrants established the town of Petersburg where the Broad River flows into the Savannah, in Elbert County, Georgia. Here tobacco warehouses were erected and a brisk business ensued. But it did not last long. When the invention of the cotton gin made short staple cotton available for commercial purposes, this crop supplanted tobacco as the principal product of the piedmont region in Georgia and South Carolina. Tobacco warehouses were no longer necessary and Petersburg was abandoned.<sup>26</sup> Its inhabitants were the chief founders of the town of Huntsville.<sup>27</sup> In the small triangle which was the Madison County of that day, nearly a hundred and fifty thousand acres of land were sold between 1809 and 1812.

During this period the sales of land in the Tombigbee settlement were relatively small excepting that, in the single year 1812, sixty-four thousand acres were disposed of at St. Stephens.

The war naturally halted the progress of the westward movement, but with the coming of peace, the migration was resumed with greatly renewed vigor. The Indians were no longer to be feared, a vast expanse of new territory had been cleared of the native title, cotton was in great demand, and a spirit of adventure and speculation took hold upon the country. In 1816 more than a hundred seventy thousand acres were sold at St. Stephens.<sup>28</sup>

---

<sup>26</sup> C. C. Jones, Jr., *Dead Towns of Georgia*, 234-238.

<sup>27</sup> Betts, *History of Huntsville*, 22-24.

<sup>28</sup> American State Papers, Misc., II, 417.

The territory secured from the Creeks had to be surveyed before it could be placed upon the market, and surveys took time. But the westward rush of land-hungry men did not wait upon the Government. Settlers pushed into the country in great numbers. They were usually poor men who had sold all they possessed to secure the necessary means of transportation, and at the end of the journey they sometimes found themselves stranded without food to last until the first crop could be made.<sup>29</sup> There were also land speculators who were engaged in seeking out choice tracts for purchase when the Government sales should begin; there were merchants who had brought wagon loads of goods, which they displayed in hastily-erected huts to the settlers; and there were fugitives from justice seeking refuge in a country where the hand of the law was weak.

Crimes were, of course, committed in such a community as this;<sup>30</sup> and to make the situation worse, those Creeks who had remained friendly to the United States during the war felt, with reason, that they had been unjustly treated when their lands were taken away; and they threatened to give trouble.<sup>31</sup> Since no civil jurisdiction was established in the region, Governor Holmes, of Mississippi Territory, issued a proclamation on June 29, 1815, incorporating the whole of the Creek cession as Monroe County.<sup>32</sup>

This action was not in accord with the ideas of the Government, for an act of 1807 had forbidden intrusion upon the public lands. In accordance with this act, President Madison issued a proclamation in December, 1815, ordering the removal of squatters and authorizing the use of military force to accomplish that purpose.<sup>33</sup> Some ejections were made, but Congress heard the plea of the squatters and, by an act of April 26, 1816, those who had come in before February of that year were to be allowed to remain until the land upon which they were settled should be sold.<sup>34</sup>

---

<sup>29</sup> Indian Office files, R. J. Meigs, to Andrew Jackson, Jan. 17, 1816; Jackson Papers, E. P. Gaines to Andrew Jackson, March 6, 1817.

<sup>30</sup> Toulmin-Holmes correspondence, Gen. E. P. Gaines to Judge Harry Toulmin, June 1, 1815; Judge Toulmin to Gov. Holmes, June 5, 1815.

<sup>31</sup> *Washington Republican*, Oct. 21, 1815.

<sup>32</sup> Gov. Holmes, Executive Journal, 1814-1817; Proclamation of June 29, 1815.

<sup>33</sup> *Washington Republican*, Jan. 10, 1816; Jackson Papers, Wm. H. Crawford to Andrew Jackson, Jan. 27, 1816.

<sup>34</sup> *Ibid.*, June 12, 1816.

The Creek cession overlapped, on the north and west, lands claimed by the Choctaw, Chickasaw, and Cherokee Indians. The Government commissioned Andrew Jackson to treat with these tribes for their claims to the disputed areas, and treaties providing for the relinquishment of all three tracts were drawn up in 1816. This cleared up the Indian title to the greater part of that territory which was soon to become the State of Alabama. The Creeks still held the entire tract lying east of the Coosa River; the Cherokees held the northeastern corner above this; the Chickasaws held a small tract in the northwestern corner; and the Choctaws retained a little land west of the Tombigbee.<sup>35</sup>

On May 9, 1817, Governor Holmes issued a proclamation creating three new counties which included the new cessions and a part of the Creek cession. Elk County was to comprise the land lying north of the Tennessee River and west of Madison County; Blount County was to be made up of that lying south of the Tennessee and north of the watershed between that river and the Alabama-Tombigbee basin; and Shelby County was to comprise the country lying south of Blount County bounded on the west by the Tombigbee, on the south by Clarke County, and on the east by the watershed between the Tombigbee and Alabama Rivers.<sup>36</sup> But the act dividing the Territory had already passed in Congress, and these three counties never had a concrete existence. An Elk County is sometimes enumerated in the early gazetteers, and a Blount and a Shelby County were established in Alabama Territory in 1818, but they have no continuity with those established by Governor Holmes.

---

<sup>35</sup> See *Eighteenth Annual Report*, Bureau of Ethnology, Plate I.

<sup>36</sup> Gov. David Holmes, Executive Journal, 1814-1817, Proclamation of May 9, 1917.

## CHAPTER II.

---

### THE NEW COUNTRY<sup>1</sup>

The new country which was soon to become Alabama is divided, from an agricultural point of view, into three principal regions: the Tennessee Valley, the Alabama-Tombigbee basin, and the central hilly region which separates these two. Fed by streams which drain the country as far north as the Tennessee Valley, the Alabama and Tombigbee Rivers traverse the central and southwestern portions of the area, and empty their united waters into Mobile Bay. In the early days of Alabama, these streams furnished the only good commercial highway into the State. They bound her southern section into one cotton-growing community, and their fertile bottom lands furnished most desirable fields for the planter of the staple.

The central hilly region is drained by southward-flowing streams which are not navigable; and the inaccessibility of the region, together with the rugged nature of the land, prevented it from attaining agricultural importance. Yet the isolated valleys were often fertile, and a scattered population maintained frontier conditions here for a long time.

Making a large bend across the northern end of Alabama, the Tennessee River flows through a wide and fertile valley. During the early days the produce of this region had to be floated down the long and tortuous courses of the Tennessee and Mississippi Rivers to New Orleans, but the soil was fertile and attracted, from the very first, planters in large numbers.

Looked at more in detail, the surface of Alabama is divided into several areas differing in formation and fertility of soil.<sup>2</sup> Entering the northeastern corner of the State with the Tennessee River and running down toward the center, is the southern extremity of the Cumberland Plateau. Here the ridges run in long sweeps and give a really mountainous aspect to the region. Lookout Mountain is the most pronounced

---

<sup>1</sup> The description given here is based almost entirely upon that by Roland M. Harper in *A Preliminary Soil Census of Alabama* and in his *Economic Botany of Alabama*, though the writer has relied to some extent upon his personal knowledge of the country.

<sup>2</sup> In addition to the map given here, see that by Eugene A. Smith, U. S. Census, 1880, VI. 9; and that in the *Atlas of American Agriculture*, cotton section, 8.

of the highlands. South of the Tennessee Valley the ridges give way to the broken hills of the north-central portion of the State.

Skirting the plateau to the eastward and running parallel with it, lies the Coosa Valley, which represents the southern extremity of the great valley extending from Virginia. There are stretches of good land here, but the early communities were isolated and it did not become a region of extensive agriculture.

Toward the eastward, the Coosa Valley is bordered by the southern foothills of the Blue Ridge, and, forming a triangle between the Ridge and the Georgia line, lies the piedmont section which corresponds to that skirting the mountains in Georgia, the Carolinas, and Virginia. As in the piedmont regions of the older states, the stiff, red lands here are of unequal quality but capable of improvement and of fair average fertility. Until 1836 the Creek Indians retained possession of the country east of the Coosa River; consequently this section was not settled as early as most of the other parts of the State.

Beginning at the eastern border just below the piedmont section and sweeping across to the northwest corner of Alabama in a broadening curve, the short leaf pine belt borders the older country of igneous rock, and marks the beginning of the coastal plain. Here the soil is composed largely of sand and gravel. It is below the average in fertility, rolling piney woods being characteristic of the region.

Next toward the south is the Black Belt,<sup>3</sup> or prairie region, which begins within the State and follows the curve of the short leaf pine region. It presents a gently rolling terrain, much more level than any of the surrounding country, and also somewhat more depressed. These peculiarities are due, perhaps, like the quality of the soil, to the soft limestone which underlies it. The soil is a sticky, calcareous clay, and a part of it was originally unforested. Holding surface moisture in the winter, it forms a tenacious mud which renders roads all but impassable, and in the summer it bakes to a hard crust. A description of this region given by one of the early settlers in 1821 affords a graphic idea of the appearance of the country:

"Wherever these prairies exist, the lime is this soft consistence, when it approaches near the surface, the soil appears whitish, and is clothed with a short growth of grass

---

<sup>3</sup> See H. F. Cleland in *Geographical Review*, X, 375-387.

and herbage; where it lies deeper the grass is denser and taller, and upon the borders, between the wood land and prairies, the growth of weeds and grass is very luxuriant. But upon the prairies themselves, there is not sufficient depth of earth for the growth of trees. Such is the checkered and diversified appearance of this part of the country where those prairies exist. Fancy yourself for a moment in such a situation; before you a wide and extended meadow, to the right and left intervening strips of oaks and pines; proceeding onwards, the prospect seems terminated by the surrounding woods; anon, you catch a glimpse of the opening vista; and now again the prospect expands into the wide spread horizon of an extensive prairie. These prairies are generally rolling; which is a great advantage, as otherwise they retain water, to the great injury of the crops; and as it respects the quality of the soil, it is generally admitted that it is the best the country affords. . . . The only objection to these prairies is, the scarcity of good water. . . ."<sup>4</sup>

The relative scarcity of running water, together with other disadvantages, affords special problems to the farmer, and the towns which grew up in connection with the cotton industry here—Montgomery, Selma, and others—are located on the edge of the prairie rather than within it. Though the planters at first sought the river bottoms and avoided the prairie, the latter came after 1830 to be looked upon as the best cotton land in the State. As late as 1880 it formed the principal cotton producing area of Alabama.

Montgomery County has always been a cotton-planting center, and its early history is illustrative of such settlements. Almost the entire area of the County consists of fine prairie lands which extend in long, unbroken stretches of fertile fields. But the Alabama River, which forms its northern boundary, is bordered by bottom land which is not of the prairie type. A map of the County, made up from the land records and showing the dates at which the tracts were purchased from the Government, brings out the fact that the great majority of the settlements before 1821 were made in the river bottom area. By 1828 encroachments were being made upon the prairie, but the greater part of it was still unsettled. On the other hand, in Clarke County, at the confluence of the Alabama and Tombigbee Rivers, there were extensive settlements be-

---

<sup>4</sup> Letter from Dr. J. W. Heustis, of Cahawba, April 1, 1821, *Cahawba Press*, June 2, 1821.



fore 1821, though very few between that year and 1828. In Dallas and Perry Counties where there is both river and prairie land, the river bottoms and the red lands bordering the prairies were taken up, but few settlements were made in the prairies before the end of 1828.<sup>5</sup>

The Black Belt is bordered on the south by the Chunnennuggee Ridge. This runs across the State in a narrow strip, but toward the eastern border where the Black Belt dwindles away, the Ridge broadens and replaces it. A limestone formation underlies this section, but it is different from that of the prairie region in being of normal hardness. This accounts for the fact that the Ridge country rises distinctly above the prairie, and that its surface is of a relatively rugged character. The soil is predominantly a sandy loam and is, like that of the Black Belt, above the average in fertility. Looked at from the standpoint of cotton culture, the two regions might be grouped together.

Below the Chunnennuggee Ridge and extending to the southern border of the state, lie the Southern Red Hill<sup>6</sup> and Southern Pine Hill regions. Between these lie two small calcareous areas, but there are no marked transitions in the surface here. The appearance of the country and the nature of the soil are fairly uniform, so that from an agricultural standpoint, these areas might be considered together.

In the region of the Red Hills the surface is broken and rises almost to mountainous ruggedness in places. One of the two railroad tunnels in the whole coastal plain lies in this section. Pine predominates over other forest trees, and the soil is reddish sandy clay. Its fertility is only average, but fertilizers can be used to advantage.

Proceeding toward the coast, the hills become less pronounced and the long leaf pine predominates over all other trees. The character of the soil does not change materially; it is relatively infertile, but subject to improvement by artificial fertilization.

It is worthy of note that in the Gulf coastal plain there is nothing corresponding to the pine barrens of the South Atlantic States. The reddish sandy clay prevails all the way to the coast, and the surface presents a rolling, and often a rugged, appearance.

---

<sup>5</sup> Based upon maps made from the tract books in the office of the Secretary of State, Montgomery, Alabama.

<sup>6</sup> See R. M. Harper in *South Atlantic Quarterly*, XIX, 201.

### CHAPTER III

---

#### THE IMMIGRANTS

During the latter half of the seventeenth century, England was developing the spinning and weaving machinery which played such a large part in bringing about the Industrial Revolution. The increased demand for raw cotton which resulted from this development was answered in 1793 by Whitney's invention of the cotton gin. Until this time, it was necessary to separate the lint from the seed by hand or by means of a pair of simple rollers. The black seeded sea-island, or long staple, cotton was the only variety amenable to such processes, for its long fibre did not cling closely to the seed and could be removed easily. The short staple of the green seeded variety clung so closely to the seed that it could not be removed profitably by these simple processes in use.

Long staple cotton could be raised only in the tidewater regions, and the coast and sea-islands of Georgia and South Carolina produced practically all the American output. The short staple cotton, on the other hand, could be raised in the uplands, and when the invention of the cotton gin rendered the culture of this variety profitable, the Georgia and South Carolina piedmont supplanted the tidewater as the principal cotton-producing area.<sup>1</sup>

This region had been settled by men largely from Virginia and Pennsylvania. The culture of tobacco was the main industry for some years, but when upland cotton was introduced it quickly came to predominate. Towns founded for the warehousing and inspection of tobacco were abandoned because their facilities were no longer necessary.<sup>2</sup> Such a one was Petersburg, at the confluence of the Broad with the Savannah River, the removal of whose inhabitants to Madison County was mentioned in the first chapter.

That the spread of the culture of cotton into the Southwest was inevitable, is indicated by its early introduction into Mississippi Territory. This natural movement was interrupted by the War of 1812, but its pent-up force was precipitated by the

---

<sup>1</sup> *Atlas of American Agriculture*, cotton section, 16, 18.

<sup>2</sup> Phillips, *Transportation in the Eastern Cotton Belt*, 46-56.

conditions which followed the end of the struggle. In England, cut off from her source of supply during the War, the price of the staple rose to an abnormal level; while in America, deprived of her usual market, the price fell off sharply. When peace was made and normal trade relations were resumed with the lifting of the blockade of our coast, England again obtained her supply of American cotton and the price in this country rose immediately. The average price for 1815 was almost thirty cents a pound.<sup>3</sup>

To this situation was added the inducement of new lands cleared of the Indian title during the War, and the innate restlessness of the population. Sales of newly surveyed land were opened at St. Stephens during the latter part of 1815, and the following year over a hundred thousand acres were disposed of by the Government.<sup>4</sup> No sales were made in the new Creek cession until 1817, but in that year three-quarters of a million dollars' worth of these lands were sold.<sup>5</sup>

The old Georgia-South Carolina piedmont region had two distinct disadvantages from the point of view of the cotton planter. Its soil was not considered so fertile as that of the Alabama river-bottoms and prairies; and it lacked transportation facilities, being cut off from the tidewater by the broad pine-barrens, and being without navigable rivers. Thus, before the culture of upland cotton had reached anything like a mature development here, it began to be transferred to the new Southwest. Population began to flow from the older states into the pioneer country until the drain was keenly felt in the deserted communities.

Though the statement cannot be backed by statistics, it seems that the majority of the planters who moved westward with their slaves came from the piedmont rather than from the tidewater regions of the South Atlantic states.<sup>6</sup> The tidewater had its staple crops of tobacco, rice, and sea-island cotton, which were not disturbed by the new developments. The planters here were usually well established, their investment was heavy, and their land had a certain monopoly value. Their slaves could still be employed more or less profitably, and their social position tended to hold them where they were. The

<sup>3</sup> *Atlas of American Agriculture*, cotton section, 18.

<sup>4</sup> American State Papers, Misc., II, 417.

<sup>5</sup> *Ibid.*, Lands, V, 384-385.

<sup>6</sup> This statement is strongly supported by the cases where the writer has been able to ascertain the origin of the immigrants.

piedmont region had never had a staple until upland cotton was introduced, and the west offered it a choicer field.

Few people of extensive wealth moved into the Alabama region during the period of early settlement. Only the man who needed to better his fortune had an inducement to make the necessary sacrifice. Those who had slaves usually owned but a small number, and many who later became planters had no slaves at all to begin with. In other words, the small farmer of the piedmont region became the pioneer planter of the Southwest.

When a man prepared to transplant his establishment, he usually sold the land he held and retained the proceeds for the purchase of his new domain. His household goods and farm implements were packed on wagons and started out on the rough road toward the new home. The slaves drove the herds of cattle and hogs, while the planter's family brought up the rear in a carriage.<sup>7</sup> It was a tedious journey, the roads being merely clearings through the forest, and without bridges. The smaller streams were forded and crude ferries were established at the larger ones. Yet there were compensations; hunting along the way afforded diversions for the men, and the camp-fire about which the wayfarers gathered at night shed a romantic glow upon the faces of those who were traveling into a strange land.

Having reached the place where he was to make his home, the planter constructed a log cabin after the usual manner. Two rooms were built opposite each other and joined by a passage-way. Chimneys built of stones or clay-daubed sticks were put up at opposite ends of the structure and great open hearths served for both heating and cooking. A "lean-to" might be attached behind one or both of the rooms, and an attic might be constructed above. Before the introduction of saw mills, the floors were made of puncheons, or logs split in halves, with the flat side upward. The chinks between the logs were filled with clay; the doors and shutters were of crude boards, and the shingles were hand-split. In such a dwelling, the planter who brought his household furnishings could establish a kind of rude comfort, which sufficed even the wealthiest immigrants during the first few years of their sojourn. The first and only governor of Alabama Territory lived in

---

<sup>7</sup> Hodgson, *Letters from North America*, I, 138.

such a log cabin during the years of his administration and until his premature death.<sup>8</sup>

But all the newcomers were not even thus fortunately situated. No very extensive tracts of the new land were offered for sale before 1818, and men who had homes to sell in the old states would naturally wish to purchase a location in the new country before removing. Yet, from 1815 onward, men poured into the ceded lands and "squatted" upon them in spite of the law and the Government.<sup>9</sup> It was the policy of the United States to prevent intrusion until surveys could be made and the lands offered for sale at auction. Attempts were made to remove the squatters; the troops were called in and ordered to burn the cabins of those who refused to leave, but it was all of no avail.<sup>10</sup>

Men of this class, being improvident by nature, did not come to seek wealth, but merely to gain a subsistence, or to enjoy the freedom of the woods. They built their simple cabins and planted their crops of corn between trees which they killed by circling. Their greatest immediate problem was to live until the first crop was made, and here there was much difficulty.<sup>11</sup>

The influx of immigrants was so great in 1816 and 1817 that the Indians and scattered pioneers were not able to furnish enough corn to meet the needs of the new-comers. In 1816 corn brought four dollars a bushel along the highway from Huntsville to Tuscaloosa,<sup>12</sup> and so scarce did this article become among the local Indians that the Government had to come to their rescue in 1817 in order to relieve actual distress.<sup>13</sup>

It is worth our while to know whence the various immigrants came into the Alabama country; by what routes they reached their destination; and in what part of the territory they settled. Although statistics cannot be produced, a fairly reliable idea may be had from various accounts which, in the main, agree.

---

<sup>8</sup> Pickett Papers, *Sketch of Wm. Bibb*, by John D. Bibb.


<sup>9</sup> Indian Office files, R. J. Meigs to Louis Winston, June 12, 1815.

<sup>10</sup> Jackson Papers, Instructions from Wm. H. Crawford, Jan. 27, 1816; Indian Office files, A. Jackson to Wm. H. Crawford, July 4, 1816; *Ibid.*, R. J. Meigs to Louis Winston, June 12, 1815.

<sup>11</sup> An interesting letter from Clabon Harris to General Jackson, Fort Claiborne, Jan. 12, 1816, gives an account of the conditions of some of the squatters. This is in the Jackson Papers.

<sup>12</sup> Meek MS., *Early Settlement of Alabama*.

<sup>13</sup> Indian Office files, Cherokee Chiefs to R. J. Meigs, March 20, 1817; *Ibid.*, Samuel Riley to R. J. Meigs; Jackson Papers, E. P. Gaines to A. Jackson, March 6, 1817.



EMBRYO TOWN OF COLUMBUS ON THE CHATTAHOOCHEE  
From *Camera Lucida* by Capt. Basil Hall, R. N., 1828.

The two roads through Mississippi Territory for which Congress made appropriations in 1806 were continuations of established routes of travel.<sup>14</sup> That from Nashville to Natchez crossed the Tennessee River at Muscle Shoals and was known as the "Natchez Trace." It was a continuation of the "Kentucky Trace" which passed from Nashville through Lexington, to Maysville, and thence by the Old National Road through Columbus, Zanesville, and Wheeling, then on to Pittsburgh. Following the general course of the Mississippi, the Natchez Trace was the principal highway for the region which it traversed. As a matter of fact, however, it was hardly more than a bridle path through the woods and did not deserve to be called a road.

The highway along the route from Athens to New Orleans which followed the direction of the Alabama River and passed through the Tombigbee settlements, came to be known as the "Federal Road."<sup>15</sup> Beyond Athens, the route passed north-eastward through Greenville, Salisbury, Charlotte, and Fredericksburg, then on to Washington, Baltimore, and Philadelphia. Thus it traversed the piedmont region of the South Atlantic states and connected the Southwest with the commercial centers of the East.

Diverging from this route just beyond the Georgia line, another highway passed eastward of it and connected the Southern capitals which stood at the fall line of the rivers flowing into the Atlantic. Extending through Milledgeville, Augusta, Columbia, Raleigh, and Richmond, this again united with the piedmont route just before reaching Washington.

But there was still another means of access to the Alabama country which was of great importance. Diverging from the Pittsburgh-Philadelphia highway, this road passed southwestward through the Valley of Virginia, then followed the course of the Holston river to Knoxville. From Knoxville the original highway passed westward to Nashville, but with the formation of Madison County, a spur was extended southward to Huntsville, and this soon came to be an important route of travel.

---

<sup>14</sup> The map given here is based upon that prepared by John Melish for 1818, but it has been compared with all those in the Library of Congress for the period covered. Information as to principal routes of communication is based also upon the accounts of travel available to the writer.

<sup>15</sup> It seems that this road was not actually opened until 1811. See Phillips, *Transportation in the Eastern Cotton Belt*, 69; and Ball, *Clarke County*, 134.

Now, a man coming into Alabama from the piedmont region of Georgia would have the choice of two routes. He could go by the Federal Road into the Alabama-Tombigbee basin or he could take a road which passed from Augusta to Athens, crossed the Tennessee River where Chattanooga now stands, and led on to Nashville.<sup>16</sup> The highway crossed the road from Knoxville to Huntsville and gave access to the fertile Tennessee Valley region. The Georgia men who helped to settle Madison County in 1809 took this route,<sup>17</sup> but the later emigration of Georgia planters was mostly into the southern part of Alabama, and they passed along the Federal Road.

The first lands of the Creek cession which were put on sale were disposed of at Milledgeville, Georgia, and they lay along the upper course of the Alabama River in the neighborhood of the later Montgomery County.<sup>18</sup> It is easy to understand, therefore, how it was that the Georgia planters established a predominance in this region from the first. With this as a nucleus, the immigrants from Georgia seem to have followed the route of the Federal Road and they came to form perhaps the strongest element in the population of all the southeastern counties of Alabama.<sup>19</sup>

Men from the piedmont region of South Carolina also had two routes open to them. They could take the fall-line road through Columbia or the piedmont road through Greenville and reach the Alabama basin by the Federal Road. But if they wished to reach the Tennessee Valley, they could pass northward from Greenville, through Saluda Gap in the Blue Ridge where it borders North and South Carolina, then to the site of Asheville, and along the course of the French Broad to Knoxville, and thence to Huntsville.<sup>20</sup> Immigrants came by both of these routes, and, appearing to have avoided the settlements of those who preceded them in the Tennessee Valley and in the Alabama River basin, the majority of them passed on from both directions into the central hilly region or the basin of the Black Warrior and upper Tombigbee Rivers.

---

<sup>16</sup> Phillips, *Transportation in the Eastern Cotton Belt*, 68-69.

<sup>17</sup> Betts, *History of Huntsville*, 21.

<sup>18</sup> Land Office, *Record of Proclamations*, May 24, 1807.

<sup>19</sup> The account given here of the distribution of population in Alabama agrees, in general, with the available statements concerning different localities; and with the general statements to be found in Garrett's *Reminiscences*, 35; and in the Meek MS. on the *Early Settlement of Alabama*. See also Hamilton, *Colonial Mobile*, 456-457; and Smith, *Pickens County*, 37-39.

<sup>20</sup> Phillips, *Transportation in the Eastern Cotton Belt*, 63.



Men coming from North Carolina could have taken the route along the French Broad to Knoxville, and thence to Huntsville, but since this road traversed only the mountainous western region of the State, it is probable that most of the immigrants from North Carolina found the highway from Raleigh through Columbus and Augusta to the Federal Road more convenient. These men, like those from South Carolina, found the central region of Alabama most attractive.

The Virginians who came from the Valley followed their highway through Cumberland Gap and down the Holston to Knoxville, thence gaining access to the Tennessee Valley. Some of these passed on down to the Black Warrior and Tombigbee Valleys. For Virginians from the piedmont region, it was more convenient to take one of the eastern roads leading to southern Alabama, whence they could make their way into the Tombigbee-Warrior region if they so desired.

Of course the Tennessee Valley was most easily accessible to the men just over the line, and consequently Tennesseans had a predominance in this section. Some bought lands in the Valley, while others passed beyond into the hilly region and became squatters upon the National domain, for the lands in the valley were put upon the market principally in 1818, but those south of it were not sold for several years afterward. Here back-woods communities were established in the isolated valleys, and frontier conditions of life prevailed for a long time.

The principal route of travel connecting the Tennessee Valley with the Alabama-Tombigbee region was a road passing southwestward from Huntsville through Jones Valley to the town of Tuscaloosa, which grew up at the head of boat navigation upon the Black Warrior. It was along this route that the principal settlements were made in the central hilly region. At first the Tennesseans predominated here, but South Carolinians soon came in so numerously as to outnumber the Tennesseans in some localities. The struggle for supremacy between these elements in Blount and Jefferson Counties provoked open hostilities before it was settled. Finally, the Tennesseans came to predominate in Blount, while the South Carolinians had the majority in Jefferson County.<sup>21</sup>

As in this case, most communities had their local color, and the state whence one came was always a matter of signifi-

---

<sup>21</sup> Meek MS. *Early Settlement of Alabama*; Powell, *History of Blount County*, 37.

cance. In the Tombigbee-Warrior region, North Carolinians, South Carolinians, and Virginians mingled in varying proportions, but together formed a predominating population-element which had its own characteristics. As late as 1856, Greene County, at the conjunction of the Black Warrior with the Tombigbee, had a population of 438 native South Carolinians, 357 Alabamians, 348 North Carolinians, 92 Georgians, 45 Tennesseans, 24 Kentuckians, 12 men from Connecticut, 37 from Ireland, and 10 from Germany.<sup>22</sup>

The presence of a small number of foreigners is characteristic of the early period, and so is the presence of New Englanders. The cosmopolitan population was confined to the trading towns where the merchants were largely Yankees.<sup>23</sup> This was especially true of Mobile, where the transient population was turbulent and varied. A community of Germans was established at Dutch Bend on the Alabama River;<sup>24</sup> and Demopolis, on the Tombigbee, was founded by a band of Napoleonic refugees. However, such segregated community-building was not characteristic.

Finally, in spite of the mixture which was produced by the flow of immigration into Alabama, three areas can be distinguished which show peculiarities due partly to the predominant element in the population. In the Tennessee Valley the preponderance of Tennesseans gave a strongly democratic flavor to political ideas; in the Tombigbee-Warrior region, the Carolina-Virginia predominance seems to be indicated by a flavor of conservatism in things political; while the influence of Georgia politics is clearly discernible in Montgomery County. However, there are other factors which played a more important part in shaping opinions and politics than did the origin of the population, the effect of which, indeed, is often entirely obliterated.

---

<sup>22</sup> Snedecor, *Directory of Greene County*, 1856.

<sup>23</sup> *Alabama Republican*, Aug. 15, 1823, Extract of a letter to the Editor of the Newburyport (Mass.) *Herald*, dated Claiborne (A), March, 1823; Jackson Papers, Col. Will King to A. Jackson, Nov. 23, 1821.

<sup>24</sup> Blue MS., I, *Autauga County*, 4.

## CHAPTER IV.

---

### THE DIVISION OF THE TERRITORY

The question of the division of the Territory came up as early as 1803, for in that year the Tombigbee settlers sent a petition to Congress praying that they might be separated from the community upon the Mississippi.<sup>1</sup> The petition was renewed in 1809, the petitioners stating that they had a government in name only, that they were entirely neglected by the authorities of the Territory.<sup>2</sup> This attitude was perfectly natural, for the Tombigbee settlement was widely separated from that about Natchez, and, being in a minority in the legislature, it was unable to make its needs felt at so great a distance.

In 1809 Madison County was opened up in the Tennessee Valley; and in 1810 West Florida was annexed to the United States. This country was claimed as a part of the Louisiana purchase, but the title was most flimsy. It seemed, however, that war with England was approaching, and since French and English armies were fighting over the throne of Spain, West Florida in Spanish hands was a menace to our southern coast. England might use the Gulf ports as a base through which to treat with hostile Indians, and thereby the situation of our frontier settlements in this region was rendered critical in case of hostilities. A declaration of independence by a band of men, largely Americans, who had migrated into West Florida, gave Madison the excuse which he eagerly accepted as a way out of the difficult situation. A proclamation declared the Spanish province annexed to the United States, and General Claiborne occupied the country as far east as the Pearl River.<sup>3</sup>

The newly-acquired region was joined to the Territory of Orleans for administrative purposes. In 1811, this territory became the State of Louisiana, and more than four hundred West Floridians petitioned Congress that their district might be annexed to Mississippi Territory.<sup>4</sup> Until this time the Mississippi delegate had been working in Congress for admission to the Union without division, but here the intersectional

---

<sup>1</sup> Annals of Congress, 8 Cong., 1 Sess., 624.

<sup>2</sup> Ibid., 11 Cong., Pt. 1, 695.

<sup>3</sup> McMaster, *History of the United States*, III, 371, et seq.

<sup>4</sup> American State Papers, Miscellaneous, II, 155.

rivalry in Congress came into play. The House, where the North was in the majority, showed itself, even at this early date, willing to provide for the admission of the undivided Territory. But in the Senate the South, having lost its hold upon the House, was trying to maintain an equality. This could be accomplished only by the admission of a slave state every time a free state was admitted, and from this point of view, it was desirable to carve as many states as possible from southern territory. Consequently, the Senate insisted that Mississippi Territory be divided.

The combination of this situation with the West Florida annexation suggested a new idea to Poindexter, the Territorial delegate; and he brought forward a proposition for division by a line running due east from the mouth of the Yazoo. The southern portion, with West Florida annexed, was to be admitted to the Union at once, while the northern portion was to be given a territorial government.<sup>5</sup>

This move called down a storm upon the author's head. The Madison County inhabitants would, it is true, have been glad enough to see the plan carried through, leaving them with a territorial government to administer alone.<sup>6</sup> But to be tied permanently to the Mississippi River region with its separate interests was the last thing desired by the Tombigbee settlers. Opposition was quickly expressed in this quarter, and it was seconded by many in the Natchez region who felt that the frontier settlements were yet too young to support the burden of state government.<sup>7</sup>

There were other reasons, too, why many opposed the institution of state government at this time. In 1795 the legislature of Georgia had made large grants of land in the Mississippi country to certain speculating companies which came to be known as the "Yazoo" land companies. Extensive graft in connection with the deal having been exposed, the next session of the legislature repealed the grants and deprived the companies of their charters. This was supposed to have ended the matter, but in 1809 the Federal Supreme Court, in the case of *Fletcher vs. Peck*, declared that the repeal of the grants was a breach of contract, and therefore for-

<sup>5</sup> American State Papers, Misc., II, 163-164.

<sup>6</sup> Mississippi Transcripts, J. W. Walker to Geo. Poindexter, Dec. 23, 1812.

<sup>7</sup> Claiborne, *Mississippi*, 350; Transcripts, Cowles Mead to Geo. Poindexter, Dec. 23, 1812.

bidden by the Constitution. The claimants under the companies at once appealed to Congress for relief, but John Randolph, of Roanoke, made the case his pet antipathy and prevented anything being done until 1814.

When, in 1802, Georgia ceded to the United States her claim to the Mississippi region, it was provided in the agreement that all completed British and Spanish grants should hold good. Actual settlers were to be provided for, and all claims arising under the act of Georgia which established Bourbon County in the ceded region were to be validated. In addition to this, five million acres of land were set aside for the satisfaction of any other claimants under acts of Georgia, to be appropriated as Congress might see fit. The Yazoo claimants were the chief possible beneficiaries under this provision, but it was long before the matter was put at rest.<sup>8</sup>

In 1811 many titles to land in Mississippi Territory were threatened by the Yazoo claimants, and many others were threatened by a conflict between British and Spanish grants. A number of actual settlers held tracts under Spanish grants which had been superseded by grants under the British administration. These British claims had never been established, but the matter was subject to judicial determination, and it caused uneasiness to many who lived upon the land.

Because of this uncertainty of land tenure, courts of Federal jurisdiction were not established in Mississippi Territory, and though the delegate in Congress pressed for a compromise of the British claims, nothing was accomplished up to the time when Mississippi was admitted to the Union. It was the dread of Federal courts, therefore, and of British and Yazoo claimants which caused many men to oppose admission to statehood in 1812.<sup>9</sup>

But in spite of all these objections, an act providing for the admission of the undivided Territory was passed by the House and sent up to the Senate in this year. The Senate committee to which the bill was referred advised division along the line of the Tombigbee River, and proposed that the question lie over until the next session.<sup>10</sup>

Georgia, in granting her claim to the United States, had provided that the whole territory be admitted into the Union.

<sup>8</sup> Treat, *The National Land System*, 355-364.

<sup>9</sup> *Washington Republican*, Sept. 9, 1815, March 13, and April 17, 1816, April 9, 1817.

<sup>10</sup> American State Papers, Misc., II, 182.

as a single state as soon as its population should amount to sixty thousand whites. In view of the action of the Senate, Poindexter now brought in a resolution that Congress secure Georgia's permission to a division of the Territory.<sup>11</sup> The resolution passed both Houses, and within the year Georgia's acquiescence was reported to the Senate. But the War of 1812 coming on at this time, its depression was added to the arguments of those who wished to postpone the question of statehood. Thus, from 1812 to 1815 the matter was not agitated to any great extent.

When the question of admission was again brought before Congress in 1815, two things had happened to change the situation. In 1812 so much of West Florida as lay between the Pearl and Perdido Rivers was added to the Territory, and in 1814 Congress settled the Yazoo Claims by appropriating five million dollars in scrip to be distributed to the claimants under the several companies and redeemed in payment on the first lands to be sold in Mississippi Territory.

Though the British claims still threatened many of the settlers, the prospects of peace and immigration now caused the Territorial delegate, Dr. Lattimore, who had opposed admission when first elected in 1813, to come out in favor of the admission without division.<sup>12</sup> Petitions to that effect were sent up by the legislature, and in 1816 the House passed a bill framed in accordance with that policy. But the attitude of the Senate had not changed. The committee to which the bill was referred again proposed division by a north and south line, and the question of admission was again postponed.<sup>13</sup>

Lattimore now saw the uselessness of working along the old line, and expressed himself as willing to accept division if Congress insisted upon it.<sup>14</sup> But, in the meantime, the situation had changed at home. The extensive Creek cession of 1814 and the smaller cessions from the Cherokees, Chickasaws, and Choctaws in 1816 had opened up a great stretch of country comprising most of the eastern part of the Territory. The settlers upon the Tombigbee now expected to see their river basin become, in a short while, more populous than the region bordering the Mississippi. They accordingly antici-

---

<sup>11</sup> Annals of Congress, 12 Cong., 1 Sess., II, 1480.

<sup>12</sup> *Washington Republican*, April 5 and April 26, 1815.

<sup>13</sup> Annals of Congress, 14 Cong., 1 Sess., 352; *Washington Republican*, April 16, 1817.

<sup>14</sup> *Washington Republican*, May 22 and May 29, 1816.

pated control of the legislature and the removal of the capital to St. Stephens.

Such a prospect was by no means pleasing to the men who lived between Pearl River and the Mississippi. So greatly did they dread the threatened preponderance of the eastern section of the Territory that they gave up their old enthusiasm for a single state and supported Lattimore on the question of division. This, they now believed, was the only way to keep their capital near the banks of the Mississippi.

On the other hand, the Tombigbee settlers now appeared much alarmed at the prospect of division. Meetings were held in several places, and the counties were urged to send delegates to assemble in convention at Ford's on Pearl River. Here a gathering of delegates took place in October, but Madison and the counties west of the Pearl were not represented. Resolutions opposing division were drawn up and Judge Harry Toulmin was sent to Washington to present the memorial of the convention, and to work for its cause when the matter should be brought up again.<sup>15</sup>

When Congress assembled in December, the House committee to which the Mississippi question was referred expressed itself as being in favor of a division of the Territory, with immediate admission of the western portion and a territorial government for the eastern half. The agitated question was as to the demarcation. Lattimore proposed a line running due north from the Gulf to the northwest corner of Washington County, then following the Choctaw boundary to the Tombigbee. Toulmin wished a line that would give Wayne, Greene, and Jackson Counties to the eastern government, and some attempt was made to fix upon the Pascagoula as the boundary. The counties in dispute were much nearer the Tombigbee than they were to the Mississippi, and it was argued that it would be an unnecessary inconvenience to their inhabitants to have to look to a capital upon the great River, when St. Stephens was so much closer.<sup>16</sup> In the end, Lattimore was more successful than Toulmin and, though giving some ground, he came near to having his way. The line was fixed so as to run due north from the Gulf to the northwest corner of Washington County, thence directly to the point where Bear Creek

<sup>15</sup> *Washington Republican*, Nov. 13, 1816; Jackson Papers, James Titus to Andrew Jackson, Dec. 5, 1816.

<sup>16</sup> Darby, *Immigrant's Guide*, 107-113; *Washington Republican*, Jan. 22, Feb. 26, March 5, 1817.

flows into the Tennessee, then along the course of the river to the Tennessee line.

It will be noticed that the present boundary does not run due north from the Gulf, but slightly northwest instead. This is because it was found that the line, as originally established, encroached slightly upon Wayne, Greene, and Jackson Counties. In order to remedy this, the Alabama enabling act of 1819 changed it so as to make it run southeastward from the northwest corner of Washington County and to strike the Gulf at a point ten miles east of the mouth of the Pascagoula.<sup>17</sup>

The act establishing Alabama Territory was approved March 3, 1817.<sup>18</sup> All laws applying to the old Mississippi Territory were to remain in force until they might be changed. Officials holding places under the old government for eastern districts were to retain their positions until they should be replaced, and William Wyatt Bibb, of Georgia, was appointed Governor.

Bibb had just previously resigned his seat in the United States Senate because his vote for a bill increasing the salaries of Senators aroused a storm of indignation at home. His colleague, Charles Tait, was under the same condemnation, but, urged by John W. Walker, of Huntsville, he remained until the end of his term and saw Alabama safely admitted to the Union. Then, retiring from public life in Georgia, he purchased a plantation upon the Alabama and moved into the new state.<sup>19</sup> It was Senator Tait, who, in 1802, had notified the Senate of Georgia's consent to a division of Mississippi Territory and who piloted through that body the final bill which provided for division in 1817. Both Tait and Bibb were staunch friends of William H. Crawford, of Georgia, Secretary of the Treasury, and it was likely through his influence that the latter was appointed Governor of Alabama Territory.

Such members as had represented eastern districts in the legislature of Mississippi Territory were empowered to meet at St. Stephens to set the new government in motion. There on January 19, 1818, the first session was held.

St. Stephens stood at the head of schooner navigation on the Tombigbee. In 1811 it consisted of three houses; four

---

<sup>17</sup> Statutes at Large, III, 490.

<sup>18</sup> Ibid., III, 371-372.

<sup>19</sup> Tompkins, *Charles Tait*, 12-16; Tait Papers, J. W. Walker to C. Tait, Jan. 18, 1817.



years later it boasted of nine; and in 1816 the number had grown to forty.<sup>20</sup> In two rooms in Douglas Hotel, hired for the purpose, the legislature met.<sup>21</sup> The House consisted of about thirteen members who elected Gabriel Moore their speaker. The Council had but one member, James Titus, who had been president of the old Council. Not to be abashed by the situation, he convened with all due ceremony, dispatched business, and adjourned from day to day.<sup>22</sup>

In his message, the Governor recommended the promotion of education and internal improvements, but added that the latter object could hardly be accomplished without the aid of the Federal Government. Accordingly, a memorial asking for assistance in this matter was drawn up by the legislature and sent to Washington. The legislation accomplished at this session included the establishment of new counties; the incorporation of a steamboat company, an academy, and a bank at St. Stephens; and the repeal of the law fixing a maximum rate of interest which could be charged on loans. Thereafter, any percentage agreed upon between the contracting parties and stated in writing would be legal. Six men were nominated from whom the President was to select three for the Executive Council, and a commission was appointed to report to the next session of the legislature on a favorable site for the permanent seat of the Territorial Government.<sup>23</sup>

It was during the territorial period of Alabama that the Seminole War broke out upon the Florida frontier. Several white settlers were killed by the restive Indians and militia was rushed to the seat of disturbance. Though troops were stationed at several points in Alabama, and a certain amount of fighting took place within her borders, the struggle went on primarily in Florida. The storm stirred up by Jackson's unauthorized attack upon Pensacola and by the hanging of Arbuthnot and Ambrister belong to National rather than to State history.

Alabama was not greatly affected by these events and the tide of immigration moved on undisturbed. Among those who came in about this time was a party of Frenchmen, supporters of Napoleon, fleeing from the Bourbons who had been

---

<sup>20</sup> Jackson Papers, A. P. Hayne to Andrew Jackson, Nov. 27, 1816.

<sup>21</sup> Meek MS., *The Alabama Territory*.

<sup>22</sup> Pickett, *History of Alabama*, 615; Monette, *History of Mississippi Valley*, 446-447.

<sup>23</sup> Pickett, *History of Alabama*, 615-617

returned to power. They had moved to America in a body and formed an association with headquarters at Philadelphia. Inquiring for land where the vine and the olive might be grown, their attention had been directed to Alabama. At their request, Congress agreed to sell two townships of land at the confluence of the Black Warrior and the Tombigbee. Here a town was laid out and a settlement established. A number of Napoleon's famous generals, including Grouchy, Desnoettes, Clausel, and l'Allemand, were concerned in the enterprise. Log cabins and agriculture were less familiar to them than the sword, and the vine and olive did not flourish upon the Tombigbee. Though the town of Demopolis owes its beginning to these refugees, most of them finally gave up the attempted settlement. Some returned to their native land when conditions made that possible, others took up their abode among the native population.<sup>24</sup>

---

<sup>24</sup> J. S. Reeves, *The Napoleonic Exiles in Johns Hopkins University Studies*, XXIII, 525-656.

## CHAPTER V.

---

### ALABAMA BECOMES A STATE.

So rapid had been the growth of population in Alabama during 1817 and 1818 that, when the second session of the legislature met at St. Stephens in November of the latter year, transition to statehood was expected within a short while. Preparations for this event consequently absorbed the attention of the assembly.

A petition to Congress praying that the Territory might be admitted to the Union as a state was drawn up by the legislature and sent by John W. Walker, the speaker of the House, to his friend, Senator Tait, of Georgia,<sup>1</sup> who presented it to the Senate. But the matter was not allowed to rest here. A census of the Territory had been taken, and the legislature proceeded to apportion the representatives for the constitutional convention. On this question considerable difficulty arose. Madison was the most populous county in the Territory and the members from the southern counties attempted to reduce the representation of the Tennessee Valley region by providing that no county could have more than a given number of seats in the convention. This was strongly opposed by members from the northern counties and they finally carried their point, securing a proportional representation. But in order to accomplish this it became necessary for them to accept a rider to the apportionment bill providing for the location of the seat of government in the southern part of the Territory.<sup>2</sup>

As was stated in the last chapter, the first session of the Territorial legislature appointed a committee which was to report on a suitable site for the seat of government. At the second session, Governor Bibb, who was on the committee and seems to have taken the entire responsibility of the choice upon himself, reported in favor of locating the capital at the junction of the Cahawba and Alabama Rivers.<sup>3</sup> This

---

<sup>1</sup> Tait Papers, J. W. Walker to C. Tait, Nov. 11, 1818.

<sup>2</sup> Tait Papers, J. W. Walker to C. Tait, Nov. 9, 1818, and Nov. 15, 1818.

<sup>3</sup> Tait Papers, W. W. Bibb to C. Tait, Sept. 19, 1818.

was the location forced upon the northern members by means of the rider.

The place selected, while convenient for all those who lived on the rivers of southern Alabama, was quite out of communication with the Tennessee Valley, and naturally was opposed by the men from that section. In giving their consent to the bill which established this location, the representatives from the northern counties were making a substantial concession, but, by way of compensation, they secured a provision that Huntsville should be the temporary seat of government until a town could be laid out and buildings erected at Cahawba.

Walker kept Tait posted on all these proceedings. He sent him a copy of the apportionment bill, stating that the Senate was expected to distribute the seats in the constitutional convention accordingly, and that Huntsville should be the place of meeting.<sup>4</sup> John Crowell had been sent to Washington as Territorial delegate, but his finger is to be seen in none of these transactions. Indeed, Walker wrote to Tait that he did not hold a very high opinion of the delegate,<sup>5</sup> and there is evidence to show that Crowell, in so far as he was able to bring any weight to bear, opposed the plans of Walker and Tait.<sup>6</sup> However, the Senator from Georgia succeeded in getting his enabling act through as desired, and it was signed on March 2, 1819.<sup>7</sup> The convention was to meet in Huntsville on the first Monday in July, Madison County securing eight delegates against four for the next largest county. Provision was made for granting to the new State the sixteenth section of land in each township for the use of schools; all salt springs within her borders; three per cent. of the proceeds of all sales of public lands within the State to be applied in the construction of roads; two townships for the use of a seminary of learning; and 1620 acres at the junction of the Cahawba and Alabama Rivers where the seat of government was to be laid out.

Among the men elected to the convention were some who had had experience in the public affairs of the states from

<sup>4</sup> Tait Papers, J. W. Walker to C. Tait, Nov. (?), 1818.

<sup>5</sup> Ibid., J. W. Walker to C. Tait, Feb. 8, 1819.

<sup>6</sup> Huntsville *Republican*, Feb. 6, 1819. The editor states that Mr. Crowell said that he remonstrated before a Congressional Committee in regard to the admission of Alabama, and that this remonstrance was likely against the rule of representation for the Constitutional Convention as adopted by the Alabama Legislature.

<sup>7</sup> Statutes at Large, III, 489-492.

which they came. Three former Congressmen and two supreme court judges from North Carolina sat in the body along with a number of others who had seen less conspicuous public service.<sup>8</sup> Nor was it considered incongruous that Sam Dale, the most notable pioneer and Indian fighter of the Alabama country, should sit among them. On the whole, the members seem to have been selected quietly and with the intention of securing the best available men. From among their number six governors, six state supreme court judges, and six United States Senators were later selected.<sup>9</sup>

The convention assembled at Huntsville on July 5, 1819, and John W. Walker was elected to preside. A committee of fifteen was instructed to draw up and submit a frame of government; no journal was kept of the proceedings of this committee. The instrument of government which was prepared was accepted by the convention with practically no amendments, so that we know very little concerning the process by which the constitution was framed.<sup>10</sup> It was modeled largely after that of Mississippi and the striking feature is that it made the legislature superior to the other branches of government. The Governor's vote could be over-ridden by a majority of those elected to each House of the legislature, and all State judges were elected by a joint vote of that body. These judges held office during good behaviour, but could be removed on an address to the Governor adopted by a two-thirds vote of the legislature. The heads of the executive departments,—the Secretary of State, the Treasurer and Comptroller, the Attorney General,—were elected by a joint vote of the general assembly, it being the duty of the first of these to keep a record of the acts of the Governor and to lay the same before the assembly.

The social and political temper of the convention may be judged from the constitutional provisions in regard to suffrage and representation. All white, adult males who were citizens of the United States and who had resided for a year in the State were given the right to vote. Representation, both in the Senate and in the House, was to be apportioned according to the white population, nor was there any property qualification for representatives. Slaves were to be grant-

<sup>8</sup> Tompkins, *Charles Tait*, 12-16; Tait Papers, J. W. Walker to C. Tait, Jan. 18, 1817.

<sup>9</sup> Thomas, *Birth of the Constitution of Alabama*, 4-5.

<sup>10</sup> Journal of the Constitutional Convention of 1819.

ed trial by jury in cases more serious than petty larceny, and in case of personal injury to a slave, the offending party should be punished just as though the person injured had been a white man. The legislature was given no power to emancipate slaves without the consent of their owners; but owners might secure the emancipation of their slaves, and the legislature might prohibit the bringing of slaves into the State as merchandise.

The constitution provided that a State bank might be established with as many branches as the legislature might direct, but no branch was to be established nor bank charter renewed except by a two-thirds vote of each House, nor could more than one branch be established or bank charter renewed at any one session of the general assembly. It was also provided that the banks already existing might become branches of the State bank by agreement between them and the assembly, in which case, however, they were bound by the same rules as applied to other branches. And in all such banks and branches, it was necessary that two-fifths of the stock and a proportional representation in the directory be reserved to the State.<sup>11</sup>

It was provided that the first session of the general assembly should meet at Huntsville, and after that it was to meet at Cahawba until 1825. The first session which should meet in that year would have power, without the consent of the Governor, to designate a permanent seat of government, but if this were not done, the seat was to remain permanently at Cahawba.

The general assembly might, by a two-thirds vote of each House, propose amendments to the constitution. These had to be published three months before the next general election of representatives; and if a majority of votes were cast in favor, the next session of the assembly might incorporate them into the constitution by a two-thirds vote of each House. Thus the initiative as well as the final action in changing the constitution was in the hands of the legislature.

This instrument of government was, judged by the standards of the time, liberal. In the older states, restricted suffrage, discrimination between religious denominations, unequal representation, and imprisonment for debt, were still common. In Alabama, imprisonment for debt was to be for-

---

<sup>11</sup> Constitution of Alabama, 1819.

bidden, slaves were to be treated as liberally as circumstances seemed to warrant, nor was any interest or section to be given special weight in the councils of the State. It is significant that the slave holder was given no advantage over the non-slave holder in the matter of suffrage and representation.

All this looks like pioneer democracy as it came to be understood under Andrew Jackson. But there was a difference. Manhood suffrage meant a government by the people, but once they had voted, their power passed to a remarkable degree into the hands of their representatives. The legislature controlled the executive and the judiciary and dominated in the matter of constitutional amendment. Pure Jacksonian democracy would not have consented to a bench elected by the legislature and holding office during good behaviour. Though the government was framed along liberal lines, the conservative element was strongly marked. Instead of reserving as much power as possible to the hands of the people, it was placed in the hands of those whom the people should choose to represent them.

The convention made provision for the election of representatives and officials under the new government, and the constitution went into effect without submission to the people.<sup>12</sup> It served Alabama until the War of Secession with but three amendments.

In the selection of officials, the contest for the governorship and for the Federal judgeship are of especial interest in that they foreshadow political alignments that were of more than temporary importance. Bibb, the Territorial governor, was at first the only candidate for the governorship. Later Marmaduke Williams, of Tuscaloosa, came out against him. Bibb lived in the southern section of Alabama and his choice of Cahawba as the seat of government had provoked strong opposition in the northern section.<sup>13</sup> Of course, there was no chance of locating the capital in the Tennessee Valley, but Tuscaloosa was accessible to that section by way of the Jones Valley Route. This town, though within a few miles of the Mississippi line, was also fairly easy of access from the southern part of Alabama, because of its situation on navigable water and on the thoroughfare between the two sections of the State. The Tennessee Valley region united with the Black Warrior and upper Tombigbee regions in support of

---

<sup>12</sup> Constitution of 1819, Schedule, section 7.

<sup>13</sup> Tait Papers, W. W. Bibb to C. Tait, Sept. 19, 1818.

this place as the logical seat of government, and Williams was fitted to express this sentiment. Bibb was the stronger candidate, however, and his influence with the National government would likely prove of much use to the new State. He was supported by conservative men and carried two counties in the Tennessee Valley, but, aside from this, the line which separates the waters of the Black Warrior and Tombigbee from the waters of the Alabama was the line which separated the supporters of Bibb from those of Williams.<sup>14</sup> The election was won by Bibb.

The first general assembly of the State met at Huntsville in October, and one of its most important duties was to elect the two United States Senators. There was an understanding that one was to come from the south and one from the north, each section being ready to vote for the candidate put forward by the other. The choice of the Tennessee Valley easily fell upon John W. Walker, nor did it take the Alabama and Tombigbee section long to decide on William R. King.<sup>15</sup> This gentleman had represented North Carolina in Congress during those exciting days when the second war with England was decided upon, and he had been of the "war hawks." He had later served as secretary of legation to William Pinckney at Naples and St. Petersburg, and a long political career now awaited him in Alabama.<sup>16</sup>

Because of the agreement between the two sections, the choice of the Senators passed off quietly enough in the legislature, but there was commotion below the surface. Tait, after his valuable services to Alabama in the United States Senate, had returned to private life and taken up his residence in the southern part of the new State. It was not natural that he should be passed over in the matter of political preferment, and he had at least one friend who did not intend that he should be overlooked. That friend was William H. Crawford, Secretary of the Treasury. Crawford and Tait had become fast friends while teaching together in Augusta, and they later came to be political allies.

The Secretary was anxious for Tait to be sent to the Senate from Alabama,<sup>17</sup> and Tait would not have objected. But Walker and his friends in the north could not further this am-

<sup>14</sup> House Journal, 1819, 37.

<sup>15</sup> Tait Papers, J. W. Walker to C. Tait, Aug. 7, 1819.

<sup>16</sup> Pickett, *History of Alabama*, 641-647.

<sup>17</sup> Tait Papers, W. H. Crawford to C. Tait, Nov. 7, 1819.



bition, for the south was choosing its own candidate, and it chose King. Tait indicated that his second choice would be for the Federal judgeship in Alabama,<sup>18</sup> but there was another candidate for this place also. Toulmin had been Federal judge for Alabama Territory and it was natural that he should expect to retain his place when Alabama became a state. William Crawford, of Alabama, had applied to Governor Bibb for the appointment, and Bibb had recommended him to the Secretary of the Treasury; but when the Alabama Crawford heard that Tait wanted the position, he withdrew his request.<sup>19</sup> Bibb then recommended Tait to the Secretary,<sup>20</sup> and by this time Walker was in Washington and able to help his friend. He went to the President with the matter, and the appointment was easily put through, Monroe answering a letter from Toulmin to the effect that he could do nothing for him.<sup>21</sup>

Crawford was in control of the patronage of Alabama and put his friends into office wherever he could. He even offered a land office receivership to King in order to get him out of the way of Tait's senatorial ambitions. This situation naturally aroused the antagonism of those who sought office in vain, and tended to unite all elements against the men from Georgia who were strongest numerically in the neighborhood of Montgomery County, but who constituted a powerful minority in Huntsville and other towns. Denunciation of the "Georgia faction" became common, and the Georgia men, seeing the danger in this, did what they could to allay it, even securing the appointment of some outsiders to office.<sup>22</sup> But here was a political situation which cast a long shadow down the early history of Alabama.

During the first session of the general assembly, there occurred another event which will serve to complete the political picture of Alabama in 1819. General Jackson came to Huntsville with his horses to take part in some racing. Such an occasion could not be passed over in silence and the legislature took the opportunity to celebrate.<sup>23</sup> A resolution admitting the General within the bar of both Houses was passed,

<sup>18</sup> Walker Papers, H. Toulmin to J. W. Walker, Feb. 21, 1819.

<sup>19</sup> Walker Papers, C. Tait to J. W. Walker, Nov. 19, 1819.

<sup>20</sup> Tait Papers, W. H. Crawford to C. Tait, Nov. 29, 1819.

<sup>21</sup> Ibid., J. W. Walker to C. Tait, Dec. 20, 1819.

<sup>22</sup> Walker Papers, C. Tait to J. W. Walker, Oct. 9, 1819; Tait Papers, W. H. Crawford to C. Tait, Nov. 7, 1819, and Nov. 29, 1819.

<sup>23</sup> Pickett, *History of Alabama*, 661-662.

and another approving his course in the Seminole War was introduced. This latter resolution read as follows: "And be it further resolved that this General Assembly do highly disapprove of the late attempt made by some members of the Congress of the United States at the last session to censure the military course of this inestimable officer from motives (as we believe) other than patriotic." It was carried in the House by a majority of twenty-seven to twenty-one; five counties, two in the north and three in the south, going against it, ten well scattered counties voting in favor of it and six splitting their vote equally.<sup>24</sup>

This, on the surface, does not appear to be a very decisive affair. But James G. Birney, who lived in Huntsville in the days before he became a leader of abolitionists and who was now a member of the assembly, signed his political death warrant in Alabama by opposing Jackson on this occasion.<sup>25</sup> The same is true of most of the others who took a similar course. Jacksonism had not been an issue when the assembly was elected and many got seats whose opinions would have debarred them at a later time.

But such men as Birney had strong company. Governor Bibb wrote to Tait concerning Jackson's attack on Pensacola in the Seminole War as follows:

"Government has done right respecting the occupation of Florida, except in apologies for Genl. Jackson. In that they have erred (according to my judgment) most egregiously. They will gain nothing by it with his friends, and lose much with the thinking part of the nation. Not a moment should have been lost in arresting the Genl. and thereby showing a just regard to the preservation of our constitution. No man should be permitted in a free country to usurp the whole powers of the whole government and to thwart with contempt all authority except that of his own will."<sup>26</sup>

Walker showed a different spirit. He wrote to Tait:

"I fear we think too much alike about some things touching the Seminole War. I would to God they were undone. He is a great man with great defects. One cannot help loving or blaming him. But I follow your exemplary course—

---

<sup>24</sup> House Journal, 1819, 45.

<sup>25</sup> Birney's *Birney*, 40.

<sup>26</sup> Tait Papers, W. W. Bibb to C. Tait, Sept. 19, 1818.

<sup>27</sup> *Ibid.*, J. W. Walker to C. Tait, Jan. 19, 1819.

and perhaps go further: when I cannot praise I try to be silent."<sup>27</sup>

As for the opinion of the more eminent friends of these Alabama leaders, Crawford expressed his very clearly in a letter to Governor Holmes, of the Mississippi Territory, in 1818. He said: "Persons so regardless of our laws as those engaged in the expedition against Pensacola deserve their severest penalties, and you may rely upon my exertions to bring them to punishment."<sup>28</sup>

Calhoun, Crawford's colleague in the Cabinet as Secretary of War, wrote to Tait palliating the conduct of Jackson and upholding the course of the Administration.<sup>29</sup>

But there was evidently trouble ahead in Alabama for those who did not uphold "The General."

---

<sup>28</sup> Mississippi Transcripts, W. H. Crawford to Gov. Holmes, April 22, 1818.

<sup>29</sup> Tait Papers, J. C. Calhoun to C. Tait, Sept. 5, 1818.

## CHAPTER VI.

### THE PUBLIC LANDS

As previously stated, when the War of 1812 and the blockade of our coast cut off cotton from its British market, the price fell to a low figure in America, while it rose in England. With the return of peace, this condition was reversed. English mills bought heavily to make up for lost time, and the price went up with a bound, averaging nearly thirty cents a pound for 1816. This situation would hardly have been expected to last, and the next year the market fell off to an average of about twenty-seven cents. At these figures the production of the staple was distinctly profitable, and planters began to move out in large numbers to the new lands in Alabama. But 1818 proved to be an exceptional year. Instead of continuing to fall off, the price of cotton now rose to the unprecedented average of about thirty-four cents a pound.<sup>1</sup> A rush to the western lands resulted and prices ranging from fifty to a hundred dollars an acre were paid for farms lying in a virgin wilderness.

The monetary situation of the country was such as to favor the spirit of speculation that set in. There had been a general suspension of specie payments during the War and the currency of the country had fallen into great disorder. Many of the bank notes that circulated were of uncertain value and much inconvenience was caused by their use. Largely in order to remedy this state of affairs, the second Bank of the United States was chartered in 1816. It was to go into operation early in 1817, and a resolution was passed that the Government would receive only specie-paying paper after February 20th. In order to effect resumption, the banks of issue had to cut down their circulation, but the object was accomplished, and by February specie payment had been restored.<sup>2</sup>

The reduction in the number of notes in circulation which accompanied the resumption of specie payments would naturally have tended to retard speculation; but the temptation

---

<sup>1</sup> *Atlas of American Agriculture*, cotton section, 20.

<sup>2</sup> Dewey, *Financial History of the United States*, 151.

of the western cotton lands was too great to be denied, and means were found to overcome the difficulty. In the first place, the management of the new bank of the United States was reckless, and its notes were turned loose largely in the South<sup>3</sup> to be invested by the speculators. But more important than this, about seventy local banks were founded in Tennessee and Kentucky in 1818.<sup>4</sup> These institutions had troubled careers, but their notes remained good long enough to make the first payment on Government lands.

Yet another resource was open to many of those who wished to purchase land in Alabama. The five million dollars in scrip which had been issued to the Yazoo claimants was redeemable only in payments for lands in the Georgia cession;<sup>5</sup> and since no new Indian concessions had been obtained within Mississippi, the first chance afforded the Yazoo men for redeeming their scrip was at the Alabama sales of 1817 and 1818. The greater part of it was turned in at this time to make the first payments on purchases, and it added much to the frenzy of speculation.

Land sales during this period were made under the act of 1800, as extended and amended in 1803 and 1804.<sup>6</sup> It was provided that the public domain should be surveyed by marking it off into townships six miles square, and the townships subdivided into thirty-six square miles or sections. A quarter-section, or one hundred and sixty acres, was the smallest tract which could be sold.

Having been surveyed, the land was advertised for sale at public auctions which were held at the offices established in the various land districts. Tracts were sold to the highest bidder, and those remaining unsold might be entered privately at the minimum price of two dollars an acre. In either case, one-fourth of the purchase money had to be paid at the time of the sale, and the remaining three-fourths in annual installments of one-fourth each.

The surveys in the Creek cession were begun in 1816,<sup>7</sup> and speculators at once began making investigations. A. P. Hayne made a tour of the lands to be put upon the market and wrote to Andrew Jackson giving a favorable account of

<sup>3</sup> Ibid., 153.

<sup>4</sup> Annals of Congress, 16 Cong., 2 Sess., 233.

<sup>5</sup> Statutes at Large, III, 116-117.

<sup>6</sup> Treat, *The National Land System*, 111-112, 120-121.

<sup>7</sup> Jackson Papers, Thos. Freeman to Andrew Jackson, April 12, 1816.

the rich river and prairie tracts.<sup>8</sup> Jackson wrote to a friend in Washington to inquire as to the price of the Yazoo scrip and found that it had risen from forty to sixty-eight dollars.<sup>9</sup> Companies were formed for participation at the auctions, and Hayne wrote that "speculation in land is superior to Law or Physic."<sup>10</sup>

The first sale took place at Milledgeville, Georgia, in August, 1817; and comprised a tract lying along the headwaters of the Alabama River in the neighborhood of the present city of Montgomery.<sup>11</sup> Only the best river bottom tracts were disposed of at this time, and these were taken up by speculators from various places. The men who had moved into the region were generally too poor to make their way to the place of sale, and they had little hope of being able to compete with the wealthier purchasers.<sup>12</sup> Sales during this year amounted to nearly \$800,000, and the new tracts in the same region which were offered in 1818 brought the sales of that year up to nearly a million dollars.<sup>13</sup> Almost nothing but river bottom lands were sold at Milledgeville during these two years,<sup>14</sup> and there were few actual settlers among the purchasers.

The most coveted bit of land that was disposed of at this time lay within a wide bend of the Alabama River and upon a bluff which formed the opposite bank. The soil in the bend was of the best quality, and the bluff afforded an excellent site for a town. Members of the Bibb family were anxious to purchase here, and so was A. P. Hayne, who wrote to Jackson concerning the matter.<sup>15</sup> A land company, of which William Wyatt Bibb was a member, secured the tracts, and the town of Montgomery was founded upon the bluff in 1819.<sup>16</sup>

Though these sales were the most extensive that had taken place up to that time, they were small in comparison with those which were held in Huntsville in 1818. All the lands lying west of Madison County, on both sides of the Tennessee River, were offered for sale in that year,<sup>17</sup> and the amount

---

<sup>8</sup> Ibid., A. P. Hayne to Andrew Jackson, Nov. 27, 1816.

<sup>9</sup> Ibid., D. Parker to Andrew Jackson, Jan. 6, 1817.

<sup>10</sup> Jackson Papers, A. P. Hayne to Andrew Jackson, Nov. 27, 1816.

<sup>11</sup> L. O. Record of Proclamations, May 24, 1817.

<sup>12</sup> Jackson Papers, A. P. Hayne to Andrew Jackson, Aug. 5, 1817.

<sup>13</sup> American State Papers, Lands, V, 384-385.

<sup>14</sup> Tract Book of Montgomery County, Office of the Secretary of State, Montgomery, Ala.

<sup>15</sup> Jackson Papers, A. P. Hayne to Andrew Jackson, Aug. 5, 1817.

<sup>16</sup> Meek MS., *Early Settlement of Alabama*, 1815-1819.

<sup>17</sup> L. O., Record of Proclamations, Nov. 1, 1817 and March 31, 1818.

sold reached a value of seven million dollars. Out of the sum of about one and a half million which was paid down upon the purchases, over a million was in Yazoo scrip, or "Mississippi stock," as it was called.

A speculating company, composed of men from Virginia, Georgia, Kentucky, and Madison County was formed. Prominent Tennesseans bid against this combine and prices were run up to figures ranging between fifty and a hundred dollars an acre. Average cotton land sold at prices between twenty and thirty dollars.<sup>19</sup>

The excitement caused by the sales was nation-wide. Men came from every part of the country to participate in them. A company was formed in Charleston, South Carolina, for the purpose of buying acreage in Alabama, and Stephen Elliott was sent out to make the purchases.<sup>20</sup> Much swindling went on during the sales. A company of speculators would combine, and, by a show of force, intimidate their competitors and bid off large tracts of desirable land at low prices. They would then sell out at a considerable gain to those who had not been able to compete with them. It is stated on good authority that one such association of swindlers cleared \$1,980 each on a transaction of this kind.<sup>21</sup> The situation became so notorious that the Government authorized its agents to bid against the combinations when they thought it advisable.<sup>22</sup>

No such extent of fine lands was ever again offered for sale in Alabama during a single year, but in 1819 large areas along the Alabama River below Montgomery County were put upon the market. The land office for this district had now been moved from Milledgeville to Cahawba, and the sales here amounted to nearly three million dollars during the year.

By the time the credit system of sales was abolished in 1820, Alabama had, in all, amassed a land debt of eleven million dollars, or more than half the total for the entire Country.<sup>23</sup> And in the meantime the price of cotton had gone down to eighteen cents; the country was in the throes of commercial depression; and the prospect of paying for the lands which

<sup>18</sup> American State Papers, Lands, V, 384-385.

<sup>19</sup> Jackson Papers, Jno. Coffee to Andrew Jackson, Feb. 12, 1818.

<sup>20</sup> Record of Deeds, Dallas County, D, 305.

<sup>21</sup> *Niles' Register*, XVI, 192; *St. Stephens Halcyon*, Oct. 11, 1819; *Alabama Republican*, May 1, 1818.

<sup>22</sup> American State Papers, Lands, V, 378-380, 513.

<sup>23</sup> *Ibid.*, 645.

had been bought at abnormal prices became almost hopeless.

Such a state of affairs prompted Congress to discontinue the policy of credit sales. In 1820 it was provided that half quarter-sections might be sold, that the minimum price should be \$1.25 an acre, and that all payments should be in cash. The system of public auctions followed by private entry was continued.<sup>24</sup>

But something had to be done for those who had already fallen into debt beyond hope of recovery, and this problem was attacked in 1821. It was provided that land which had been purchased but not completely paid for might be relinquished and the sum paid on it applied on the balance due for lands which were retained. In addition to this, the balance due on lands retained was to be reduced by thirty-seven and a half per cent. and an extension of credit to be granted.<sup>25</sup> Large numbers took advantage of this act, and within a year the land debt of Alabama was reduced by half. Those who did not take advantage of it were later given a further chance to do so, and by 1825 the debt had been decreased to about three and a half million dollars.<sup>26</sup>

Yet the consequences of the speculation of 1818 and 1819 were not so easily overcome. The men who relinquished their land under the act of 1821 did not consider that they were giving up their right to it. They continued to live upon and cultivate it, and expected to be able to buy it back some day under favorable arrangements which they looked to Congress to make. Thus the community was injured by the presence of a large number of farmers who were mere tenants by common consent. The unsettled condition of such men was disturbing to the whole system of rural economy. By 1828 about three and a quarter million out of the twenty-four million acres of public lands in Alabama were sold, and nearly half as much had been relinquished.<sup>27</sup> The extent of the evil can be imagined.

In the natural course of events, the relinquished lands would be put on the market again at auction sale, and here the relinquisher would have to compete with all comers for fields that he had owned and cleared and still cultivated. The spirit of the community was in sympathy with the relinquisher.

---

<sup>24</sup> Statutes at Large, III, 566.

<sup>25</sup> Ibid., III, 612-614.

<sup>26</sup> American State Papers, IV, 795.

<sup>27</sup> American State Papers, Lands, V, 513, 800.



It would hardly have been considered honorable to bid against him for lands which were looked on as his by natural right. However, there were many sharpers who made it a business to prey upon those who had made improvements upon lands to which they did not have title. It was their practice to go to the interested party and threaten to bid against him unless he should make terms. An agreement was generally reached, and the settler had to pay the sharper about as much as he paid the Government for his lands.<sup>28</sup>

The same situation was faced by others than the relinquishers. The more desirable areas in the State, accessible to river communication, were the first to be surveyed and sold. Later on, the more inaccessible areas were put on the market. Where men of small means had come into Alabama and settled upon desirable lands in the river regions, they were frequently unable to hold them when they were put up for sale at auction. It became necessary for these people to move out into the back country and start all over again, but the auctioneer in time came to them in their newer homes. Here, however, the situation was different. The speculative period was over after 1819 and lands would no longer bring abnormally high prices. The back country tracts, being relatively inaccessible, would not command prices much above the statutory minimum, even though they were fertile, nor would a man's neighbor bid against him for lands which he had improved. Consequently, the settler in the hill districts would normally have been able to buy his improved land at a price close to \$1.25 an acre had not the sharper attacked him in the same manner in which he attacked the relinquisher.<sup>29</sup> Land offices were established in Tuscaloosa and Conecuh Counties in 1820, and men who had not yet been called upon to prove their titles began to fear that they would lose their homes in the competition of the sales. There is on record the case of a preacher in Conecuh County who was forced by swindlers to pay \$37.50 an acre for the privilege of buying his lands without competition, but the fraud became known to the Government, the sale was canceled, and the preacher was able to buy in his land at the minimum price.<sup>30</sup> Public auctions were more than once suspended because of the operation of swindlers.

---

<sup>28</sup> *Southern Advocate*, May 19, 1826.

<sup>29</sup> Smith, *Pickens County*, 42-44; *Cahawba Press*, Oct. 29, 1821.

<sup>30</sup> Riley, *Conecuh County*, 96.

In order to obviate such difficulties, it was strongly advocated in Alabama that the unsold lands be divided into classes and that each class be given a price according to its grade. Actual settlers were to be allowed to enter their lands at the fixed prices and thus be assured in the tenure of their fields and their homes. This was especially urged in regard to the relinquished lands, and Alabama's representatives in Washington worked for the adoption of the plan by Congress, but nothing came of their efforts.<sup>31</sup> There was adopted, instead, an act which permitted those who had relinquished or forfeited lands to repurchase them at a reduction of thirty-seven and a half per cent. on the original price.<sup>32</sup> This did not meet the situation, and the auction continued to stare the settlers in the face.

---

<sup>31</sup> Alabama Legislature, House Journal, 1825, 96-97; American State Papers, Lands, IV, 529; Ibid., V, 380-382; *Southern Advocate*, April 28, June 23, Sept. 29, Oct. 6, 1826.

<sup>32</sup> Statutes at Large, IV, 158-159.

## CHAPTER VII.

### AGRICULTURE

By 1820 Alabama had attracted a population of over 125,000, black and white, and of these the slaves made up thirty-one per cent. This was about the same proportion which had existed between the races in 1816 when Alabama was still a part of Mississippi Territory and contained but two widely-separated settlements. By 1830 the population had swelled beyond 300,000 and the per cent. of slaves had gradually risen from thirty-one to thirty-eight.<sup>1</sup> So that during this period of rapid immigration and the planting of the cotton kingdom in the lower South, there were about two white men coming in for every slave that entered. If the whites averaged five to the family and the slaves ten to the master, but one family in four could have been of the slave-holding class.

Whereas, during this early period, the population was inclined to spread over the face of the country, there was a striking segregation of the slave population into certain districts. In 1830 there was but one county in the State (Madison) with over 16,000 population, and but seven of the most barren had less than 4,000. The counties which attracted the heaviest population were those of the Tennessee Valley and those of the region of clay ridges which skirts the hilly district of the northeastern part of the State.

On the other hand, the slave population was very largely confined to the counties of the Tennessee Valley and to those lying along the navigable portions of the Alabama and Tombigbee Rivers. The river bottom lands were the most highly prized by the cotton planters because of their great fertility, but these were of limited extent, and recourse had to be had to the ridge lands lying along the courses of the rivers. It is notable that the prairie region, or Black Belt, which came later to be so highly esteemed for cotton culture, was avoided by

<sup>1</sup> In addition to the U. S. Census of 1820 and 1830, we have that taken by the Mississippi Territory in 1816 (*Am. State Papers, Misc.*, II, 408); the census of Alabama Territory taken in 1818 (*Walker Papers*); and those taken by the State of Alabama in 1824 (*Huntsville Democrat*, Nov. 22, 1824), and 1827 (*Huntsville Democrat*, Dec. 14, 1827).

the planters before 1830 because they had not learned how to master the difficulties of the sticky soil.<sup>2</sup> In selecting his site, the planter had to consider communications as well as fertility of soil; and continuity of fields also counted for something. All these factors combined to make the river valleys the slave sections of the State before 1830.

How soon cotton culture came to be an established industry in Alabama cannot be stated with accuracy. The staple is said to have been produced to some extent as early as 1772,<sup>3</sup> and by 1807 it had come largely to supplant indigo in the agriculture of the Tombigbee region.<sup>4</sup> It is fairly clear that the Georgians who came to Madison County in 1809 came for the purpose of planting cotton, and it is stated that the crop of that country in 1816 amounted to ten thousand bales.<sup>5</sup> Certainly by the time of the great immigration in 1817 and 1818 the economic prospects of Alabama must have been clear to practically all who entered. Yet, Darby, in his *Emigrant's Guide* of 1818, states that extensive vineyards would be planted upon the dry slopes of the Alabama if ever anywhere in the United States, and that the olive would find a congenial soil upon the banks of the Alabama, Cahawba, Coosa, and Tallapoosa Rivers.<sup>6</sup> That this view was seriously entertained at that time is proven by the attempt of the ill-fated colony of Napoleonic refugees to bring forth the grapes and olives of southern France on the banks of the Tombigbee in 1817.<sup>7</sup> It was probably their failure which precluded further earnest attempts along that line, but when cotton prospects were gloomy, there were not wanting those who would urge experiments with other crops. Grapes, sugar cane, and small grain were all suggested at different times,<sup>8</sup> and limited experiments were made with each. But Alabama was to have but two predominant systems of agriculture: that of the planter who raised cotton, with corn as his subsidiary crop; and that of the small farmer who raised corn with cotton subsidiary.

---

<sup>2</sup> This view is based partly on charts made from the tract books of Clarke, Montgomery, Dallas, and Perry Counties.

<sup>3</sup> Pickett, *History of Alabama*, 325.

<sup>4</sup> *Ibid.*, 503.

<sup>5</sup> Wyman, *Geographical Sketch of Alabama* in Alabama Historical Society, Transactions, III, 126.

<sup>6</sup> Darby, *Emigrant's Guide*, 33.

<sup>7</sup> See Pickett's *History of Alabama*, Chap. XLV.

<sup>8</sup> *Southern Advocate*, July 1, 1825; *Alabama Journal*, Sept. 15, 1826; *Mobile Register*, Dec. 1, 1827, Jan. 8, 1828, April 15, 1828, May 17, 1828, Oct. 8, 1828; *Southern Agriculturist* (from the Alabama Journal), I, 379.

When the planter with money to invest and slaves to work decided to come out to Alabama, he often made a tour of investigation, or at least wrote to friends in the new country asking for advice as to conditions. He could not afford to take unnecessary chances. He needed to know where good lands were located and what were the chances of buying at a fair price. The first Madison County lands to be disposed of were offered for sale at the Nashville land office, and the first lands sold along the upper Alabama were auctioned at Milledgeville, Georgia. Land offices were later established at Huntsville and Cahawba, in addition to the one which had been put in operation at St. Stephens at an early date, so that all but the very first sales in these districts were made within the State. Yet, it is unreasonable to suppose that many men with a planter's capital at stake would have sold out their old homes and moved westward without first having purchased their land.

Having arrived upon his new estate, it did not take the planter long to establish himself. With plenty of labor, the ground was soon cleared, or the first crop might be planted after the trees had merely been deadened by girdling. A house for the master's family was built of logs, and the routine of plantation life was resumed as well as the crude conditions permitted.<sup>9</sup>

The log house, so typical of a frontier community, was not an ephemeral thing. It remained the standard of domestic architecture in the more isolated sections and was sometimes adhered to from inertia or sentimental reasons by men who could easily have afforded more modern quarters. It was not long, however, before the average planter replaced his log structure with one of boards. The typical Southern "mansion house," with its generous veranda and stately white columns, arose throughout the cotton region. Hodgson, on entering the Montgomery district in 1820, was impressed by the fine appearance of the plantations,<sup>10</sup> and Saxe-Weimar, traversing the same ground six years later, not only speaks in general terms, but comments upon the handsome dwellings.<sup>11</sup>

In general appearance, the homes of the Southwestern planters resembled those of the Virginia colonists. They

<sup>9</sup> See Phillips, *Negro Slavery*, Chap. X, for an account of the westward movement of the cotton planter.

<sup>10</sup> Hodgson, *Letters from North America*, I, 39.

<sup>11</sup> Saxe-Weimar, I, 30-31.

were white, two-storied buildings of classical proportions, with broad verandas and gigantic columns. But a different spirit showed itself in plan and execution. Instead of a well-knit structure with architectural finish, there was a rambling house with a suggestion of unnecessary space. The difference, it would seem, was due primarily to the shaping influence of the log cabin. The simple cabin, consisting of two rooms joined by a wide passage-way, having only a floor below and a roof above, accustomed the pioneer to architecture embodying generous open-air passages. The planter started his new career in such a house, but sometimes amplified it into a dwelling of from four to eight rooms, keeping to the same materials and method of construction throughout. Finally, when he came to put up his frame house, he followed the old lines of internal arrangement. Crossing the veranda with its tall columns, one entered a spacious hallway which served no particular purpose, but merely carried out the idea of the open passage between the rooms of the log cabin. The spacious rooms which flanked the hall on either side were almost invariably square and regular in design, just as they must have been had they been built of logs. And the plan upstairs was the same as below.<sup>12</sup>

But the plantation was much more than a house and lands; being, if it chose to be, largely independent of the outside world for its daily supplies, it was a community in itself. Grouped about the "mansion" were the barns, the smoke-house where pork was cured, the cotton gin and press, and the quarters for the slaves. Places were frequently advertised for sale in the early newspapers, and from these advertisements we get an interesting description of the equipment of a plantation in houses, barns, cattle, mules, swine, and slaves.<sup>13</sup>

<sup>12</sup> This is the writer's interpretation of the facts, but the general idea is completely borne out by the following passage from Stuart's *Three Years in North America*, 11, 160: "The planters' houses in the southern states are very different in their mode of construction from those in the north. The common form of the planters' houses, and indeed of all houses that you meet with on the roadside in this country, is two square pens, with an open space between them, connected by a roof above and a floor below, so as to form a parallelogram of nearly triple the length of its depth. In the open space the family take their meals during the fine weather. The kitchen and the places for slaves are all separate buildings, as are the stable, cow-houses, etc. About ten buildings of this description make up the establishment of an ordinary planter, with half a dozen slaves."

<sup>13</sup> *Alabama Republican*, Nov. 14, 1823; *Cahawba Press*, Dec. 20, 1823, Jan. 7, 1826; *St. Stephens Halcyon*, May 1, 1820.

Slaves were rated, according to their fitness, full, three-quarters, half, and quarter hands, and given tasks accordingly. Adding these fractions, a planter determined how many "full hands," or equivalents, made up his working force. A census of Madison County for 1819 gives nearly twelve acres of cleared land for every full hand,<sup>14</sup> and other evidences make it clear that each hand rated at full work was expected to cultivate five or six acres of cotton and an equal area in corn.<sup>15</sup>

There were several reasons for devoting the land in nearly equal parts to cotton and corn. A gang of hands could plant more cotton than they could possibly pick, so that a part of their time had to be devoted to some other crop, and corn had a peculiar place in the economy of the plantation. The weekly allowance of bread-stuff to the slave was a peck of meal, and this, together with his allowance of pork—the supply of which article was also dependent on the corn crop—made up the regular fare of the working force. The slaves usually had garden plots of their own, and could sometimes add fish or game to their diet by hunting or fishing in spare time. The watermelon and the 'possum were favorites then as now, but corn and pork was the regular fare during the twelve months of the year.<sup>16</sup>

Clothing was issued twice yearly, in the spring and in the fall. Suits of "osnaburg," or coarse cotton clothing, were provided for the summer, and "plains," or coarse woolen stuff for the winter. Hats, shoes, and blankets completed the list of articles which had to be furnished by the master. Medical attention was provided for the sick and nurseries for the children of mothers who went to the field. Altogether, the maintenance of a slave for a year, including his food allowance, his clothing, blankets, and medical attention, cost between twenty and twenty-five dollars.<sup>17</sup>

Judicious farming required that the master produce all his own corn and pork, but, especially when the price of cotton was high, he was likely to increase his crop of the staple and buy corn in the market.<sup>18</sup> This kind of speculative planting

<sup>14</sup> *Alabama Republican*, Aug. 25, 1820.

<sup>15</sup> Wyman, *Geographical Sketch of Alabama* in *Alabama Historical Society, Transactions*, III, 126; *American Farmer*, III, 299; Jackson Papers, A. P. Hayne to Andrew Jackson, Aug. 6, 1820.

<sup>16</sup> Phillips, *Negro Slavery*, Chan. XV.

<sup>17</sup> *American Farmer*, IV, 308-9. See also Phillips, *Negro Slavery*, Chap. XV.

<sup>18</sup> Walker Papers, C. Tait to J. W. Walker, Nov. 19, 1819.

was not only bad from an economic point of view, but tended to over-work the slaves during the picking season. For the small farmer, excessive cotton planting meant that his family was put on short rations.<sup>19</sup> But such practices as this seem to have been common during the early, speculative period of the industry in the State. Though periods of low prices operated to check this over-planting of cotton, it is certainly true that during the early 'twenties, a large quantity of corn and pork was imported from other states by the planters, and many complaints were made about it by the agricultural critics.

There seems to have been little difference between the methods employed in the culture of cotton and of corn, but naturally that of cotton received more attention. The agricultural year began about the middle of February, when the first plowing could be done. All the old cotton and corn stalks were gathered and burned, and the ground was bedded up by running one furrow and then lapping several others upon it. This process was called "listing."

During March the cotton was planted by running a drill down the center of the beds and sowing the cotton rather thickly in the drill. The seeds were covered by attaching a board with a concave surface to a plow and drawing it along the crest of the bed. When the young cotton was well above the ground, the stand was thinned with the hoe, leaving but two stalks in a place. Later, another thinning reduced the stand to a single stalk in a place. The distance between the beds and between the stalks in the bed varied according to the fertility of the soil or the caprice of the planter. Three and a half feet between beds and eight inches between stalks was given as a fair average for the Tennessee Valley.<sup>20</sup>

Frequent cultivation was necessary in order to keep down the grass and weeds, and this was done partly by the plow and partly by the hoe. That crops were usually kept in very good condition is indicated by the favorable comments of travelers into the cotton region. The bolls began to open the latter part of August, but they fruited gradually, and had to be picked often in order to prevent damage to the fibre. This

<sup>19</sup> Hodgson, *Letters from North America*, I, 206-207.

<sup>20</sup> *American Farmer*, VIII, 222-223, quoting a letter from John Pope, of Florence, Alabama, dated Sept. 29, 1826; *Southern Agriculturist*, II, 255; Hammond, *Cotton Industry*, 76-77; Fessenden, *Complete Farmer*, 263-265.



was the busiest time of the year and all available help was called in. The picking went on steadily through the fall months and well into the winter. Sometimes a part of the crop was still in the field and had to be destroyed when the time for spring plowing arrived.<sup>21</sup>

Ginning was also a slow process compared with modern methods. Every planter of any importance had his own gin-house where his staple was prepared for the market. If properly prepared, the cotton had to be carefully picked over by hand for the removal of trash and yellow flakes before it went to the gin; and after coming from the machine, it always had in it particles of seed and other foreign matter which had to be removed by another picking over, or moting. The ginned cotton was taken to the press where it was squeezed into bales of about 350 pounds. The gin and the press were both run by horse power, and several hands were kept busy at the work.<sup>22</sup>

During the decade, however, two important advances were made in the processes of preparing cotton. In 1822 Carver's improved gin was introduced in Mississippi and its advantages were noised abroad in the agricultural papers. It was claimed that the new machine did not tear the fibre while removing it from the seed, and that the quality of the staple was thereby much improved. James Jackson and General Coffee introduced the new gin into the Tennessee Valley, and the cotton which they turned out with it was said to be of unusual quality.<sup>23</sup> In 1824 the first supply of these machines was received at Mobile.<sup>24</sup>

At about the same time there was contrived and introduced in Mississippi an apparatus for moting the cotton as it came from the gin. In Whitney's gin the cotton fibre was removed from the seed by means of revolving saw-teeth, and revolving brushes removed the fibre from the saws. The arms of the revolving brushes were now supplied with fans which blew the issuing cotton through a horizontal wooden

<sup>21</sup> Royall, *Letters from Alabama*, 62.

<sup>22</sup> An excellent description of the method of preparing cotton for market was furnished the *Nashville Agriculturist* by Alexander McDonald, of Eufaula, Alabama, in 1845. It is reprinted in Sen. Doc., 1 Sess., 29 Cong., Vol. VI, No. 307. Though this is later than the period under discussion, it gives a clear idea of the problems and methods of ginning and packing cotton on a plantation.

<sup>23</sup> *Alabama Republican*, Feb. 15, 1822, Mar. 22, 1822.

<sup>24</sup> *Mobile Register*, March 26, 1824.

flue with a latticed bottom. As the lint passed through the flue, the particles of foreign matter dropped through the grating into a trough below. Thus a large part of the labor of moting was dispensed with.<sup>25</sup>

The ginning and packing of cotton was a matter of great importance, for the market value of the staple depended largely upon its freedom from flaws and foreign matter. Many complaints were made as to the carelessness with which the Alabama planters handled their product. It was stated that, while the staple of the Alabama cotton was as good as that of any upland variety, it brought a lower price than that of either Georgia or Louisiana because of the indifferent way in which it was ginned and handled.<sup>26</sup> The truth of this statement is, however, hard to judge. Louisiana and Mississippi cotton consistently brought a higher price than that of Alabama. That of south Alabama and Georgia stood on a fairly equal footing, while that of Tennessee and north Alabama usually brought the lowest price. The adaptability of climate and soil to the cotton crop in these several localities was undoubtedly the prime factor in these distinctions, but it is quite likely that there was also a difference in agricultural methods. As far as Alabama is concerned, the people who moved into the southern part of the state came chiefly from sections in Georgia and South Carolina where the planting of cotton was already familiar and well-established. Those who moved into the Tennessee Valley came in greater numbers from Tennessee, Virginia, and North Carolina, where cotton had never been of importance.

Alabama writers, and especially those in the Tennessee Valley, often complained that the various methods in use indicated that no scientific basis of field-management had been arrived at. The greatest bone of contention was as to the distance that should be allowed between the beds and the stalks in the beds. There was also much variety as to the use of fertilizer. Stable manure was, of course, used, and cotton seed was employed by many. The latter was sometimes mixed with leaf mold or other material and allowed to stand in great piles until spring, when the mixture was strewn in drills. Yet there can be but little doubt that the worth of cot-

<sup>25</sup> *Cahoeba Press*, Jan. 21, 1822; *American Farmer*, IV, 380-382.

<sup>26</sup> *Alabama Republican*, Sept. 7, 1821, Nov. 23, 1821, Sept. 27, 1822; *Cahoeba Press*, Dec. 13, 1821, Jan. 28, 1822.

ton seed as fertilizer was generally overlooked and the valuable material thrown away.<sup>27</sup>

The greatest advance that was made during the decade in the raising of cotton was the introduction of the "Mexican" variety of seed. This produced larger pods which opened wider than the old variety and allowed the fibre to hang from the bolls, making the picking an easier process than it had previously been. Industrious hands were now able to pick two hundred pounds a day, whereas one hundred had formerly been a good average.<sup>28</sup>

The planting of a localized staple such as cotton was a more speculative industry than was the raising of the more widespread crops. Since the South furnished the world with most of its cotton, a bountiful crop in that section, not being offset to any great extent by differing conditions in other places, would depress the price to the full extent of the local overproduction. Likewise, a short crop in the South meant a shortage of cotton for the world, and a high price which would spend its whole buoyant force upon the industry of a few states. And the planters were the most helpless of people in the matter of adjusting themselves to the varying economic conditions. Once a man had established himself as a slave holder in the lower South, he found it hard to vary his agricultural system.<sup>29</sup> He could not diminish his crop much below the normal, for his slaves were efficient only when worked according to the usual routine; nor were there any facilities for marketing other crops.

It was the high price of cotton during the years following the close of the second war with England which gave Alabama her first great influx of population. During 1818 land sales in Alabama reached their zenith. So keen was the competition at the Government auctions for good cotton acreage, that especially desirable tracts were sold off at prices which caused comment throughout the country. But cotton fell from thirty-four to twenty-four cents the next year; to seventeen cents in 1820; to fourteen in 1821; and in 1823 it

---

<sup>27</sup> Saxe-Weimar, I, 33; *Southern Advocate*, July 21, 1826; *Southern Agriculturist*, II, 254-262; Royall, *Letters from Alabama* (quoting letter from Col. Pope), 162.

<sup>28</sup> *American Farmer*, II, 116 (July 7, 1829); *Southern Advocate*, Sept. 8, 1826, Sept. 29, 1826; *Huntsville Democrat*, Sept. 8, 1826.

<sup>29</sup> *Southern Advocate*, Nov. 17, 1826.

reached bottom at about eleven cents a pound.<sup>30</sup> During these years of falling prices, the value of slaves declined steadily,<sup>31</sup> though there was more land cultivated in the Tennessee Valley in 1821 than during any previous season.<sup>32</sup> By 1823, however, discouragement had set in, and the low price resulted in the planting of a smaller cotton crop.<sup>33</sup> Retrenchment was, however, a hard matter for the planter. He could do little more in that direction than raise all his own supplies of corn and pork, and the amount of cotton shipped from Mobile remained practically stationary during 1822, 1823, and 1824.<sup>34</sup>

In 1825 there came a jump in the price as a result of speculation in the British market. Corn was actually plowed up in Alabama for the sake of planting more cotton;<sup>35</sup> the volume of the crop rose; and the value of slaves was stimulated. But the optimism was short-lived. The price of the staple receded to a lower level than it had reached before, and for several years thereafter cotton sold in New York for about ten cents a pound. The depression in Alabama was marked.

Complaints of the unprofitableness of cotton went up on all sides, and the need for diversification was urged. The prevalent unscientific methods of planting were condemned and a widespread agitation for agricultural societies set in.<sup>36</sup> The Governor's message of 1826 urged diversification and suggested a standing committee to consider the agricultural problems of the State.<sup>37</sup> So great had been the over-planting of cotton in 1825 that the *Alabama Journal*, on Sept. 6, 1826, proposed a special meeting of the general assembly to afford relief in view of the impending scarcity of provisions. Yet there was only a temporary decrease in the amount of cotton that went out from Mobile.

---

<sup>30</sup> For yearly average of prices for middling upland cotton in New York and Liverpool, see J. L. Watkins, *Production and Price of Cotton*, U. S. Department of Agriculture, Statistics, Miscellaneous Bulletins, 1895, No. 9, p. 8-9.

<sup>31</sup> For chart of slave prices, see U. B. Phillips, *Negro Slavery*, 370.

<sup>32</sup> *Alabama Republican*, Nov. 2, 1821.

<sup>33</sup> *Mobile Argus*, Oct. 31, 1823; *Huntsville Democrat*, Oct. 28, 1823; *Alabama Republican*, Oct. 24, 1823.

<sup>34</sup> Hazard, *U. S. Commercial and Statistical Register*, III, 272.

<sup>35</sup> *Tusculumbian*, June 27, 1825.

<sup>36</sup> *Alabama Journal*, Sept. 29, 1826; *Southern Advocate*, Sept. 15, 1826, Dec. 1, 1827; *Huntsville Democrat*, March 9, 1827.

<sup>37</sup> Senate Journal, 1826, 9.

The average production of cotton for a slave was, during these years, about a thousand pounds, ginned.<sup>38</sup> This, at ten cents a pound, would be worth one hundred dollars, and since the maintenance of a slave cost approximately twenty-five dollars a year in money and provisions, there remained about seventy-five dollars to provide for up-keep, interest, and profits. The indications are that ten cents was the lowest price at which cotton could be raised at this time without a loss; but it seems that the production of a slave was later increased so that a lower price became possible.

As to the management of slaves in Alabama during the early period, no information has been obtained. In describing a Georgia plantation in 1828, Basil Hall gives an account of the "tasking" system;<sup>39</sup> and E. C. Holland, in a treatise written on the subject in 1822, says that this was the universal practice at the time.<sup>40</sup> Fields were staked off into quarter-acre, half-acre, or three-quarter-acre "tasks" in proportions to the laboriousness of the work and the strength of the hand. By diligence, the worker could finish his task early in the afternoon and have the rest of the day to himself. In this way, compulsion was reduced to the minimum, and the slaves given a stimulus to work. Another account shows that this system was in use in South Carolina, and there are scattered references to it in agricultural discussions. Whether it was really universal cannot be stated except upon the authority of Holland's assertion. For Alabama there is no information one way or the other.

The small farmer was not dependent upon the price of cotton. He had come into the new country in search of economic freedom rather than of fortune. He sought subsistence for his family rather than cotton lands and access to market. He did not compete for the most fertile and accessible locations because he lacked the capital, and because it was not to his interest to do so. A secluded nook would serve him as well or better, for he loved the freedom of the forest, his rifle, and his

<sup>38</sup> Statistics for Madison County for 1819 give 825 pounds as the average for a full hand. See *Alabama Republican*, Aug. 25, 1820. James G. Birney is said to have produced 1850 pounds to the hand in 1820, Jackson Papers, James Jackson to Andrew Jackson, May 28, 1821. But a thousand pounds to the hand is mentioned in most estimates as the average.

<sup>39</sup> Basil Hall, *Travels in North America*, II, 229-231.

<sup>40</sup> Edwin C. Holland, *A Refutation of the Calumnies Circulated against the Southern and Western States Respecting Slavery*, 48-53.

axe. He built his house of logs, cleared his corn patches, and raised his hogs. There was a fine range for cattle in the woods, and large herds found their own subsistence for the greater part of the year.<sup>41</sup>

Many, perhaps most, of the small farmers had come west with practically no property, and their farming equipment was at first of the crudest kind. Wheat was a familiar crop to many of them, and it was tried in Alabama, but lack of flour mills made the grinding of it a difficult problem. Corn proved to be more practicable, and grist mills were built on the streams during the first stages of settlement. Cotton, too, soon came to be popular with the small farmer. Though a man could not raise the supplies for his own family and plant a large cotton crop at the same time, he could raise a small amount of the staple and sell it for enough to supply his financial needs. Thus, largely because of the ease of marketing it, cotton came to be the "money crop" among the farmers.<sup>42</sup>

Taking a general view of the State, the several regions within Alabama differed materially in their economic composition. The Tennessee Valley, to begin, offers the most complete picture of agricultural, and hence social and political, diversity. The Georgians who established Madison County in 1809 invested extensively in land, and, being on the ground during the phenomenal years of 1817 and 1818, their fortunes soared. By 1826 some of them owned gangs of negroes numbering into the hundreds.<sup>43</sup> Also among the Virginians, North Carolinians, and Georgians who purchased lands in the Valley in 1818 were men of extensive wealth. The speculative conditions under which the valley region west of Madison County was opened up served to debar men of moderate means from securing desirable tracts. But all the northern counties contained lands lying outside the valley region, and consequently there remained many less desirable tracts which could be taken up by private entry after the auction sales were over. Tennesseans of moderate means came down in large numbers and settled in the same counties with the wealthy planters.

---

<sup>41</sup> Hodgson, *Letters from North America*, I, 124; Riley, *Conecuh County*, 52; *Southern Advocate*, Sept. 7, 1827.

<sup>42</sup> Teeple and Smith (Publishers), *Jefferson County*, 59; Riley, *Conecuh County*, 22-25, 92-111; Smith, *Pickens County*, 46-48; Yerby, *Greensboro*, 3.

<sup>43</sup> Based on statements published in *Southern Advocate*, Dec. 1, 1826.

This diversity of origin and station between close neighbors developed a certain antagonism which was aggravated by the commercial situation. The cotton of the Valley had to be lightered over Muscle Shoals and then floated all the way down to New Orleans before it could be marketed. To have a crop ginned and baled, and shipped in this way to merchants in New Orleans; then to cash the draft which was received in return and secure the proceeds, required months of delay and entailed reliance upon forwarding agents, brokers, and banks, which the small producer was not able to face on his own account. In order to avoid all this, he sometimes sold his cotton in the seed to local merchants who provided him with his supplies. Sometimes he prepared his crop for shipment and turned it over to a merchant who advanced him a certain per cent. of its value and paid the balance when the remittance came up from New Orleans.<sup>44</sup> In either case, he was likely to lose at every turn in the transaction, and this condition of commercial dependence tended to leave him resentful toward those with whom he was forced to do business. The political result of this situation made the Tennessee Valley a hotbed of partisan contention.

This section seems to have gone in more for quantity than quality,<sup>45</sup> and its cotton brought the lowest prices on the market. When a crop was disposed of to a country merchant, the staple was usually taken at a uniform price.<sup>46</sup> The fact that a large part of the output was sold in this way may account for the relatively careless handling of the product in the Tennessee Valley. Picking and preparing the staple for market required great care, and negligence in these processes resulted in a trashy fibre that greatly reduced the value of the article. Over-planting of cotton caused congestion during the picking season and naturally led to careless handling.

Over-planting also made it necessary to purchase a large part of the corn and pork supply for the negroes, and the importation of these articles into the Tennessee Valley was large. The trade was encouraged by the ease with which such products could be brought down the River from East Tennessee.

<sup>44</sup> See Chapter IX.

<sup>45</sup> *Documentary History of Industrial Society*, from the *Georgia Courier*, Oct. 11, 1827, 283-298.

<sup>46</sup> *Mobile Register*, Jan. 6, 1823.

Occupying the north-central portion of the State and extending from the Tennessee Valley to the navigable waters of the Alabama and Tombigbee Rivers, lay the hilly region. Here the isolated valleys were settled by men of pioneer instincts who began to come in as early as 1815. Small clearings were made and log cabins rose here and there. The woods furnished abundant game and an excellent range for cattle, while corn and hogs were relied upon as the principal food supplies. In other words, this region reproduced the characteristics which have always typified the advancing frontier of our Country.

Since a large majority of the inhabitants of Alabama were of the farmer rather than of the planter class, and since the planters needed supplies of corn and pork which the farmers principally raised, it seems, at first glance, strange that the hilly region did not send large quantities of these products into the river valley regions. This would have been an easily accessible market for the farmers, and the planters would have had a convenient source of supply, but no such trade ever reached significant proportions. The explanation is that the farmer planted his surplus in cotton rather than in corn. Cotton was easier to handle, and the financial return was evidently more satisfactory in spite of the fact that the small producer could not own his gin nor market his crop except by disposing of it to a local merchant. For the greater part of the central hilly region, Tuscaloosa, at the head of navigation on the Black Warrior, was the most convenient market after the steamboat came into general use. The road which connected Tuscaloosa with Huntsville passed through Jones Valley, in which Birmingham now stands; and along this route most of the cotton was carried to market and the supplies of coffee, sugar, and flour brought back to the farm.<sup>47</sup>

Though the sticky soil of the prairie region, or Black Belt, was avoided by the planter until about 1830, there were fertile tracts of land upon the northern border of the prairie which proved attractive to the first planters who immigrated to Alabama. These areas, together with the bottom lands along the Alabama and Tombigbee Rivers, constituted the cotton section of the southern part of the State.

Excepting in the prairie region, the stretches of good land were not so extensive as in the Tennessee Valley, and the

<sup>47</sup> *Alabama Republican*, March 1, 1822; *Huntsville Democrat*, Jan. 19, 1827.



planter lived in closer relation to the man who farmed without slaves; and since he was a fellow agriculturist rather than a capitalist in the eyes of his less wealthy neighbors, the sharp political dissensions which agitated the Tennessee Valley lost their sting in the south.

Perhaps the best expanse of land in all this region lay in the vicinity of Montgomery County, and here there grew up what was probably an ideal planting community. The inhabitants are pictured as peace-loving, industrious, and economically independent. Instead of dealing with the local merchants, they carried their cotton to Mobile and brought their supplies back up the River.<sup>48</sup>

Though the indications are that the agricultural system practiced in this region was more conservative than that of the Tennessee Valley, and that there was less over-planting of cotton, yet large quantities of pork and corn were imported along with flour and whisky. Though some of this came down through the country from Tennessee, the bulk of it came from Mobile, to which point it had been shipped from the Ohio and Cumberland River region by way of New Orleans. It was said in 1824 that from twenty to thirty thousand barrels of such supplies passed through Mobile annually.<sup>49</sup>

The piney region of sandy clay which covers the southeastern corner of Alabama was considered relatively infertile, and here men without slaves or property set up a frontier community at the time when the rest of the State was being settled. Lands in the back-woods sections did not begin to be sold until about 1824, so that the immigrants could "squat" for years upon Government property and then buy in their farms at the minimum price after the speculative period was well over. Coming principally from Georgia, South Carolina, and Tennessee, the inhabitants of this region had the same general characteristics as those of the hilly region. The pasturage here made it possible for cattle to sustain themselves during the entire year, and numerous herds were kept by many of the settlers.<sup>50</sup>

Thus the agricultural life of Alabama may be divided into two predominant phases: that in which the planter, with a highly capitalized establishment, raised cotton with slave la-

---

<sup>48</sup> Robertson, *Montgomery County*, 11-13, 15-16, 36-38, 125, 139-140.

<sup>49</sup> *Mobile Register*, March 2, 1824.

<sup>50</sup> Riley, *Conecuh County*, 19, 28-32, 43-54, 55-65.

bor for the sake of profit; and that in which the farmer, with very little capital, sought an independent existence for his family. To the planter, rich lands and convenient water transportation were essential, while the price of cotton was of prime importance. To the farmer, transportation facilities were of little importance, and a large part of the State offered him isolated bits of good land which would have been of no value to the planter. The geographical segregation of these two classes of people was not complete, but there was little active competition between them. The best cotton lands were sold during the speculative period when the man without capital had little chance of successful competition; the backlands were sold during a later period when the actual settler could buy them in at the minimum price with money which he had made upon the ground. Though there was a tendency for the planter to displace the farmer who had settled in his immediate neighborhood, nevertheless, the lines which separated the planting districts from the farming districts were laid down when the Government first opened the lands to the whites.

## CHAPTER VIII.

### RIVERS AND ROADS

There is no way of realizing more keenly the difference between past and present than to look upon the untroubled waters of a navigable river and recall that it once shaped the history of a section. Though the turbid stream of the Alabama now but rarely floats a vessel, it is fitting that it gave its name to the State that it traverses. It was their separate waterway which gave the settlers along the Tombigbee interests which were distinct from those of the settlers upon the lower Mississippi. It was down the stream that the early planters intended to float their cotton to market, and so they chose their homes near the rivers.

Mobile was a struggling community of three hundred inhabitants, mostly Creoles, when it was taken over by the Americans in 1813. A few years later, when population began to spread along its tributary rivers, it began to grow and in 1819 numbered eight hundred inhabitants. In 1823 this number had increased to nearly three thousand.<sup>1</sup> Most of the higher class of Creoles had left when Spanish rule ended, and the new population was made up of Americans of every type. Merchants came largely from the North, adventurers gathered from every quarter, and the mixture, according to some visitors at least, was not attractive.<sup>2</sup>

In place of the one wharf of Creole days, there were a dozen by 1823. Markets were built and brick structures began to replace wooden buildings. Because of obstruction in the harbor, ships of the larger class entered with difficulty. This fact made it necessary for the town to confine its shipping largely to the coastwise traffic. Fruits from Cuba were to be found in the markets and a regular trade with New York was established at an early date, but a large part of the cotton which was destined for Europe had to be sent to New Orleans for shipment.<sup>3</sup>

<sup>1</sup> *Niles' Register*, XXII, 96; *Mobile Register*, Feb. 7, 1822.

<sup>2</sup> Hodgson, *Letters from North America*, I, 152.

<sup>3</sup> Saxe-Weimar, *Travels Through North America*, I, 39-41; Hamilton *Colonial Mobile*, 473; *Mobile Argus*, Oct. 28, 1823; *Mobile Advertiser*, Feb. 26, 1824.

The cotton region along the rivers gave birth to several towns between 1815 and 1818. St. Stephens already stood at the head of schooner navigation on the Tombigbee. It had been a flourishing little community when Mobile was still in the hands of Spain. But now the trade passed it by and went down to the larger town on the Bay. It still held a local trade, however, and some of its glory lingered. With its bank, its academy, its press, its land office, and its steamboat company, it maintained its place for awhile; but its well-built houses were destined to sink into ruins which have now all but disappeared from view.<sup>4</sup>

Far above St. Stephens, Tuscaloosa was located at the head of boat navigation on the Black Warrior, and from here such overland trade as there was between the two sections of the State passed through Jones Valley to the Valley of the Tennessee.<sup>5</sup>

On the Alabama River, Claiborne grew up at the head of schooner navigation and came to be the center of a cotton-planting community. The capital of the State was established at Cahawba, where the river of that name flows into the Alabama; and Selma was founded a few miles above. On a bluff not far from the head of navigation, two towns were established by land speculators in 1817 and 1818. One of these was founded by Andrew Dexter, from Massachusetts, and was christened New Philadelphia; the other was founded by the Bibb Company and named East Alabama. In 1819 the two settlements were combined and incorporated as the town of Montgomery.<sup>6</sup>

From these places, the cotton passed down the rivers to Mobile. Flat bottomed boats—crudely constructed affairs with pitched seams—could carry from fifty to a hundred bales and were broken up at the end of the journey.<sup>7</sup> Keel boats, though not used so frequently as flat-bottomed boats on the Alabama and Tombigbee, were employed where the requirements were more severe. They were frequently about fifty feet in length and were more durable and sea-worthy than the flat-bottomed type. But the greater expense of construction discouraged their use except where a return trip was to be made.

---

<sup>4</sup> St. Stephens *Halcyon*, March 30, 1822.

<sup>5</sup> *Alabama Republican*, May 4, 1821; Hamilton, *Colonial Mobile*, 463.

<sup>6</sup> Woodward, *Reminiscences*, 130; Blue, *Montgomery*, 6-8.

<sup>7</sup> Saxe-Weimar, *Travels Through North America*, I, 35.

Nor were return trips very frequent. A boat which would float down from Montgomery to Mobile in about two weeks required a month or six weeks to be poled or warped back up the river; and the freight rate prevailing at that time was five dollars a barrel.<sup>8</sup> Merchants generally preferred to bring their wares over the Federal Road from Georgia,<sup>9</sup> or down from the upper country. Whisky, pork, and flour were the most generally desired commodities in the cotton section. These articles could be obtained in east Tennessee and in west Virginia, and they could be brought thence by the following method: A keel boat was loaded near the place of production and floated down the Holston to the Tennessee River. By ascending a small tributary of the Tennessee, the Hiwassee, the boat could be navigated to within twelve miles of the headwaters of the Coosa. There was a portage across this stretch of land. Boat houses were constructed at either end of it, and arrangements were made for hauling the boats in wagons from one stream to the other. This route was traversed at a very early period in Alabama history. Tennessee produce reached Montgomery by this course, and about twelve thousand gallons of whisky were said to have been carried across the portage in 1821.<sup>10</sup>

Transportation conditions in the Tennessee Valley were rendered peculiar by the presence of the obstruction in the channel of the River at Muscle Shoals. During the dry summer months the Shoals could not be passed, but the River rose in the fall, and by February, boats could go over the rapids. The water began to go down again in the spring, so that but two or three months elapsed during which shipments could be made from above.<sup>11</sup> Warehouses were built at landing places on the River and here cotton was accumulated by merchants and shippers. As soon as the water rose, the bales were loaded on keel boats which were dispatched in fleets under the charge of experienced pilots who saw them safely past the Shoals. The pilots would then return, and the boats would

---

<sup>8</sup> Levasseur, *Lafayette en Amerique*, II, 345; *Niles' Register*, XXI, 215; Jackson Papers, E. P. Gaines to Andrew Jackson, March 15, 1816. See Phillips, *Transportation in the Eastern Cotton Belt*, 71, for a description of the flat-bottomed and pole boats.

<sup>9</sup> Hall Papers, Hines Holt to B. Hall, July 4, 1820, Sept. 20, 1820, Nov. 14, 1820.

<sup>10</sup> *Niles' Register*, XX, 63, House Ex. Docs. No. 15, 20, Cong., 2 Sess., Vol. 1.

<sup>11</sup> *Alabama Republican*, Feb. 8, 1822.

proceed to New Orleans under the direction of forwarding agents. The freight rate for cotton shipped in this manner was from four to five dollars a bale.<sup>12</sup>

But difficult as it was to get cotton to market, it was still more difficult to bring back the supplies which were needed. There were several possible routes and all of them seem to have been used at times. Until 1816 the usual method was to ship goods from New York and Philadelphia to Charleston or Savannah; transport them to Augusta, and thence carry them by the "Georgia Road" through the Cherokee country to Ross's landing, opposite the spot where Chattanooga now stands on the Tennessee. From here they were floated down to Ditto's landing near Huntsville, or to other points along the River. In 1816 a merchant named Crump was the first to bring goods from Mobile to Huntsville by poling them up the River in a boat to Tuscaloosa, and hauling them in wagons from that place. The road was found to be fairly good, and the overland trip required but eight days.<sup>13</sup> Supplies might also be brought through the Valley of Virginia by way of Knoxville; but the favorite route during the 'twenties seems to have been that down the Ohio to the Cumberland, up the Cumberland to Nashville, and across country from that place. Flour, pork, and whisky could be brought from Kentucky and the Northwest in this way, as could manufactures which went overland from Philadelphia to Pittsburgh and then down the Ohio.<sup>14</sup>

With the advent of the steamboat, conditions were radically changed. Goods could now be carried up stream as easily as they could be brought down, and the overland trade rapidly fell off. Central and southern Alabama became dependent upon Mobile for supplies and North Alabama began to obtain most of hers from New Orleans. The planter thus came in time to buy his goods in the same market in which he sold his cotton.

The first appearance of the steamboat on the rivers of Alabama cannot be fixed with absolute precision, but it seems clear that steam navigation on the Tombigbee was established in 1819. Morse's *Universal Geography* of that year states

<sup>12</sup> Belts, *History of Huntsville*, 61-62; *Alabama Republican*, Jan. 18, 1822.

<sup>13</sup> *Washington Republican*, Jan. 1, 1817; Warden, *Account of the United States*, III, 39; Indian Office files, S. D. Hutchings to R. J. Meigs, Dec. 3, 1816.

<sup>14</sup> *Alabama Republican*, Jan. 18, 1822.

that steamers were then plying between Mobile and St. Stephens;<sup>15</sup> and Hamilton asserts in his *Colonial Mobile* that the first trip up to Demopolis was made in 1819 by either the "Tensa" or the "Mobile."<sup>16</sup> There is a record of the launching of the "Tensa" on the Bay during this year, and the citizens of Mobile were a little later congratulated in the local press on another attempt to navigate the River.<sup>17</sup> During the same season the steamboat "Mobile," which had been brought from Boston, was advertised to ascend to Tuscaloosa.<sup>18</sup>

It was not long before the "Harriett" and the "Cotton Plant" were brought to Mobile for service in the river trade, and in 1820 the "Tombeckbee" was launched at St. Stephens. This last boat was of seventy tons burden, had an eighty-five foot deck and drew but fifteen inches of water when unloaded.<sup>19</sup> The others were of about the same size,—in other words but little larger than the average keel boat then in use. But these four little craft were pioneers; they established steam communication on the waters of the Alabama. In 1821 the "Harriett" ascended the Alabama to Montgomery; in 1824 the "Cotton Plant" made her way up the Tombigbee to the head of Navigation at Cotton Gin Port, Mississippi;<sup>20</sup> and in 1828 the first trip was made up the Chattahoochee to the falls at Columbus, Georgia.<sup>21</sup>

It was during the fall and winter months only that the stage of the water was high enough to permit of navigation of these rivers. Dread of yellow fever all but cleared Mobile of population during the summer; but in November the merchants began to return and collect their wares. The cotton trade commenced in this month and continued briskly until the following May or June, then it fell off suddenly and remained at a stand until the waters rose in the fall.<sup>22</sup>

<sup>15</sup> Morse, *Universal Geography*, I, 558.

<sup>16</sup> Hamilton, *Colonial Mobile*, 447-448, 471-472.

<sup>17</sup> *Mobile Gazette*, Aug. 4, 1819, copied in the *Alabama Republican* Aug. 21, 1819.

<sup>18</sup> *Alabama Republican*, April 3, 1819.

<sup>19</sup> St. Stephens *Halcyon*, May 15, 1820.

<sup>20</sup> Hamilton, *Colonial Mobile*, 172; Walker Papers, J. S. Walker to J. W. Walker, Nov. 23, 1821. In 1822, the *Elizabeth*, the *Harriett*, the *Cotton Plant*, and the *Tensa* were navigating the Alabama, while the *Tombeckbee* was plying the Tombigbee River; *Mobile Register*, June 10, 1822.

<sup>21</sup> *Cahawba Press*, Apr. 24, 1824.

<sup>22</sup> Statistics on the trade for the seasons 1826-1827 and 1827-1828 collected from the *Mobile Register*.

The number of boats on the rivers increased from year to year. In 1823 there were eleven,<sup>23</sup> and by 1826 the number had risen to eighteen.<sup>24</sup> All of these were vessels of light draft, the lightest being used in the Tuscaloosa trade. Cotton was piled high on the decks and passengers confined closely to the cabins, which were not commodious. Before reaching a town, a gun was fired from the deck in order to warn the inhabitants of the approach of the vessel. The banks of the rivers were generally steep and high, and cotton was loaded by sliding it down an inclined plane. The boats frequently lay to in order to take on wood, and they always stopped over night because of the many dangers which were to be encountered in the tortuous streams. Striking on a snag and sinking was no infrequent occurrence.<sup>25</sup> Twice within the same season the "Cotton Plant" succumbed to that fate, but each time she was raised and sent on her way.

In the Tennessee Valley the transportation problem was peculiar. Huntsville, the largest town in the region, was built around a great spring distant some ten miles from the River, and at a considerable distance above the Shoals. Florence and Tuscumbia grew up where the Natchez Trace crossed the Shoals. They had some forwarding business in connection with the shipping down the Tennessee, but there was little return trade in the early years.

The first steamboat to reach Florence, as far as records show, came in 1821.<sup>26</sup> From that time forward development was rapid. It was only the next year that a small vessel, the "Rocket," was commissioned to run regularly between Florence and the mouth of the River, depositing its cargo at Trinity to be forwarded up the Ohio or down the Mississippi in larger vessels.<sup>27</sup> Regular lines were later established to connect Tuscumbia with New Orleans and the towns along the Ohio.<sup>28</sup>

Commercial conditions in the Tennessee Valley were changed by these improvements in communication. The shippers above the Shoals continued to send their cotton down in keel boats, but after the passage over the rapids, they were often

---

<sup>23</sup> *Mobile Argus*, Oct. 28, 1823.

<sup>24</sup> *Mobile Register*, Dec. 19, 1826.

<sup>25</sup> Saxe-Weimar, *Travels through North America*, I, 32-38.

<sup>26</sup> *Alabama Republican*, March 16, 1821.

<sup>27</sup> *Ibid.*, Jan. 18, 1822, March 15, 1822.

<sup>28</sup> *Ibid.*, May 17, 1822; *Tuscumbian*, Aug. 22, 1825, May 8, 1826.



towed to New Orleans by the steamers, or their cargoes were transferred to the larger vessels. Freight rates to New Orleans fell from more than a dollar a hundred-weight to eighty cents in 1822 and to fifty cents in 1828.<sup>29</sup>

Keel boats still came to Florence from the upper waters of the Ohio, and merchants in the vicinity of Huntsville still brought goods down from Nashville; but the steamboats which came up to Florence brought large quantities of produce from New Orleans, and this came to be the main source of supply for the entire Valley region.

One further advance in transportation facilities was made when, in 1828, the little steamer "Atlas" ascended the Shoals and began to ply the Tennessee and Holston Rivers between the rapids and the town of Knoxville, Tennessee.<sup>30</sup>

The introduction of steam navigation made more evident than ever the desirability of overcoming the obstruction at Muscle Shoals by means of a canal. The question was taken up by the legislature in 1823 and continued to be discussed during following years. Two successive companies were incorporated by the State for the construction of the desired canal, but the proposition did not prove sufficiently attractive to private investors and nothing was accomplished along these lines of endeavor.<sup>31</sup>

Hope was aroused in 1824 by an act of Congress which appropriated money for the survey of an extensive system of internal improvements. Calhoun, then Secretary of War, was called upon to submit a report on the subject, and the Muscle Shoals canal was among the works which he classed as of national importance.<sup>32</sup> A Government survey was made and a report submitted, <sup>33</sup> but Congress was not acknowledged to have the right to appropriate funds for the construction of such works, and it seemed that the matter would drop here. Yet there was no objection to the donation of land to states for the purpose of internal improvements, and in 1828 Congress granted 400,000 acres of relinquished lands in the Huntsville district, proceeds from the sale of which were to be ap-

<sup>29</sup> *Alabama Republican*, Jan. 18, 1822; *Southern Advocate*, March 14, 1828.

<sup>30</sup> *Southern Advocate*, Feb. 15 and March 14, 1828.

<sup>31</sup> *Alabama, Acts*, 1823, 66-69; *Ibid.*, 1828, 79-86; *Southern Advocate*, March 2, 1827.

<sup>32</sup> *American State Papers*, Military, II, 698-701.

<sup>33</sup> *American State Papers*, Military, IV, 13; *Huntsville Democrat*, July 11, 1828.

plied to the construction of a steamboat canal around the shoals.<sup>34</sup>

While the people of the northern section of the State were interesting themselves in this project, those of south Alabama were working for a canal to connect the waters of the Tennessee with the Alabama River. Such a canal would enable the inhabitants of east Tennessee and west Virginia to ship their produce to Mobile, which was a much closer market than New Orleans. But the main consideration was that the people of south Alabama would be able to purchase their flour, whisky, and pork directly from east Tennessee instead of having to bring it around by New Orleans and Mobile.

This plan did not look unreasonable, for the route of the canal was to be the portage between the Hiwassee and the Coosa, and this covered a distance of only twelve miles, with but a moderate elevation to be overcome. The legislature, in order to enlist the support of both sections of the State, made a practice of dealing with both canal projects at the same time. A company was incorporated and empowered to co-operate with any company which Tennessee should establish for the construction of the Coosa-Hiwassee canal, the reason for this being that the site of the proposed work lay within the lands of the Cherokee Indians above the Tennessee line.<sup>35</sup>

Calhoun, in his report of 1824, considered the Coosa-Hiwassee canal, but classed it as of less national importance than that around Muscle Shoals. Though a Government survey was made and a report presented,<sup>36</sup> the scheme for connecting the waters of the Alabama and Tennessee did not recover from this set-back, and the Muscle Shoals project forged ahead while the other died a lingering death.

While Alabama was divided into two commercial sections by her rivers, the roads which connected her with the rest of the country did not tend to draw these two sections together. There were two main routes of travel connecting Washington with New Orleans: the one which passed through Richmond, Raleigh, Columbia, Milledgeville, and Montgomery to Mobile; and the one which passed into the Valley of Virginia at Rockfish Gap, threaded the Valley and then followed the course of the Holston to Knoxville. From Knoxville, it passed to Huntsville, then on to Tusculumbia at Muscle Shoals, and fol-

---

<sup>34</sup> Statutes at Large, IV, 290.

<sup>35</sup> Alabama, Acts, 1823, 62-66.

<sup>36</sup> House Executive Documents, No. 15, 20 Cong., 2 Sess., Vol. I.

lowed the Natchez Trace to New Orleans. In addition to these, there was one other important route of travel between the East and the Southwest. This was a continuation of the National Highway from Cumberland on the Potomac to Wheeling. Passing from Zanesville, Ohio, to Maysville, Kentucky, it ran on through Lexington and Nashville, joining the Natchez Trace at Muscle Shoals.

Most of the travelers journeying from the East to New Orleans took the route through the Southern capitals. Some of them, instead of going all the way to Mobile before embarking, took boat at Montgomery and made the circuitous voyage down the river rather than endure longer the hardships of the road. Hodgson, who passed this way in 1820, took the land route to Mobile,<sup>37</sup> but Lafayette took the water course when he came in 1825,<sup>38</sup> and so did the Duke of Saxe-Weimar who followed in 1828.<sup>39</sup>

A journey over the roads of that day was a real undertaking. The traveler had to content himself with log cabin accommodations as he passed through the forests, and the inns of the towns were not attractive. It was a frequent occurrence for vehicles to be upset at some danger to life and limb, and consequently most of the traveling was done on horseback. The building of a road consisted merely in cutting a passage through the woods, the stumps being left several inches above the ground. Bogs were traversed by causeways made of small logs placed close together across the road with dirt thrown on top. Bridges were not ordinarily built across the fordable streams, but ferries were established at the crossings of the rivers.

Instead of going through the Southern capitals, the mail from Washington to New Orleans went through the Valley of Virginia and by Huntsville until 1827. From Huntsville it was carried to Tusculum and thence followed the Natchez Trace.<sup>40</sup> As far as Huntsville, there was something that could be called a road, but the Natchez Trace was reported to be nothing more than a broad grass path.<sup>41</sup> The route was circuitous, and in 1816 Congress made an appropriation to enable Andrew Jackson to cut a more direct road from Tennes-

<sup>37</sup> Hodgson, *Letters from North America*, I, 39 et seq.

<sup>38</sup> Levasseur, *Lafayette en Amerique*, II, 345.

<sup>39</sup> Saxe-Weimar, *Travels Through North America*, I, 32-38.

<sup>40</sup> House Reports, No. 48, 20 Cong., 1 Sess., I, 176.

<sup>41</sup> Hodgson, *Letters from North America*, I, 273.

see to New Orleans.<sup>42</sup> The troops were employed on this work, which was begun in 1817 and completed in 1820. It diverged from the old Trace road at Muscle Shoals, and, passing Columbus, Mississippi, on the Tombigbee River, took a straight course to Madisonville, opposite New Orleans on Lake Ponchartrain.<sup>43</sup>

This Military Road, as it was called, was forty feet wide, had bridges over the smaller streams, and well constructed causeways over the marshy places. But no provisions were made for keeping it in repair, and since the Trace road passed through the towns on the Mississippi while the Military Road lay through a region largely uninhabited, the latter was allowed to fall into disuse. By 1824 the bridges had mostly been washed away and a growth of young trees was flourishing in the road itself. Though it was intended that the mail should have passed this way to New Orleans, it became necessary to cross over below Columbus and continue to take it along the old Trace route.<sup>44</sup>

Though the road to Huntsville was at first a mere branch of the main thoroughfare between Knoxville and Nashville, it afforded a more direct route to New Orleans and this fact was recognized by sending the mail this way after 1822. In 1820 Huntsville was made the terminus of the first stage line in Alabama. This connected with the main line between Knoxville and Nashville, and at first the service was only once a week.<sup>45</sup> This was increased in 1823 to two trips each way every week.<sup>46</sup> In 1825 an increase to three trips a week was made, and the line was extended to Tuscumbia.<sup>47</sup> Stages also connected Tuscumbia with Kentucky and Ohio by the route through Zanesville, Lexington, and Nashville.<sup>48</sup> But below Tuscumbia, the river did not permit of continuous navigation and the Natchez Trace did not permit of stages. Consequent-

<sup>42</sup> Statutes at Large, III, 315; American State Papers, Military, IV, 627.

<sup>43</sup> American State Papers, Miscellaneous, II, 537; *Alabama Republican*, Dec. 17, 1819, and June 9, 1820; Jackson Papers, Wm. H. Crawford to Andrew Jackson, March 8, 1816, W. Young to Jackson, March 14, 1817.

<sup>44</sup> American State Papers, P. O. Dept., 119-120; *Tuscumbian*, Nov. 12, 1824.

<sup>45</sup> *Alabama Republican*, May 6, 1820.

<sup>46</sup> *Ibid.*, Aug. 16 and Sept. 13, 1822.

<sup>47</sup> *Tuscumbian*, April 11, 1825.

<sup>48</sup> American State Papers, P. O. Dept., 241; *Southern Advocate*, Sept. 4, 1827.

ly, from Tusculumbia to New Orleans the mails were still carried on horseback.

The route through the Southern capitals, instead of paralleling the streams as did the one through Huntsville, crossed them and hence was more subject to interruption from swollen waters. Though it lay through more populous communities than did the western route, the through mail between Washington and New Orleans was not carried along it until the latter part of 1827.<sup>49</sup> This accounts for the later development of stage facilities on the road between Milledgeville, Montgomery, and Mobile. The first stage route from Montgomery eastward was established in 1821. At first only one trip a week was made, but this was increased in 1823 to two trips weekly. Not until 1826 was there a regular line established between Montgomery and Milledgeville giving three trips weekly.<sup>50</sup> It was during the next year that the through mail to New Orleans began to come this way. It was carried from Montgomery to Mobile in two-horse wagons, from Mobile to Pascagoula by sulkey, and from Pascagoula to New Orleans by steam packet.<sup>51</sup>

This is as far as the development of transportation through Alabama went during the period under review, but a great deal of futile discussion was aroused by the Congressional act of 1824 which provided for the survey of a system of internal improvements. Calhoun, in his report on the subject, stated that a highway from Washington to New Orleans would be best calculated to further the interests of that section and of the country lying south of the Capitol City; and the survey of three separate routes was planned. The first of these was to intersect the eastward-flowing rivers at their fall lines; the second was to lie between this and the Appalachian Mountains; and the third was to pass down the valley beyond the mountains.<sup>52</sup> The surveys were accordingly made. The routes recommended in the first two cases were already followed by lines of travel. The first one lay through the Southern capitals, passing on to Mobile. The second diverged from this in northern Virginia and passed through the piedmont towns of Petersburg, Salisbury, Greenville, and Athens, rejoining the

<sup>49</sup> House Reports, No. 48, 20 Cong., 1 Sess., 176.

<sup>50</sup> Blue, *History of Montgomery*, 11-12; *Alabama Journal*, June 23 and 30, 1826.

<sup>51</sup> *Mobile Register*, Nov. 24, 1827; House Reports, No. 63, 20 Cong., 2. Sess.

<sup>52</sup> American State Papers, Military, III, 137-138.

other route near where it entered Alabama. But the third route differed from that already established. After passing through the valley of Virginia to Knoxville, instead of proceeding to Huntsville, it followed the valley of the Tennessee to where Chattanooga now stands, then, paralleling Lookout Mountain, passed into the valley of the Cahawba. From Centreville, at the falls of the Cahawba, it turned westward and passed out of the State by way of Demopolis.<sup>53</sup>

This route followed the course of the rivers and valleys, and, theoretically, was perhaps the best. But it had the disadvantage of Jackson's Military Road in that it did not follow an established route of travel. The Huntsville people proclaimed loudly that the route through their town should be surveyed, and they had their way.<sup>54</sup> The mail then took this course to New Orleans, and the Postmaster General favored the route. After the survey was made, no further action was ever taken. The Old South stood opposed to the policy of internal improvements, and, shortly, with Jackson's aid, it was able to restrain the desires of those who would have the general Government construct a system of communication for the country.

Commercially distant as were the two sections of Alabama, there was necessarily some communication between them. The first route traveled from north to south seems to have been the portage between the Muscle Shoals and the head of navigation on the Tombigbee at Cotton Gin Port. Pioneers floating down the Tennessee took this trail in order to reach the settlements in the neighborhood of St. Stephens.<sup>55</sup> Jackson, in the Creek War, cut a road from Huntsville southward through the country east of the Coosa River and on to the place where Fort Jackson was established at the confluence of the Coosa with the Tallapoosa.<sup>56</sup> By this route travelers were enabled to reach the Federal Road in the neighborhood of Montgomery.

Yet there was but one passage between north and south Alabama which came to be traveled with frequency, and that

---

<sup>53</sup> House Executive Documents, No. 156, 19 Cong., 1 Sess., IX; House Reports, No. 48, 20 Cong., 1 Sess., I; American State Papers, Military, III, 109; Huntsville *Democrat*, Sept. 7, 1827.

<sup>54</sup> House Executive Documents, No. 125, 20 Cong., 1 Sess., III; *Southern Advocate*; Jan. 13, 1826, letter from Gabriel Moore.

<sup>55</sup> Pickett, *History of Alabama*, 466-479.

<sup>56</sup> Streit, *Marshall County*, VIII.

was the one which led from Huntsville through Jones Valley to Tuscaloosa at the head of navigation on the Black Warrior.<sup>57</sup> The road through the Valley was good, and much produce came down from Tennessee and reached central and southern Alabama by this way.<sup>58</sup>

---

<sup>57</sup> Warden, *United States*, III, 39.

<sup>58</sup> *Alabama Republican*, March 1, 1822.

## CHAPTER IX.

### THE COMMERCIAL SITUATION.

The lack of a well developed financial system in the United States rendered commercial transactions much more complicated in the 'twenties than similar business would be today. Instead of a currency resting upon the credit of the Government and of uniform value, there were only bank notes, the value of which depended upon the credit of the issuing banks.

The first Bank of the United States had done much to stabilize the condition of the currency, but this institution had gone out of operation in 1811 and the end of the War of 1812 found the country flooded with paper money which was no longer redeemed in specie by the banks which issued it. It was during this period that settlers began to find their way into the Alabama country in increasing numbers, and practically the only money which permeated this frontier consisted of the depreciated notes of the banks of Georgia.<sup>1</sup>

It has been explained<sup>2</sup> how the state banks were forced to resume specie payments when the second Bank of the United States went into operation in 1817, and how the immigrants to Alabama were supplied with funds by the numerous new banks which sprang up in Tennessee and Kentucky in 1818. But the financial stress of 1819 caused these institutions to close their doors and leave their notes to circulate at a depreciated value in the western country.

In 1816 the legislature of Mississippi Territory had chartered the Merchants' and Planters' Bank of Huntsville, and in 1818 the Tombeckbee Bank of St. Stephens and the Bank of Mobile were chartered by the Alabama Territory. The two last-named of these institutions were not seriously affected by the events in Tennessee, for there were few commercial ties between south Alabama and that State; but the interests of the Huntsville region were closely bound up with those of the region to the northward, and the Huntsville bank was necessarily influenced by the affairs of the banks of Tennessee.

---

<sup>1</sup> Riley, *Conecuh County*, 22-25.

<sup>2</sup> Chapter VI.



The West was a debtor section ; it owed for lands, for slaves, for goods. The East was creditor and had to be paid. But when the banks of Tennessee suspended specie payments, their notes were no longer available for remittance to the East. One way around the difficulty lay in purchasing Huntsville notes with the Tennessee notes, and drawing specie on the former. This was done, and so great was the drain on the specie reserve of the Huntsville bank that it felt itself forced to suspend payments in 1820.<sup>3</sup> Its notes continued to be used, but they fell below par and usually circulated on an equality with notes from Tennessee. Specie and the notes of specie-paying banks, being at a premium, ceased to pass from hand to hand, and north Alabama was left with a depreciated currency.<sup>4</sup>

The value of a bank note depended not only upon the solvency of the issuing institution, but upon the chance of presenting it for payment in specie. Thus the value of a note in a locality at some distance from the place of issue would depend upon the commercial relations between the two places. If the merchants who held the notes had no remittances to make to the place where they could be redeemed, they would have to bear the expense of sending them for redemption and bringing back the specie. The value of the notes would be diminished by the amount of this expense. If, for instance, it cost five per cent. to collect in this way, notes would be worth only ninety-five per cent. of their face value. But if the merchants had remittances to make, notes would be more convenient for that purpose than specie and they would command their full value. In fact, if the remittance to be made outran the supply of notes, the value of these might rise above their face value by the amount that it would cost to ship specie in their stead. For instance, if it cost three dollars to send a hundred in specie, a hundred dollar note would be worth a hundred and three dollars to a merchant who had remittances to make.

This situation is brought out by the condition of affairs in Alabama. The Georgia and South Carolina notes, which formed the bulk of currency in the southern part of the State were worth about four per cent. less than specie in the Tennessee Valley because there was very little business between

<sup>3</sup> American State Papers, Finance, III, 765-766.

<sup>4</sup> *Alabama Republican*, Sept. 22, 1820, advertisement of P. Yeatman & Co.; *Ibid.*, Oct. 6, 1820; also statistics collected on bank note exchange from newspapers.

that section and the country directly to the south or east of it. The notes of New Orleans banks were usually on a par with these because the cotton sent down to the City was more than sufficient to cover all remittances for goods. But, on the other hand, the notes on Virginia banks and on the banks of Baltimore, Philadelphia, and New York were always nearly equal to specie because the Tennessee Valley imported its manufactured goods through the Eastern cities and obtained its agricultural produce from the Ohio River region and from Tennessee. Eastern notes could be used to pay the East directly, or they could be employed with equal facility to pay the West, for the latter section was in debt to the former and anxious to have funds for remittance.<sup>5</sup>

So difficult was communication between the two sections of the State that the trade of the southern section was entirely distinct from that of the northern. Not only did the towns along the rivers send their cotton down to Mobile, but the central hilly region also forwarded its crop by way of Tuscaloosa and Montgomery. Some of the staple was shipped directly from Mobile to European ports, but the greater part of it went to Eastern cities, principally New York.<sup>6</sup> An amount almost as great, consisting largely of the best grades, which could be passed off as the Louisiana product, was sent to New Orleans to pay for the corn, pork, flour, and whisky which came down from the Ohio River region and which were purchased by the merchants of Mobile to be sent up the Alabama and Tombigbee Rivers to the interior of the State.<sup>7</sup>

In the trade between Mobile and the Eastern cities, there was a balance in favor of Mobile, more cotton being shipped than was necessary to pay for the imports which were received in return. As a result, there was a balance due the Southern merchants which had to be paid in cash. But in the trade with New Orleans the cotton shipped was not sufficient to pay for the produce that was imported, and the Mobile merchants had to use their cash to pay the difference.<sup>8</sup> In other words, the money which the planters of southern Alabama received for their cotton was spent largely in payment for corn,

<sup>5</sup> Statistics on bank note exchange in Huntsville and Tuscumbia, collected from newspapers.

<sup>6</sup> *Mobile Register*, Oct. 5, 1824. Exports for the year 1824 included 14,990 bales of cotton to New York, 13,094 to New Orleans, and 8,778 to Liverpool.

<sup>7</sup> *Mobile Register*, Nov. 7, 1822; Feb. 17, 1824.

<sup>8</sup> Biddle Papers, John Hunter to Nicholas Biddle, Jan. 6, 1827.

pork, flour, and whisky which were brought down the Ohio and Cumberland Rivers to New Orleans, and shipped thence to Mobile.

The larger planters usually went down to Mobile once a year to transact their business with the merchants of the port; but the smaller producers had to do their business with country merchants who bought their goods in Mobile and transported them to the interior. These merchants did a local "factorage" business, which consisted in "advancing" supplies to farmers and taking their cotton in payment when the crop was made, a balance being struck once a year. The transactions between the larger planters and the merchants in the principal towns were perhaps frequently on this same basis.<sup>9</sup> This was the method whereby the cotton producer secured capital to finance his operations throughout the year. This capital was obtained from the local merchants in the first instance, but these dealers were financed by the Eastern merchants for whom they purchased the staple; and in this way the East furnished capital for the production of cotton.

During the early 'twenties, when the country was just being opened up, money was scarce in southern Alabama and many complaints were heard upon the subject;<sup>10</sup> yet the notes of the local banks, as well as those of South Carolina and Georgia, furnished a sound, though limited, currency.<sup>11</sup> So complete was the commercial separation between the two sections of the State, that each kept to its own medium of exchange with practically no interference from the other. Aft-

<sup>9</sup> See *The Cotton Factorage System of the Southern States*, by Alfred H. Stone, *American Historical Review*, XX, 557-565. This system came to be the usual practice, but whether it was completely developed during the 'twenties cannot be stated definitely. Merchants frequently advertised that they would advance on cotton turned over to them for shipment, but a committee of the legislature estimated in 1826 that two-thirds of the cotton shipped to Mobile was sold by the negotiation of bills of exchange, and the banks of that town did a large business in such paper. The fact that the planters received payments in these bills indicates that the local merchants were hardly more than purchasing agents for their Eastern correspondents.

Another indication of sales on a cash basis is the prevalence of auctions in Mobile at this time. It was customary to beat a drum as an announcement of the sale, and the noise made in this way came to be such a nuisance that complaint was made in the newspapers. But country merchants doubtless made advances to the small producers in their neighborhood from the very first. See Alabama, House Journal, 1826, 80; *Southern Advocate*, May 12, 1826; *Mobile Register*, April 21, 1823, and Jan. 17, 1824.

<sup>10</sup> Alabama, Senate Journal, 1819, 188-190.

<sup>11</sup> American State Papers, Finance, IV, 745.

er business conditions became more settled, the notes of South Carolina and Georgia banks ceased to pass at their face value because of the lack of trade between Mobile and those states. A currency sufficient for practical purposes was furnished by local banks, the Bank of the United States, and the New Orleans banks.<sup>12</sup>

The specie foundation upon which all these notes rested was very slight, judged by modern standards of safety. Both gold and silver were legal tender, according to law, but according to the market prices of the metals, a gold dollar was worth more than was one of silver. The result of this situation was that silver passed from hand to hand, while gold was withdrawn from circulation and a premium had to be paid to obtain it.

But even silver was scarce. There had been a profit made out of sending silver dollars to Latin-American countries and exchanging them on equal terms for the Spanish dollars, or pieces of eight *reals*, which were a little heavier. These foreign coins were brought back and melted down because the silver in them was worth a little more than a dollar according to our monetary standard. Hence there was left for circulation in this country only the Spanish dollars which were too light to afford a profit in the bullion market, and a certain amount of fractional Spanish coin.

This situation had caused Jefferson to suspend the coinage of silver dollars in 1806 and none had been produced since.<sup>13</sup> Spanish, Mexican, and other foreign coins made up our supply of specie, and it afforded a very light reserve against the notes which were issued by the banks, nor were there nearly enough of the smaller coins to serve the ordinary purposes of trade. A remedy was sought in the issue of "change tickets," which were merely bits of paper purporting to be worth twenty-five, fifty or seventy-five cents. They were signed by the issuer and were supposed to be redeemable for specie, but, since there was a demand for them, they were expected to remain afloat. This was a very profitable form of printing and it was indulged in by business houses and municipal authorities.<sup>14</sup> The irregularity in the issuance of such tickets made this practice a great nuisance to the community. Forgeries were easy, and the country was flooded with the paper

---

<sup>12</sup> *Mobile Register*, Oct. 29, 1823, and Aug. 30, 1828.

<sup>13</sup> White, *Money and Banking*, 33-34.

<sup>14</sup> *Alabama Republican*, Nov. 10, 1820.

of various uncertain houses. These considerations finally induced the State to take the matter up; the issuance of change tickets by private firms was forbidden and the government undertook to furnish the people with a lawful supply.<sup>15</sup>

Such was the condition of the currency in Alabama; but the man who had cotton to sell was affected not only by local conditions, but by national and international trade relations as well. The crop of Alabama was sold largely through Mobile and New Orleans merchants, who in turn disposed of the bulk of it, directly or indirectly, in the British market. The American merchant collected his account by drawing a bill of exchange on the British purchaser and disposing of this to some other American merchant who was in need of funds to remit to England.

During the period following the War of 1812, America was importing more than she was exporting and the bills of exchange drawn by exporters were not sufficient to meet the demand of the importers who needed funds for remittance. The result was that some of the importers had to send gold to pay their debt and this operation cost about ten per cent. It normally cost only about five per cent. to ship gold to England, but that country was on a gold basis and nothing but silver was circulating in this country. Consequently, the man who had a remittance to make in specie had to take silver at the current rate and purchase gold with it at about five per cent. advance. This premium on gold, added to the expense of shipment, accounts for the ten per cent. which it cost to send specie to London. Now the man who could buy a bill of exchange on London to cover his debt was willing to pay—and the competition for such bills forced him to pay—a premium of about ten per cent. over its face value.<sup>16</sup>

The Mobile merchants usually transacted their foreign business through New York firms, and received the proceeds of their foreign exchange in drafts on New York. Since, after the first few years of expansion, the cotton crop of south Alabama brought in more of these than could be used for remittances to New York, the balance had to be sent for collection in specie, and it cost about three per cent. to bring the specie from New York to Mobile. Hence New York paper passed at about three per cent. below its face value in the Alabama port, and the local merchant, not caring to stand the loss of

<sup>15</sup> *Ibid.*, May 18, 1821, June 29, 1821; *Cahawba Press*, June 8, 1822.

<sup>16</sup> Statistics on London exchange, collected from newspapers; *Alabama Republican*, Feb. 12, 1822, extract from the *National Gazette*.

the three per cent., made a practice of remitting to the planter in New York funds, leaving the latter to pay the cost of converting them into current money.<sup>17</sup> Yet, as a total result, there was a gain of about seven per cent. to the cotton producer because of the condition of trade-balance between the cotton region and the East on the one hand, and between this Country and England on the other.

It must not be understood from this discussion, however, that there was a trade balance in favor of Alabama as against the rest of the world and that specie was pouring in. While money was coming in from New York, it was all going out in other directions, and the State was accumulating no capital in cash. Like all newly opened country, Alabama was in debt.<sup>18</sup> The settlers owed for their lands and slaves, and for consumable goods. What they made from their crops, they invested in their establishments and there was no capital for commercial enterprises. This was doubtless due largely to the fact that cotton planting was the only occupation which was sure to give social prestige. Merchandising was carried on to a large extent by men from the North, and it was not regarded with great esteem by the agricultural community. The merchant was likely to be looked upon by the planter as a grasping inferior, while the poor man was apt to consider him an economic enemy.

Speculation, land grabbing, and graft of all kinds were the necessary accompaniments of a rush into new country where all were scrambling for a place and where the strong could use his strength to greatest advantage against the weak. The man without capital was largely at the mercy of him who had it, as is well illustrated by the situation in regard to the sale of the public lands.

The planter who bought his land and settled down to the business of raising cotton was not looked on with disfavor by any part of the people, for his profits did not come from his neighbors. But the man who used his capital in a commercial way made his profits largely out of the community, and he often made too much. Thus the poorer men frequently looked with suspicion upon those who did business with them, which fact manifests itself forcibly in connection with the banking question.

<sup>17</sup> Alabama, House Journal, 1826, 80; American State Papers, Finance, III, 762; statistics on domestic exchange, collected from newspapers.

<sup>18</sup> Alabama, Senate Journal, 1821, 21, Message of Governor Pickens.

## CHAPTER X.

---

### THE BANK QUESTION.

The money which cotton brought into Alabama during the 'twenties went out largely through the land offices and for slaves, and the State was left without commercial capital. Funds were needed to finance the cotton crop; to promote agricultural expansion; and, especially, to furnish the basis for a sufficient circulating medium. The first of these needs was met by the New York cotton dealers, for they financed merchants in the South who bought the staple on their account; agricultural expansion was provided for by the planter's reinvestment of his profits; but there seemed to be no means of securing a sufficient circulating medium except by local banks, and this expedient was resorted to.

The difficult problem was to obtain sufficient capital for investment in banking enterprises. As such institutions are conducted today, with solid value behind their paper dollars, they do not add greatly to the capital of the community, being merely organizations for its efficient use. If this had been the case in 1820, they would not have met the requirements of the Southwest. A multiplication of capital was expected of them—the creation of money where none existed before. Yet promising as were the prospects of these money-making machines, men would have invested their funds in lands rather than in banks had they not expected to borrow more than they put in—so great was the lure of cotton in the eyes of the planting community. This situation must be understood before the bank question can be made clear.

The charter of the Merchants' and Planters' Bank of Huntsville was granted by the legislature of Mississippi Territory in 1816, while the Mobile and St. Stephens banks were granted theirs by the legislature of Alabama Territory in 1818, yet the provisions of all three documents were very similar. The capital of each institution was limited to half a million dollars, a minority of which was reserved to the territorial government in each case; no interest over six per cent. might be charged; and the issue of notes was not to exceed three times

the amount of capital actually paid in.<sup>1</sup> This last provision indicates that the authorities were more solicitous for a currency than they were for financial safety. They evidently expected the banks to be money-manufacturing institutions, and their hopes were not disappointed.

In September, 1818, the Tombeckbee Bank, of St. Stephens, went into operation with only \$7,700 of its stock subscribed for. Israel Pickens, a lawyer of St. Stephens, and register of the land office there, was elected president; and George S. Gaines, for a long time factor for the Choctaw Indians, was chosen secretary.<sup>2</sup> In January, 1820, Pickens wrote to the Secretary of the Treasury that the Mobile Bank had but a nominal existence. He stated that that institution, which had been chartered in 1818, had had \$70,000 subscribed to its capital, and that one-eighth of this, or about \$8,000 had been paid in specie. An agent was sent North with a part of this sum to secure the materials for putting the bank in operation, but while he was gone, the bank's balance was lost by robbery. Now the agents of the Mobile institution were supposed to be drawing upon the Tombeckbee Bank for specie with which to put their corporation on its feet.<sup>3</sup>

Meantime, the Huntsville bank, being an older institution, was doing business in a larger way. In August, 1819, it had a capital of \$164,000 and had discounted to the extent of \$408,000.<sup>4</sup> The Secretary of the Treasury wrote to Leroy Pope, president of this bank,<sup>5</sup> as well as to the president of the Tombeckbee Bank,<sup>6</sup> and expostulated on the reckless way in which their affairs were being conducted; but no practical reform was effected. Demand for accommodation was great, capital was limited, and the temptation to profit was too strong to be withstood.

The first evident result of this situation was the suspension of specie payments by the Huntsville bank in 1820. It has already been explained how the suspension of payments by the Tennessee banks in 1819 was followed by a drain of specie from the Huntsville bank, which was too heavy for an institution whose circulation far exceeded its specie reserve.<sup>7</sup>

<sup>1</sup> Toulmin, Alabama Code of 1823.

<sup>2</sup> American State Papers, Finance, III, 767-768.

<sup>3</sup> American State Papers, Finance, IV, 740.

<sup>4</sup> Ibid., III, 778-782.

<sup>5</sup> Ibid., Finance, III, 764.

<sup>6</sup> Ibid., Finance, III, 768.

<sup>7</sup> Ibid., Finance, III, 765-766.



It was believed, however, that the bank was sound, and its notes continued to circulate on a par with those of the Tennessee banks, and the two together made up the currency of northern Alabama.

On account of the lack of commercial relations between the two sections of the State, this financial trouble did not communicate itself to the south, where the two local banks continued to pay specie and where the bulk of the circulation consisted of notes of the solvent banks of Georgia. The equilibrium of Alabama would hardly have been disturbed had not the situation developed a political as well as a commercial phase. As long as the Huntsville bank paid specie on its notes, they were, of course received by the State in payment of taxes. But when the bank suspended payments, the legislature refused to debar its notes from acceptance.<sup>8</sup> The result of this was that all who could procure the depreciated notes turned them in to the Treasury instead of sound funds, and the entire community suffered by the situation. In addition to this, the legislature, during the same session, emitted an issue of treasury notes which were made payable in Huntsville currency. The natural result was that they at once fell to a par with the Huntsville notes, and the State lost the difference.

Though the legislature could hardly have misunderstood the inevitable result of the course which it took in this matter, the Governor defended its action by arguing that the people of northern Alabama could not secure other funds than the notes of the Huntsville bank, and that it would be unjust to refuse to let them pay their taxes with this money.<sup>9</sup> This governor was not the William Wyatt Bibb who had presided over the Territory of Alabama and had been elected to the chief office under the new State government. He had died in 1820 from the effects of a fall from his horse, and was succeeded by his brother, Thomas Bibb, president of the State Senate.<sup>10</sup> It is interesting to note in this connection that Thomas Bibb was a director of the Huntsville bank in 1823.<sup>11</sup>

This confusion in financial affairs brought out more strongly than ever the desire for a State bank. The three private banks in operation had been chartered under territorial gov-

<sup>8</sup> *Cahawba Press*, Oct. 15, 1821.

<sup>9</sup> Alabama, Senate Journal, 1821, 8-9.

<sup>10</sup> Pickett, *History of Alabama*, 666-668.

<sup>11</sup> Huntsville Democrat, Dec. 16, 1823.

ernment and there was no intention of chartering any new ones under the State. The constitution provided for a bank of the Commonwealth, and efforts were soon on foot to found such an institution.

The first step in this direction was taken by the legislature in 1820. Provision was made for a State bank with a capital of two million dollars. Half of the stock was to be reserved to the State and the government was to choose the president and six of the twelve directors, thus controlling the institution.<sup>12</sup> Books were opened for public subscription, but no capital was found for investment in such a bank, and the scheme fell through.<sup>13</sup>

But the idea was not abandoned. In 1821 Israel Pickens succeeded Thomas Bibb as Governor. Pickens came to Alabama from North Carolina in 1817, having served his native State in Congress since 1811. It has been mentioned that he took up his residence at St. Stephens and became president of the Tombeckbee Bank. Before Bibb retired from office, commissioners had been appointed by the legislature to negotiate with the private banks and to discover on what terms they would be willing to become branches of a State bank.<sup>14</sup> The constitution had provided that such an arrangement might be made, and, since other capital did not seem to be obtainable, the idea of founding a State institution through the instrumentality of those already existing appealed to many. A bill for carrying this plan into effect was passed by the legislature, but was vetoed by Governor Pickens at the inception of his term of office.<sup>15</sup> If allowed to become law, this measure would have committed the credit of the State into the hands of a few bankers without any careful scrutiny of their affairs. Considering the way in which the private banks of Alabama had been conducted, such a move would have been dangerous, to say the least. There were many who praised Pickens for stepping in to prevent it and there were many who blamed him for his action.

The political division in Alabama had previously been due to the rivalry between the north and the south of the State, or to the antagonism which grew up against those Georgia men who, through the friendship of William H. Crawford, en-

---

<sup>12</sup> Toulmin, *Alabama Code of 1823*.

<sup>13</sup> *Alabama Republican*, June 29, 1821.

<sup>14</sup> *Alabama, Senate Journal*, 1821, 8-9.

<sup>15</sup> *Alabama, House Journal*, 1821, 227.

joyed a practical monopoly of the Federal patronage. Now the bank question was injected into the midst of the situation.

Though Pickens was not a Georgia man, his being made register of the land office at St. Stephens would indicate that he was not at odds with them. It is significant that in 1819 he wrote a letter endorsing Dr. Henry Chambers, who was running against Col. John Crowell for the seat in the Lower House of Congress.<sup>16</sup> Dr. Chambers was from the Tennessee Valley and represented the Georgia faction, while Crowell was from the southern part of the State and not a Georgia man. In 1821 it was Chambers who opposed Pickens for the governorship, but he was a weak candidate and carried only a few of the counties in his own section.<sup>17</sup>

No political issues seem to have been brought forward in this campaign. The question of the currency and the State bank was before the people and had been discussed at random, but no definite line of action had been proposed. Pickens' attitude on the subject does not appear to have been canvassed, but he no sooner took his stand than a general agitation began.

The Huntsville bank had profited, or was thought to have profited, at the expense of the people of the State, and the capital of this institution was largely in the hands of men from Georgia. The feeling against the bank was added to the feeling against the Crawford faction, and those who shared these sentiments rose up to proclaim Pickens the man who had saved his State from the hands of the spoilers.<sup>18</sup>

The veto of the charter was followed by an attack on the Huntsville bank. Its notes were debarred from acceptance in payment of debts to the State,<sup>19</sup> and this, together with the failure of the prospect that the institution would become a branch of the State bank, led to a rapid decline in their value. In all this, the newspapers of the State, which were edited largely by Adams men, supported the act of the Governor, the *Alabama Republican*, of Huntsville, being a notable exception.

But when it came to the constructive side of Pickens' program, there was a greater difference of opinion. Private capital had failed to come to the support of the State managed bank in 1820, and the existing banks were not to be trust-

---

<sup>16</sup> *Cahawba Press*, July 30, 1821.

<sup>17</sup> *Alabama House Journal*, 1822, 25.

<sup>18</sup> *Cahawba Press*, Feb. 4, 1822, April 27, 1822, May 25, 1822; St. Stephens *Halcyon*, Feb. 9, 1822.

<sup>19</sup> *Huntsville Democrat*, July 20, 1824.

ed with the destinies of a public institution. There was but one other possible chance, and the Governor set his face in that direction: the State was to furnish its own capital and direct its own bank for the benefit of the people. For procuring the necessary funds, the State had but one recourse: the lands which had been granted to it by the National Government. It was proposed that the proceeds from the sale of these lands be invested in the bank and that six per cent. interest be paid on the funds and devoted to the purpose for which the original grants had been made. The management of the institution was to be in the hands of a president and board of directors chosen by the legislature.<sup>20</sup>

The bearing of such a proposition in a State where the majority of the people were hard-pressed for money can easily be understood. Those who had some capital and a fairly intelligent interest in economic affairs would oppose it. Those who had no capital, wanted cheap money, and knew little of business methods, would favor it with all the ardor of frontier democracy. In other words, here was the material for a political cleavage along economical lines, but the Governor who gave the popular party its rallying-ground was not a Jackson man.

Discussion of the question went on with unabated earnestness, but without practical results, during the whole of Pickens' first term in office. The *Alabama Republican*, of Huntsville, showed an unmistakable leaning toward the private banks, while the Mobile papers contended for a commercial rather than a democratic institution. It was argued with reason that unless the bank was located at the center of trade, its notes would not circulate at par at any distance from the place where they were issued and could be redeemed.<sup>21</sup> It was also questioned whether a bank would be efficiently administered under the auspices of the legislature. But the striking feature in the discussion was the appearance of a new paper in Huntsville called the *Democrat*, and edited by a man from Kentucky. In the fall of 1823 this publication suddenly came forward and announced itself the champion of "the people."<sup>22</sup> The people had been without a leader, it said, and had suffered many things at the hands of the aristocrats. The

<sup>20</sup> Alabama, Senate Journal, 1821, 27-34; House Journal, 1822, 9 et seq.

<sup>21</sup> *Alabama Republican*, Aug. 24, 1821; *Mobile Argus*, Nov. 6, 1823; *Mobile Advertiser*, Dec. 15, 1823.

<sup>22</sup> *Alabama Republican*, Oct. 17, 1823.

president of the Huntsville bank was accused of several kinds of rascality, and the administration of the corporation was condemned as a robbery of the poor. It was alleged that cotton had been shipped to New York, sold there for sound money and the proceeds brought back to Huntsville and exchanged by the bank for its own notes, which it took at a discount.<sup>23</sup> This process was known as "shaving," and the term "shavers" was applied in opprobrium to those connected with the bank. Color is lent to charges of this kind by the fact that Pope, the president of the bank, who was also pension agent, paid pensioners in the depreciated notes of his institution, and was for this dismissed from his office by the Treasury Department.<sup>24</sup>

Pickens was again candidate for the governorship in 1823. The bank question was made a leading issue of the campaign,<sup>25</sup> and his second election was followed shortly by the incorporation of the Bank of the State of Alabama. The capital was to be derived from the sale of lands donated to the State for the founding of a university, from the 1640 acres donated for a seat of government, from the three per cent. which was given out of the sales of Federal lands for the purpose of constructing roads within the State, and from several minor sources. The amount of university money which could be invested in this manner was limited to \$100,000, and \$100,000 additional was to be borrowed on the credit of the State. It was provided that six per cent. was to be paid on all funds, and the interest on the university fund, the "three per cent." fund, and other special funds, was to be devoted to the object for which the original donations had been made. The bank was to be founded at the seat of government, the president and directors were to be chosen by the legislature, and all discounts were to be apportioned among the several counties in proportion to their representation in the legislature.<sup>26</sup> In the Senate, the vote on this measure was thirteen to six, those who were in the negative coming from the more commercial communities.<sup>27</sup>

---

<sup>23</sup> Huntsville *Democrat*, Oct. 14, 1823; *Alabama Republican*, Dec. 12, 1823.

<sup>24</sup> Huntsville *Democrat*, March 30, 1824; *Franklin Enquirer*, Apr. 7, 1824.

<sup>25</sup> *Alabama Republican*, June 13, 1823; *Mobile Argus*, July 22, 1823.

<sup>26</sup> Act. of Dec. 20, 1823.

<sup>27</sup> Alabama, Senate Journal, 1823, 65.

In July, 1824, the bank was organized with a capital slightly in excess of \$200,000, half of which was derived from the resources of the State, and the other half of which was borrowed.<sup>28</sup> Its discounts soon exceeded its capital, and its notes began to constitute an appreciable part of the local circulation.

This addition to the amount of available money came at an opportune time, for several of the older issues of notes were shortly withdrawn from general use. The war against the Huntsville bank was carried on until 1825, when, on account of its failure to redeem a pledge to resume specie payments, its charter was annulled,<sup>29</sup> and though all its notes were not withdrawn, they ceased to form any appreciable part of the circulating medium of the Tennessee Valley.

The Tennessee notes, which made up the greater part of the currency of this section, circulated in abundance as long as they were not redeemable, for Eastern merchants who collected debts in Tennessee funds found it profitable to purchase cotton with them rather than to take them into a part of the country where they were at a great discount.<sup>30</sup> But in 1826, the Tennessee banks resumed specie payments and their notes ceased to circulate extensively in Alabama.<sup>31</sup> Thus the Huntsville region was left almost destitute of a currency, and "change tickets" appeared in great numbers in spite of the fact that their issuance was illegal.<sup>32</sup> A planter who sold his cotton in New Orleans and received a draft on New York in payment could realize cash on his paper by exchanging it in Nashville for "post notes" issued by the firm of Yeatman and Woods. These notes were made payable in Philadelphia several months after date, which arrangement put them at a discount and kept them in circulation, so that they came to make up a large part of the currency in northern Alabama.<sup>33</sup>

In the meantime, the southern part of the State was having its troubles. In 1826 the United States Bank established a branch at Mobile in spite of the protests of those who believed that it would be a menace to the Bank of Alabama.<sup>34</sup> The

<sup>28</sup> Alabama, Senate Journal, 1824, 7.

<sup>29</sup> Alabama, Senate Journal, 1825; 10; *Alabama Republican*, Feb. 18, 1825.

<sup>30</sup> Huntsville *Democrat*, April 27, 1824.

<sup>31</sup> *Southern Advocate*, Sept. 8, 1826, Sept. 15, 1826.

<sup>32</sup> Huntsville *Democrat*, March 9, 1827.

<sup>33</sup> *Southern Advocate*, Jan. 5, 1827.

<sup>34</sup> *Mobile Register*, Nov. 18, 1826; *Alabama Journal*, May 6, 1826; Alabama, Senate Journal, 1826, 9.

branch bank refused to receive the notes of the local banks, but made an exception in the case of the Mobile bank provided that it would redeem its obligations at frequent intervals. In turn, the Mobile bank, in order to protect itself, refused to receive the notes of the St. Stephens bank and of the State bank unless they would redeem them at frequent intervals in Mobile. This was necessary because there was a flow of currency from the interior toward Mobile, but no counter-flow to balance the situation. The State bank made terms, but the St. Stephens bank refused to do so and seems to have damaged its credit by the stand which it took. At any rate, it closed its doors in 1827 and its notes ceased to pass as currency.<sup>35</sup>

By 1828 the capital of the State bank had increased to \$409,000, and arrangements were made for borrowing another \$100,000.<sup>36</sup> In addition to this, permission had been obtained from Congress for selling the sixteenth section in each township which had been donated for the establishment of public schools, and provision was made by the legislature for investing the proceeds in the bank.<sup>37</sup> The discounts of the institution were now more than \$600,000; its notes in circulation amounted to \$395,000; and its cash funds to \$294,000.<sup>38</sup> Here was an establishment of portentous possibilities.

---

<sup>35</sup> Alabama, Senate Journal, 1827, 184-185; Huntsville *Democrat*, April 13, 1827; *Mobile Register*, June 25, 1828.

<sup>36</sup> Act. of Jan. 12, 1828.

<sup>37</sup> American State Papers, Lands, VI, 891; *Southern Advocate*, Feb. 1, 1828.

<sup>38</sup> Alabama, Senate Journal, 1828, 18.

## CHAPTER XI

---

### POLITICS AND THE ELECTION OF 1824

Something has been said of the influence of Georgia on the early politics of Alabama. It remains to trace the consequences of the situation. The fraudulent Yazoo land speculation had split the former state into two factions; those who attacked and annulled the sales were led by General James Jackson, while the defenders adhered to General Elijah Clarke. In time the leadership of the Jackson party passed into the hands of William H. Crawford, while the opposition was maintained by John Clarke, son of the General.<sup>1</sup>

Between these factions there were no standing political differences, but the rivalry between the leaders on each side was backed by certain economic and sectional differences between their respective followings. There had been two centers of settlement in Georgia: one along the tide-water region where sea-island cotton formed the basis for a planting aristocracy; and the other in the piedmont region where the Savannah River cut through the red hills and afforded transportation facilities for planters of upland cotton. The older settlements were those of the tide-water region, but after the Revolution, while upland cotton was coming into its own, numerous emigrants had come from Virginia and North Carolina and established themselves in the piedmont section. Elbert County came to be a center of Virginia influence, while Wilkes County, just to the northward, came to be a center of North Carolina influence. A marked rivalry grew up between the two groups of settlers, both of which tended toward exclusiveness.

James Jackson, and later, Troup, stood for the tide-water aristocracy, while Clarke represented the plain men of the frontier sections of the State. Crawford was a Virginian of the piedmont section, and his co-operation with Jackson brought about an alliance of the two groups which they represented. The North Carolinians were thus thrown into the arms of the Clarke party.

---

<sup>1</sup> On the subject of the Georgia parties, see U. B. Phillips, *Georgia and State Rights*, Chap. IV.



The majority of the leading men of the State were of the Crawford faction and for a long time they succeeded in maintaining political control. When the new lands in Alabama were opened up, however, the exodus of cotton planters was a severe blow to the party. A substantial number of wealthy Georgians, including Leroy Pope and his son-in-law, John W. Walker, had gone from Elbert County and established Huntsville in 1809 and 1810. But it was in 1817 and 1818 that a great body of them bought land at the Government sales at Milledgeville and moved out into the basin of the Alabama River to become the back-bone of the planter class in that section.

It was during this time that Georgia's two Senators, Charles Tait and William W. Bibb, voted for a bill to increase the salaries of the members of their body, and thereby brought down a storm upon their heads which resulted in their withdrawal from Congress, and which was instrumental in causing them to remove to Alabama. Bibb at once became Governor of the new Territory; but Tait remained in the Senate until the end of his term, and then, statehood having been obtained for Alabama, reaped his reward for senatorial service by being made a district judge of the new commonwealth. These men were accompanied to Alabama by other strong supporters of Crawford, among whom was Bolling Hall, who had sat in the House of Representatives for his native state, and who now took up his residence in Autauga County across the river from Montgomery.

Governor Bibb was popular in Alabama, and Walker seems to have won his way to the Senate through sheer worth. Tait also had senatorial aspirations, but yielded to William R. King when jealousy of the Georgia group made it clear that it was dangerous to push too far. William H. Crawford was not so cautious, however, in dispensing the Federal patronage for the State. He controlled practically all appointments and his friends were invariably put into office except when it became expedient to shelve an opponent. Bait was held out to King in the hope of diverting him from his race for the Senate, but he refused to be diverted.<sup>2</sup> William Crawford, who succeeded Pickens as president of the Tombeckbee Bank, was district attorney and, at the same time, receiver for the St. Stephens land office. If the receiver had been irregular in his ac-

---

<sup>2</sup> Tait Papers, Wm. H. Crawford to C. Tait, Nov. 7, 1819.

counts, the attorney would hardly have been eager to prosecute the case!<sup>3</sup>

Such a condition as this necessarily aroused the anger of those who did not have a finger in the pie, and complaints of partisanship and inefficiency went up on all sides. It was not a struggle which would greatly concern the mass of the people, who were absorbed in other things, but it concerned the politicians and they, in turn, had some power to arouse the people.

This power seems to have been more limited than would be imagined. There were no parties, nor even any standing issues. The people, busy with their clearings and their crops, appear to have elected their more ambitious neighbors to go up to the legislature and relieve them of anxiety about all political questions excepting only such as concerned immediate economic interests. No serious attempt was made to arouse them until Pickens seized upon the bank question and made an issue of it.

The relation existing between the champion of the State Bank and the Crawford men is not easy to trace. It is stated that Pickens, then a Congressman from North Carolina, supported Crawford when he stood for the Presidency against Monroe in 1816. But when Crawford refused him the appointment as register of the land office at Cahawba, which place had been promised him by Dallas, Pickens turned against the Georgia men and threatened to become the head of an opposition.<sup>4</sup> It was probably Tait who secured for him the appointment as register of the land office at St. Stephens,<sup>5</sup> and this seems to have prevented hostilities until the gubernatorial campaign of 1821, when Pickens denied all connection with the Crawford party.<sup>6</sup>

It has been mentioned that Crawford stood for the aristocratic group in Georgia and that the majority of his followers who came to Alabama were planters of some means. The connection of a few of them with the unfortunate Huntsville bank made it possible for their enemies to call them "oppressors of the poor," and the fight for the State Bank was made a fight against the Georgia faction. The challenge was ac-

<sup>3</sup> *Mobile Argus*, March 3, 1823, letter copied from the *Franklin Gazette*.

<sup>4</sup> Hall Papers, Jack F. Ross to Bolling Hall, Aug. 25, 1821; Tait Papers, William H. Crawford to C. Tait, Nov. 27, 1819.

<sup>5</sup> Tait Papers, Wm. H. Crawford to C. Tait, Nov. 29, 1819.

<sup>6</sup> Bibb Papers, C. Tait to W. W. Bibb, Nov. 28, 1820.

cepted, and the Crawford men led the defense of the private banks, while their opponents combined against them to establish the "people's bank."<sup>7</sup>

It is an interesting alignment of factions that was brought about by this situation. Farmers on a small scale had come into Alabama primarily from Tennessee, Georgia, and South Carolina; but whatever their origin, they were preponderantly Jackson men. Among the planters there was no such unanimity. Those from Georgia were most numerous along the upper Alabama River, and they were the principal supporters of Crawford. Those from the Carolinas and Virginia predominated in the Tombigbee basin as far up as Tuscaloosa, and Adams was strongest in this section. In the Tennessee Valley, the Georgia planters mingled with the planters from Virginia and the Carolinas and produced a variety of political sentiments, the Georgia influence being strong in Madison County but dwindling away toward the west. On the bank question, the Adams planters were allied with the Jackson farmers to defeat the Crawford men.<sup>8</sup>

The election of Pickens was the beginning of hard times for the Georgia faction. They had at first made Alabama their own, and the new State was glad to have their powerful influence in Washington. Their monopoly of the Federal patronage raised up enemies among the politicians from other states. In the untimely death of Governor Bibb, they lost a strong leader. This misfortune was followed in 1823 by the death of Senator John W. Walker. These two men had won much respect in the community, and there were no others of equal caliber to take their places. In the contest to fill the vacant seat in the Senate, the Crawford men supported John McKinley, while their opponents, the "friends of the people," backed William Kelly. The latter won the contest by a narrow majority, and when the unexpired term was completed, he stood for re-election, being opposed this time by Dr. Henry Chambers. Chambers won the race and thereby restored the balance, for William R. King, who, like Pickens, was from North Carolina and no friend of the Georgia faction, retained

---

<sup>7</sup> *Alabama Republican*, March 25, 1824; *Huntsville Democrat*, Nov. 11, 1823, July 20, 1824.

<sup>8</sup> The origin of the population in different sections of the State has been discussed in Chapter III. The statement of the political tendencies of the various sections is based upon the attitude of the press and the presidential vote of 1824.

his seat continuously in the Senate for twenty-five years after Alabama became a State.<sup>9</sup>

But the Crawford men, while able to maintain a condition of political balance in the legislature, were not nearly so strong when elections went straight to the people. None of the early Congressmen were of their number, nor were they able to elect a governor after 1819. It is indeed surprising to consider how small was the group of men who all but dominated the legislature of the State. The planters were but few compared to the total number of settlers, nor did the Georgians constitute a majority of the planters, yet they made up the predominant class in an important section of the State and found their way into politics in relatively large numbers. This was possible because of their prominence as office-holders; because there were no organized parties; and because there was no standing antagonism between the planter and the farmer. There were politicians who wanted to teach the people to know their rights, and in the matter of the Bank, they succeeded in their aim. But ordinarily the people did not feel a great need of instruction. In the absence of parties, politics were largely personal. Only men of some station thought of running for office, and the lesser sort selected their favorite and voted for him without asking many questions as to his creed. While a study of the popular elections shows very clearly that the people knew what they wanted when a matter of political interest was put squarely before them, a comparison of the votes of the legislature indicates that popular control was, under ordinary circumstances, very slight.

Until the campaign of 1824 approached, local matters tended to push national issues into the background, and the reason was that there was a nearly unanimous agreement upon all Federal questions excepting as to who should be President after Monroe. Clay had a few strong friends in Alabama, but his advocacy of the tariff rendered him unpopular; and Crawford had no followers excepting the Georgia planters. The plain people were devotedly attached to Andrew Jackson, while Adams had strong support among the Carolina and Virginia planters. New Englanders were generally disliked in this section of the country and the popularity of Adams indi-

<sup>9</sup> *Columbia Press*, Dec. 14, 1822; *Huntsville Democrat*, July 20, 1824, Dec. 14, 1824. Dec. 21, 1824; *Alabama Republican* Dec. 17, 1824; Tait Papers, Wm. H. Crawford to C. Tait, Feb. 16, 1823; Hall Papers, Aug. 21, 1823.

cates that the conservative element entertained a strong prejudice against the aggressive democracy of the Jackson men. The support which Adams gave to the cause of internal improvements was an asset in a state where improvements were badly needed, and his friends claimed that he was safer on the question of the tariff than any of the other candidates.<sup>10</sup>

The tariff question was the disturbing one. Alabama was a unit in condemning the system of protection, and the supporters of Jackson found their greatest difficulty here. The hero of New Orleans voted for the increased duties that were established in 1824, and this fact was used against him by his enemies, nor could they have found a better weapon. It became necessary for the Jackson men to bestir themselves in the matter. A direct question on the subject was propounded to the General and his answer was published in the *Mobile Advertiser*. Here he stated clearly that he favored protection for those industries which were of military importance, such as the manufacture of iron and cheap woollen goods, but that he was otherwise for a revenue tariff only.<sup>11</sup> No clear case could be made for Adams, however, and the cause of Jackson was not seriously hurt by the issue.

A strong section of the local press favored Adams, and it was conceded that he would carry the southern part of the State, while Jackson was expected to carry the northern.<sup>12</sup> An attempt was made to have the presidential electors chosen by district with the hope that two of the five could be carried for the New England candidate,<sup>13</sup> but the plan was defeated and in 1823 the legislature declared Jackson to be the choice of the State.<sup>14</sup> So great was the popularity of the General that even his enemies had to speak respectfully of him. Those members of the legislature who voted against the nomination took the trouble to explain that they did so, not because of hostility, but because they did not consider the question a proper one

<sup>10</sup> *Alabama Republican*, May 21, 1824, Oct. 8, 1824; *Cahawba Press*, July 10, 1824; *Huntsville Democrat*, June 24, 1824.

<sup>11</sup> *Tuscaloosa Mirror*, May 29, 1824. Jackson did not refer simply to munitions of war, but meant to include all articles necessary to put the country in a condition of economic independence, considering this necessary to military safety. See letters to John Coffee, dated May 7, and June 18, 1824, in the Coffee correspondence.

<sup>12</sup> *Huntsville Democrat*, Aug. 24, 1824; *Alabama Republican*, August 8, Oct. 1, 1824.

<sup>13</sup> *Alabama*, Senate Journal, 1823, 12; *Alabama Republican*, Sept. 26, 1823.

<sup>14</sup> *Alabama*, Senate Journal, 1823, 82; House Journal, 1823, 77.

for legislative action.<sup>15</sup> Governor Pickens explained on the same grounds his failure to sign the nominating resolution.<sup>16</sup> Indeed, the loss of popularity which one suffered by opposing Jackson brought many men to a new way of thinking. Dr. Henry Chambers was backed by the Georgia group when he ran for the governorship in 1821 and 1823,<sup>17</sup> but he became a supporter of Jackson and was made presidential elector on the popular ticket in 1824. Nicholas Davis, who for five years was president of the State Senate, was an opponent of the State Bank and no friend of Jackson's,<sup>18</sup> but he so far gave way as to vote for the nomination by the legislature in 1823.

There was no regularly established political machinery in 1824, but co-operation was necessary in order to win a spirited contest, and this was accomplished in an informal but effective way. Public meetings of the friends of the several candidates were announced in the newspapers and held in the leading towns. These gatherings proposed electoral tickets and chose committees of correspondence. One of them, which was held at the court-house in Perry County on May 8, 1824, proposed that representatives be chosen by friends of Jackson in the various parts of the State and sent to a convention which should meet at Cahawba during the following session of the Supreme Court.<sup>19</sup> The friends of Adams and Crawford followed this example, and accordingly there were three conventions held in due time at the seat of government. These were informally constituted bodies, consisting partly of representatives from various public meetings and partly of men who came without any public authorization. The Jackson delegation appears to have been the most representative. It considered the electoral ticket which had been promulgated by the local press; made some changes in it; and appointed a correspondence committee for each judicial circuit, authorizing them to notify the nominated electors and to replace any who might decline to serve.<sup>20</sup> The other conventions followed much the same lines of procedure, and placed before the voters the electoral tickets which had already been generally agreed upon through the press.<sup>21</sup>

---

<sup>15</sup> Alabama, House Journal, 1823, 120-125.

<sup>16</sup> *Niles' Register*, XXV, 323-324, 362.

<sup>17</sup> *Greensboro Halcyon*, Nov. 1, 1823.

<sup>18</sup> Pickett, *History of Alabama*, 653-654.

<sup>19</sup> *Cahawba Press*, May 8, 1824.

<sup>20</sup> *Cahawba Press*, June 18, 1824.

<sup>21</sup> *Cahawba Press*, June 28, 1824, July 7, 1824.

When the returns from the election came in, it was found that Jackson had a majority in every county in the State except three,—Greene, Butler, and Montgomery.<sup>22</sup> This unexpected strength of the General emphasizes the very important point that it was not the editor, nor the politician, nor the planter who furnished the main support of Jackson, but the plain farmer who could vote more potently than he could talk. It became clear that the small farmer had the balance of power even in the counties where slaves were most numerous. He spoke his mind very clearly and carried his point when his mind was made up, but he did not differ from the planter on principle and never tried for separate control.

Some interesting information is obtainable from a study of the election of 1824. Over seventy-five per cent. of the vote went to Jackson in all the counties of the Tennessee Valley and the hilly region lying below it. The predominance of Tennesseans in the Valley and of small farmers in the hilly region accounts for this situation. The counties of the extreme southeast were also overwhelmingly for Jackson, and these, like the hill counties, had a minimum slave population. But in the basins of the Alabama and Tombigbee Rivers, the General failed of a majority in three counties and carried but two with a vote as high as seventy-five per cent. Here the Tennesseans were relatively few in numbers and the planters made up a greater proportion of the population. Crawford received an appreciable vote in only two counties, while Adams attracted the greater part of the opposition.

It is a significant fact that the Alabama-Tombigbee River basin, which later became the stronghold of Whigism, was carried for Jackson in 1824, yet with a smaller margin than he obtained in the other sections of the State. There was the nucleus here among the planters for a strong fight when circumstances should give them an argument which could attract allies.

---

<sup>22</sup> The returns are to be found in the Huntsville *Democrat* for Nov. 22, 1824, and in the *Cahwa Press* of the same date.

## CHAPTER XII.

---

### LOCAL POLITICS AND FEDERAL RELATIONS, 1824-1828.

After the election of 1824, there was a distinct change in the political situation in Alabama. No sooner was Jackson defeated than his friends announced their determination to "fight the battle o'er again,"<sup>1</sup> and their opponents recognized the futility of a further struggle against the General. The administration was able to hold a few scattered supporters, but even the *Southern Advocate*, of Huntsville, which had been an ardent friend of Adams before the election, now went over to the cause of Jackson, though this change was clearly one of letter rather than of spirit. Among the Crawford men the defection was even more general. Their hero was no longer in the race, and it was left for them to make the best terms they could for themselves. The new editor of the Huntsville *Democrat*, the acknowledged champion of "The People" in the State, admitted that he had supported Crawford in 1824,<sup>2</sup> but former allegiance was not held against any man in those days unless there was some special reason for doing so. When resolutions proposing Jackson for the presidency were passed by the legislature in 1827, their mover was no other than Dixon H. Lewis, nephew of Bolling Hall, and closely connected with all the supporters of Crawford who had led the Georgia faction in Alabama. Adams had to be beaten and only Jackson could beat him.

Yet beneath this general accord regarding Jackson, there were political divisions on local questions which were more significant of the true state of the public mind. In 1825 the term of Israel Pickens expired and John Murphy was elected to the governorship without opposition. Murphy, like Pickens, was from North Carolina, and a supporter of the State Bank. His unopposed election indicates the completeness of the triumph of the popular cause and is a tribute to the political sagacity of the retiring Governor.

The first important question to come up was the location of the capitol. The constitution had provided that, during the

---

<sup>1</sup> *Tuscumbian*, March 7, 1825, from the *Nashville Gazette*.

<sup>2</sup> *Huntsville Democrat*, Nov. 7, 1826.



session of 1825, the legislature might remove the seat of government from Cahawba, but if no removal were made at that time, the original seat would be permanent. The subject was taken up with alacrity and several new locations were proposed. The fight developed mainly between Cahawba and Tuscaloosa, the former being favored by the southern and southeastern, the latter by the northern and northwestern portions of the State. Cahawba was accessible to all the Alabama River region, while Tuscaloosa had the advantage of accessibility from the Tennessee Valley as well as water communication with the Tombigbee region. In the final struggle, the Tennessee, Tombigbee, and Warrior valleys were able to outvote the Alabama River region, and the capitol went to Tuscaloosa.<sup>3</sup> Cahawba had proved to be an unhealthy location, but it was urged against Tuscaloosa that it was too near the Mississippi line, and there was little prospect that the capital could remain there after the Indian lands east of the Coosa River should be opened up.

Such a question was not good for party purposes, but another came up at this time which was ridden for all it was worth by the seekers for office.

In 1818 the legislature of Alabama Territory had passed an act which abolished all limitations on the amount of interest which might be charged on loans. John W. Walker then wrote to Tait saying that he was largely responsible for the measure, and asking his friend what he thought of it.<sup>4</sup> It looks like a work of ignorance or, more probably, of self-aggrandizement on the part of the law-makers, and it aroused such strong opposition at the time that it was repealed the next year without struggle. But, in the meantime, numerous contracts had been made under its provisions and the interest called for ranged from 60 to 240 per cent. a year. Many of these contracts provided that a certain sum was to be paid on a certain date, but that if the debt were not discharged as prescribed, it was to bear interest of from five to twenty per cent. a month until paid. A number of such contracts were carried out, but finally legal opposition was made and in 1824 it was decided by the Supreme Court of Alabama that the interest in contracts of this kind was in the nature of a penalty and hence illegal. This protected those who had not already paid, but

<sup>3</sup> Alabama, House Journal, 1825, 75; Senate Journal, 1825, 47.

<sup>4</sup> Tait Papers, J. W. Walker to C. Tait, Sept. 22, 1818.

those who had paid were in another situation. They applied for relief, but the court decided in 1827 that a statute of limitations barred the recovery of money which had already been paid out under such contracts.<sup>5</sup>

This has the appearance of a purely legal matter, and so it should have been, but it was turned into a political question chiefly through the instrumentality of William Kelly who, having failed of re-election to the Senate in 1824, had returned to the legislature and was counsel for a number of those who were seeking to recover money paid out under the "big-interest" contracts and who lost their cases by the decision of 1827. Whereas the judges had been very popular because of their decision of 1824, a cry was now raised against them. They were accused of being enemies of the people and in league with the money-lenders. The old cry against the "Royal Party" of Huntsville was revived and there was said to be a "Radical Party" in the south which was the counterpart of the northern royalists. This party was not supposed to be made up of any section of the public, but of a small group of men in the legislature,—the old guard of the Crawford faction,—who were working for their own interest. The *Huntsville Democrat* presented its view of the situation as follows:

"In no county in the State, has the spirit of local partyism raged with equal violence as in Madison County. . . . But this local feeling has pervaded the whole state, in some counties quite covertly; while in others, it has burned with the utmost intensity. Some twelve or fifteen years ago, the Indian title to a large portion of Alabama was extinguished and straightway the tide of emigration set strongly towards this fertile territory. Persons flocked to it from all quarters; few of them wealthy—most from the expectation of bettering their fortunes. It was not to be presumed that a mass thrown thus loosely together could have pursued any systematic plan of internal policy, or have been actuated by anything like an identity of interests. It was consequently easy for an inconsiderable minority acting in concert, and with a determinate and well understood purpose to give tone to public sentiment, to carry their measures, and possess themselves of all valuable offices. Now, such a minority did exist in this state. They were chiefly composed of Georgians, who, from previous ac-

---

<sup>5</sup> Somerville, *Trial of the Judges*, 62-75; Brickel's *Digest*, Vol. II, Pt. 1, pages 4-5; *Southern Advocate*, Feb. 9, 1827, March 9, 1827; *Huntsville Democrat*, Jan. 19, 1827.

quaintance, attachment to the civil institutions of Georgia, and a more than common portion of wealth, seemed to be connected together by a tie, the strength of which they all recognized by the support which they mutually extended to each other. . . . . These circumstances inspired greater confidence, and led to such developments of their views, as to create a distrust of that purity of character for which they had heretofore obtained credit. They evinced a determination to monopolize all power, and to fill every office with their own creatures. Many of these were so glaringly deficient in the requisite qualifications, that the people began to discover the "family" arrangements which were making to impose rulers over them. The yeomanry of this country, devotedly attached to Democratic principles, could but illy brook this assumption of superiority. . . . . It is to Israel Pickens that the people are chiefly indebted for their dethronement; it was he who first broke the charm and showed that the Georgians with all their management and manoeuvring were not invincible.

Madison County was their great headquarters; here it was that the plan of operations was generally framed; and from thence communicated to their partisans throughout the State."

The article goes on to say that these men had control of the Huntsville bank, and that they were responsible for the passage of the act abolishing interest limitations in 1818.<sup>6</sup>

In 1826 Henry Chambers died and the vacancy thus left in the Senate was filled by the appointment of Israel Pickens. But ill health forced Pickens to resign during the same year, and the election of a successor soon occupied the attention of the legislature. The opposing candidates were John McKinley, a wealthy lawyer of Florence, and Clement C. Clay, a prominent attorney of Huntsville. Though Clay was a member of the Territorial Council and is said to have voted for the fateful interest bill of 1818, and though he was at one time a stock-holder in the Merchants' and Planters' Bank of Huntsville, he did not become identified with the capitalist group at Huntsville and seems to have kept himself square with the people. In 1820 he became Chief Justice of the Supreme Court of Alabama, but resigned that position in 1823 to resume his legal practice.<sup>7</sup> This was his first appearance before the public since that time, and there seems to have been no reason why he should not have received the support of the

---

<sup>6</sup> Huntsville *Democrat*, Feb. 9, 1827.

popular party, but the Huntsville *Democrat* opposed him for reasons which are not evident and gave its support to McKinley, whom the same paper had opposed and labeled an aristocrat when he stood against Kelley for the Senate in 1822.<sup>8</sup>

That all this talk about party, though based upon certain concrete facts, was largely worked up for campaign purposes, is indicated by an apparently candid statement made by McKinley shortly before the election of 1826. It runs as follows:

"I know nothing of the Royal party or its policy, further than I have seen the subject discussed in the newspapers, and as far as comprehended by that discussion, I have no personal or political interest in it. I had been a citizen of this state about a year before I ever heard of the existence of a party in it. I was then informed by a friend, if I supported a particular individual for Governor, I would be considered as belonging to the *Georgia* party. What was meant by this party, I did not know, nor could my friend inform me as he was equally a stranger to its meaning or object. In 1821, I heard for the first time of the Royal party, and was equally at a loss to know what was the meaning of the name or the object of that party. In the fall of that year, I removed to this place where I heard but little more of parties until the fall of 1822, when I became a candidate for the same office for which I am now a candidate. When at the seat of government pending the election between Judge Kelly and myself, the charge of belonging to the *Georgia* party, Huntsville, and Royal party, was brought to bear upon my election. I had no mode of defending myself against the charge, but simply denying that I belonged to any party, which was the fact. In that contest I was beaten by a single vote, to which I submitted, I hope, with becoming propriety. I continued to reside in this place until February, 1825, without hearing my name connected with party, and having kept myself aloof from all party contests, had hoped to escape such an unfounded, and as I conceived, ungenerous imputation. But shortly after my return to Huntsville in the early part of 1825 this charge was revived against me, although I was a candidate for no office, nor took any active part in the local or general politics of the country. In the year 1823 a newspaper discussion took place in the

<sup>7</sup> For a sketch of Clay's career, see Pickett, *History of Alabama*, 648-653.

<sup>8</sup> *Southern Advocate*, Jan. 12, 1827; Huntsville *Democrat*, Dec. 29, 1826

*Democrat* and *Advocate* upon the subject of party, when it assumed a more tangible shape. The principal cause of complaint, as well as I now recollect, against what was termed the Royal party, was the statute of February, 1818, the combination of certain men to procure its passage, and the aid afforded by the Huntsville bank to those men, to obtain funds to lend at exorbitant interest."<sup>9</sup>

This election, in which no question of policy was involved, and in which the two candidates seem to have been so nearly equal in regard to fitness for popular leadership, yet which was waged with so much bitterness of partisan feeling, marks the point at which the popular party, having gained an undisputed ascendancy, was becoming a prey to factious contests among its leaders. The struggle, though close, resulted in favor of McKinley.<sup>10</sup>

But Kelly and the *Democrat* did not mean to be without an issue of some sort. The fight against the Supreme Court judges was pressed. Kelly brought charges before the legislature against three of them on the plea that their decision of 1827 had gone counter to the precedent established by the cases of 1824 and that this was an improper application of law on their part. The complaint was not sustained, however, and the judges were exonerated by an overwhelming vote.<sup>11</sup> But the matter was not allowed to drop here. A constitutional amendment reducing judicial tenure from the period of good behaviour to a term of six years was passed by the legislature in 1827; approved the next year by popular vote,<sup>12</sup> and incorporated as the first amendment to the State constitution in 1830.

But while the disintegration of the Crawford faction after 1824 had deprived local politics of a real issue, national questions were coming more to the front. On some of these, such as the tariff, internal improvements, and slavery, the popular mind was well made up. On others, such as Indian policy and state rights, there was much more divergence of opinion. No one in the State had formulated any policies in regard to these questions, nor were there any political divisions along these lines. The legislature had to act from time to time on questions connected with such subjects, but the votes showed no

<sup>9</sup> Huntsville *Democrat*, Oct. 27, 1826.

<sup>10</sup> Alabama, Senate Journal, 1826. 20-21.

<sup>11</sup> Alabama, Senate Journal, 1826, 193.

<sup>12</sup> Alabama, Senate Journal, 1828, 76; *Mobile Register*, Nov. 21, 1828.

definite alignments and seem to have been dictated by personal convictions or temporary considerations.

As to the tariff, there was a general and strong conviction that it was wrong to tax the agriculture of one section of the country for the benefit of the manufactures of another. Yet there was a minority, led by the *Southern Advocate* and the supporters of Adams, which advocated a "competitive" tariff and insisted that the South must develop manufactures.

The interest of Alabama in the Muscle Shoals and the Coosa-Hiwassee canal projects, and the proposed road from Washington to New Orleans, brought about a general demand for internal improvements constructed with Federal aid.<sup>13</sup> This threw the State astride on the question of state rights, for it was difficult to support improvements and denounce the tariff at the same time; and Randolph and Macon were never tired of warning that to give the Government the right to construct public works within the states would give it the right also to free the slaves.

This situation necessitated a certain amount of hedging when it became necessary to formulate general political doctrines, or to make out a case for favorite presidential aspirants. Before the election of 1828, Jackson was questioned as to his views and replied that they were the same as they had been in 1824 when he supported the tariff and internal improvement measures.<sup>14</sup> The friends of Adams stated that no distinction between the two men could be made on these grounds, and the contention, at this time, was at least reasonable. The preference for Jackson was personal, sectional, and democratic.

But while the position of Alabama was not strictly logical according to the political schools of the time, it was practical and well-defined. Very little sympathy was extended to Troup while he was making his fight against the Administration on the question of the removal of the Creek Indians; and Georgia was roundly denounced for presuming that one state could upset the operations of the National Government.<sup>15</sup> The prevalent opinion was that both Troup and Adams had behav-

<sup>13</sup> The *Southern Advocate* for Sept. 19, 1828, published toasts drunk at a dinner given the Congressional delegation of Alabama. Here the tariff was condemned and internal improvements supported.

<sup>14</sup> *Southern Advocate*, April 25, 1828. Jackson's letter is dated February 28, 1828.

<sup>15</sup> *Southern Advocate*, Oct. 14, 1825, March 16, 1827; Huntsville *Democrat*, Sept. 16, 1825, July 29, 1825; *Tusculumbian*, Nov. 7, 1825.

ed rashly; that the Government was under obligations to remove the Indians from the State; and that Adams had blundered when he threatened to use Federal troops to enforce his policy, just as Troup had erred in his attitude of uncompromising defiance. The original treaty with the Indians, which was later annulled and became the bone of contention, had secured a small tract of the Creek lands which lay within the limits of Alabama. Governor Murphy raised the question whether a third party could be deprived of rights under a contract even though it were not enforced as to the contracting parties.<sup>16</sup> The question was taken up in the legislature and a bill passed extending the jurisdiction of the State over the lands concerned.<sup>17</sup> But this was looked upon as merely the testing of a legal proposition, and the matter was carried no further.

A more severe strain upon the loyalty of the State came when the "tariff of abominations" was passed in 1828. There was universal dissatisfaction and even disgust with the policy pursued. It was felt that the interests of the cotton states were being sacrificed to the ambition of the manufacturing district and, whether it was wise, whether it was constitutional as the Constitution had originally been intended, there is no question but that the planters were right as to the practical bearing of the situation. Protests went up on all sides; the development of home manufactures was urged; and the boycotting of imports from the manufacturing states was advocated. It was even urged that it would be possible to lay duties upon such imports, but it was always made clear that all resistance was to be peaceable. When forcible resistance was suggested or threatened in resolutions which were brought up before the legislature, the portentous clauses were stricken out by decisive votes;<sup>18</sup> and Senator William R. King, while condemning the tariff in an address at Selma, made the following statement:

"With a view, Gentlemen, to effect political objects, a systematic effort has been made to impress the belief upon the people of our country, that the high minded and patriotic in-

<sup>16</sup> Alabama, Senate Journal, 1826, 11.

<sup>17</sup> Alabama, Sessional Acts, 1826, 32.

<sup>18</sup> Alabama, Senate Journal, 1826, 101-102; *Ibid.*, 1828, 207. In the latter instance there were stricken from a resolution condemning the tariff the following words: "and that open and unqualified resistance should only be the *dernier ressort*."

habitants of the South and South West—the advocates and supporters of a most distinguished and meritorious citizen—are engaged in *planning the dissolution of our union; the destruction of this federative Government*—the legacy of our patriotic and sainted Fathers.”<sup>19</sup>

On this occasion the following toasts were drunk: “The Union of the States—Palsied be the arm that shall be raised to sever it,” and, “The Tariff—Unconstitutional in principle, unjust and unequal in its operation—We will not oppose it with violence and passion, but by relying on our own resources.”<sup>20</sup> The editor of the *Mobile Register*, referring to an address of the citizens of Colleton district, South Carolina, wrote: “We will frankly declare, it was not from the State of South Carolina that we ever expected a proposition the bare contemplation of which must cause the heart of a patriot to sink within him.”<sup>21</sup>

But there was another movement on foot which led in a different direction and which was big with meaning for the future. This movement, though not original in conception, was a new influence in Alabama and it was important at that time only because its leader, who knew what he believed and where he was going, was able to fit his purpose to the material in hand and secure the temporary support of men who did not understand whither he was leading them. This new influence is interesting not only because of its significance for the future, but for its connection with the past.

Dixon H. Lewis was born, according to Yancey’s sketch of him,<sup>22</sup> in Hancock County, Virginia, in 1802. His father was among those Virginians who moved to Georgia in the days when upland cotton was coming to supplant tobacco as the main agricultural staple of the South. From Georgia he moved to Autauga County, Alabama, in 1820.

Young Lewis studied law at Cahawba in the office of Henry Hitchcock, a New England man who had come out to Alabama as secretary to the Territorial governor, and who was now Attorney General of the State. The political influence in the life of Lewis was exerted largely by his uncle, Bolling Hall, the Georgia Congressman who had come to Alabama with Tait,

<sup>19</sup> *Huntsville Democrat*, Nov. 7, 1828.

<sup>20</sup> *Southern Advocate*, Nov. 7, 1828.

<sup>21</sup> *Mobile Register*, July 12, 1828.

<sup>22</sup> Obituary of Dixon Hall Lewis, MS. Yancey Papers. See also Dixon H. Lewis, by T. M. Williams, in *Alabama Polytechnic Institute Historical Studies*, 1912.



Walker, and the other supporters of Crawford. Hall was not only a friend of Crawford, but of Nathaniel Macon, John Taylor, and others who had long stood for strict construction of the Constitution.

The views of Lewis were essentially the views of these men, whom Alabama had heard from afar and ignored. But in 1826 the gigantic young lawyer won a spirited election in Montgomery County and went up to the legislature to make his debut in politics. He had not been there more than twenty-four hours when he drew up a set of resolutions condemning the exercise of implied, constructive, and unconstitutional powers on the part of the Federal Government, and had it presented before the Senate by his friend, Matt Clay. These resolutions were passed with but one dissenting vote after there had been stricken from them the following clause:

"Resolved, That we believe the time has again arrived when it is necessary for the States to assert their constitutional rights, and with becoming firmness to resist the increasing progress of federal power."<sup>23</sup>

In pursuance of his views, Lewis took up the Indian question and in 1828 presented a report in the House of Representatives in which it was argued that the State had jurisdiction over the natives within her borders and that the United States had no right to interfere between them.<sup>24</sup> Along with the report he presented a bill proposing to extend the jurisdiction of the State over the Creeks, and though almost every member of the House at first disapproved the idea, the measure was finally passed, receiving the bulk of its support from the counties bordering the Creek reservation.<sup>25</sup>

But it was not only on National questions that Lewis had convictions. He had inherited from Bolling Hall and the Crawford men a sincere dislike for the State Bank and, though at this time the foundations of that institution were unassailable, he began to attack it at vulnerable points. There had been a noisy contest in the legislature over the question as to whether that body was permitted to inspect the private accounts of the bank. The cashier refused to show the private books to the visiting committee and the opponents of the institution at once raised their voices in protest. They apparently failed in their attempt to cast discredit upon the manage-

<sup>23</sup> Alabama, Senate Journal, 1826, 101-102.

<sup>24</sup> Alabama, House Journal, 1828, 220, 223.

<sup>25</sup> *Ibid.*, 263.

ment. The procedure of Lewis was less spectacular, but more to the point.<sup>26</sup> The legislature was in the habit of levying taxes in excess of disbursements and using the balance for banking purposes. It was this practice which Lewis now attacked and succeeded in stopping.<sup>27</sup>

The attitude of the new leader on the question of the State Bank brings out his connection with the earlier opponents of the popular party, but the manner in which political ground had shifted is shown by the fact that, when resolutions proposing Jackson for the Presidency were to be brought before the legislature in 1827, it was Lewis who was chosen to present them.

After condemning the existing Administration because it had departed from the principle of strict construction; because it had accepted internal improvements as a fixed policy—and one destructive of State sovereignty; because of its attitude on the Panama mission; and because it had adopted the policy of encouraging one industry at the expense of another by prohibitory duties; the resolutions go on to say:

"Another prominent act of Mr. Adams requires particular notice, viz: his threat to employ military force against one of the sovereign members of the confederacy. So great a want of temper, such an entire misconception of the character of the American people, and so extraordinary a claim to power is believed to be unparalleled in the history of any preceding administration. More forbearance might have been expected from a prince of unlimited powers to one of the most rebellious provinces of his dominions. Before any negotiation of a friendly character was attempted, or even a measure of compromise proposed, the State of Georgia was threatened with the military force of the Union for the purpose of forcing her into an unconstitutional abandonment of substantial rights of sovereignty, secured to her by the solemn stipulation of treaty—This State cannot but share some portion of the responsibility thrown upon Georgia in this matter, inasmuch as an enactment of the last legislature, and a resolution of the same body recognized the principles for which Georgia was then contending. As Alabamians, therefore, the committee feel bound to protest against this violent measure of the President of the United States. . . . To counteract so powerful an

---

<sup>26</sup> *Cahawba Press*, March 18, 1826.

<sup>27</sup> Yancey, Obituary Notice of Lewis, 15; See House Journal, 1826, 223-224, for report on finances.

influence, a systematic effort is required of the people, and a concentration of their entire strength on some distinguished individual."<sup>28</sup>

General Jackson was named as that individual and the resolutions passed by a vote of fifty-four to eight, but they do not represent the kind of Jacksonism which was characteristic of the earlier supporters of the General. The young lawyer from Montgomery had a remarkable faculty for bringing the legislature to his way of thinking when he did not have strong convictions to overcome, and here was a fine denunciation of Adams. It was gladly accepted because it served the purpose in hand, and no one thought it worth-while to criticise its purely negative support of Jackson and its very positive support of state rights, to which the majority of the people did not subscribe.

Though Adams electors were nominated, the General carried the State almost without opposition<sup>29</sup> and soon entered upon the administration that was to see the birth of questions which would divide his followers. In Alabama, under the leadership of Lewis, the planters were to add a plea for the safety of the slave states to their old distrust of mass-government, and divide the Commonwealth into two distinct, well-defined, and fairly-balanced parties.

---

<sup>28</sup> Alabama, House Journal, 1827, 182 et seq.

<sup>29</sup> The Huntsville *Democrat* for Dec. 5, 1828, gives the vote as follows: Jackson, 13,384; Adams, 1,629.

## CHAPTER XIII.

---

### RELIGION, EDUCATION, AND THE PRESS

The press came into Alabama with the settlers and exercised a strong influence during the formative period of the State. The little four-page sheets which came out once or twice a week were largely taken up with advertisements and notices. A crude system of classifying advertisements enabled the reader to select readily those in which he was interested. This was accomplished by inserting a small cut indicative of the subject-matter; a picture of a tree, for instance, would indicate that the advertiser had land for sale; a cut of a house would show that buildings were for rent or sale; while a negro with a bundle swung over his shoulder at the end of a stick would proclaim the escape of a slave.

That portion of the paper, usually amounting to less than two of the four pages, which was devoted to the news was principally taken up with extracts from the leading papers of the older states. The most of these articles related to political affairs, but foreign news, though much belated, received relatively more attention than it does now. A florid style was typical of the press of that day, and words were used with especial freedom when a political subject claimed the attention of the editor or contributor. In fact, it seems to have been the universal practice to treat a political opponent as a moral or mental delinquent.

The editors of the Alabama papers confined their remarks to one or two columns, where they expressed their opinions upon National politics, or subjects of local interest. Personal affairs were never paraded in print, nor was mention ever made of social activities. This was due, not only to ideas of decorum which differ from ours, but also to the conception that the press was strictly a public institution. Letters from subscribers on political matters were frequently published, and these formed an important element in every discussion.

The first newspaper founded in Alabama was the *Madison Gazette*, established at Huntsville in 1812;<sup>1</sup> in 1816 its name

---

<sup>1</sup> Smith and DeLand (Pub.), *Northern Alabama*, 251.

was changed to the *Alabama Republican*;<sup>2</sup> and in 1825 this was consolidated with the *Alabamian* to become the *Southern Advocate*.<sup>3</sup> John Boardman, a Massachusetts man who allied himself with the "Aristocratic Party" of Huntsville, was editor first of the *Republican* and later of the *Advocate*. He supported Adams for the Presidency in 1824 and, though going over to Jackson in 1828, he always opposed the State Bank and its adherents.

In 1823 an opposition paper called the *Democrat* was founded at Huntsville.<sup>4</sup> Its editor, Mr. William B. Long, of Kentucky, was a supporter of Clay. Claiming to be a leader of "the people" as opposed to "the aristocracy" and the *Alabama Republican*, he hotly took issue with Boardman on the question of the State Bank; and presently came over to the support of Jackson for the Presidency. Crawford men, the Merchants' and Planters' Bank of Huntsville, and "aristocrats" in general were the particular antipathies of the *Democrat*; at the same time it was lenient toward those who combined the support of the State Bank with that of Adams. So bitter was its attitude toward its opponents that the successor of Long, a Mr. Andrew Wills, who had come from Virginia to Huntsville as a school teacher, was shot down on the street by a political enemy.

The storm center of Alabama was in the Tennessee Valley, and the *Democrat* and the *Republican* expressed the extreme views of the two factions. In the remainder of the State there was less agitation, the interior towns usually having but one paper which, while expressing its own views, took a mild attitude so as to retain the good-will of all moderate men.

In Mobile, commercial affairs were given the precedence over politics. The first paper published here,—the *Mobile Gazette*,—was established in 1816 by a Mr. Cotton.<sup>5</sup> In 1821, Mr. John Battelle, having established the *Montgomery Republican* in the same year, formed a partnership with Mr. J. W. Townsend and founded the *Mobile Commercial Register*.<sup>6</sup> John Battelle was a native of Boston and a member of the Alabama Company which helped to found the town of Montgomery. The *Register* supported Crawford for the Presidency, and in 1822

<sup>2</sup> Betts, *History of Huntsville*, 80.

<sup>3</sup> *Southern Advocate*, May 6, 1823.

<sup>4</sup> *Alabama Republican*, Oct. 10, 1823.

<sup>5</sup> Meek, *Romantic Passages*, 103-104.

<sup>6</sup> Blue, *History of Montgomery*, 12.

it bought out the *Gazette*,<sup>7</sup> a move which its enemies attributed to political motives. Its principal interest was in commercial affairs, and it opposed the establishment of a State Bank upon the plan advocated by Pickens. In 1822, the *Mobile Argus* was founded by Charles A. Henry,<sup>8</sup> but the following year the firm of Nicholas and Henry succeeded to the ownership and changed the name to the *Mercantile Advertiser*.<sup>9</sup> This paper supported Adams for the Presidency, but, like practically all the others of that faith, it claimed "to do justice to all."

The *Montgomery Republican*, founded by Battelle in 1821, changed its name in 1825 and became the *Montgomery Journal*.<sup>10</sup> It supported Adams from the first. The *Cahawba Press*, founded in 1819 at the State Capital by William B. Allen,<sup>11</sup> a native of Boston, joined the support of Adams with that of Pickens and the State Bank. In 1824, Allen sold his paper to a Mr. Lumpkin, but when the purchaser proceeded to support Crawford, the friends of the State Bank, both Jackson and Adams men, combined to set Allen up in business again and to give a new lease of life to the *Press*.<sup>12</sup> The fact that Allen, in spite of the competition of Lumpkin and others, was elected State printer as long as the capital remained at Cahawba, shows that the support of Adams was not particularly prejudicial to the popularity of an editor so long as he was a friend of "the people's Bank."<sup>13</sup>

In 1819, there were six papers in Alabama: the *Alabama Republican* of Huntsville, the *Halcyon* (established at St. Stephens in 1814), the *Mobile Gazette*, the *Cahawba Press*, the *Blakely Sun*, and the *Tuscaloosa Mirror*. By 1823 the number had risen to ten,<sup>14</sup> and the next year it amounted to fifteen.<sup>15</sup> During 1825, there were sixteen or seventeen papers published in the State,<sup>16</sup> but the following year saw the number reduced again to ten.<sup>17</sup>

<sup>7</sup> *Mobile Register*, May 9, 1822.

<sup>8</sup> St. Stephens *Halcyon*, Nov. 2, 1822; *Cahawba Press*, Nov. 22, 1822.

<sup>9</sup> *Cahawba Press*, Nov. 29, 1823.

<sup>10</sup> Blue, *History of Montgomery*, 12.

<sup>11</sup> Blue MS., Dallas County, 16.

<sup>12</sup> *Cahawba Press*, Sept. 25, 1824; *Tuscaloosa Mirror*, Sept. 11, 1824.

<sup>13</sup> Alabama, Senate Journal, 1823, 96-97; Ibid., 1824, 38-39; Ibid., 1825,

35.

<sup>14</sup> *Cahawba Press*, June 21, 1823.

<sup>15</sup> *Alabama Republican*, June 11, 1824.

<sup>16</sup> *Tuscumbian*, April 18, 1825.

<sup>17</sup> Huntsville *Democrat*, Sept. 15, 1826.

The great publishing activity of 1824 was undoubtedly a result of the presidential campaign of that year, and it speaks much for the political influence of the press at that time. In 1824 it was said that, of the fifteen papers in Alabama, seven, edited by Northern men, were for Adams; but all of these except the Huntsville *Republican*, were published in the southern part of the State.<sup>18</sup> Two years later, when the number of papers had been reduced to ten and the support of Jackson had become almost universal among the people, three publications were said to have remained steadfast in their support of Adams, three or four were said to have opposed him consistently, while the rest maintained an uncertain attitude.<sup>19</sup> The popularity of the New Englander in the Alabama press can be ascribed primarily to the northern origin of so many of the editors. The combination of the support of Pickens and the State Bank with that of Adams increased the popularity of publications which differed from the majority of their patrons on the subject of the Presidency. Nevertheless, there was a tendency among the newspaper men to modify their opinions gradually in order to accomodate themselves to the trend of public sentiment.

The early settlers of Alabama were not indifferent to the problem of education, and the grant of the sixteenth section in each township for local schools afforded a solid foundation upon which to build, but the results were not as favorable as might have been expected. In good agricultural districts, the sixteenth section usually yielded sufficient income to support, or partially support, several schools with fairly well-paid teachers. But in areas where the soil was poor, there was little income from the land, and the zeal of the population was usually not sufficient to make up the deficit.<sup>20</sup> Travelers noted the existence of creditable free schools as early as 1820,<sup>21</sup> but these were not universal—perhaps not even usual.

One of the main difficulties lay in the management of the school property. This was vested in a board of commissioners appointed by the county authorities.<sup>22</sup> Supervision over

---

<sup>18</sup> Ibid., Aug. 24, 1824.

<sup>19</sup> Ibid., Sept. 15, 1826.

<sup>20</sup> Blandin, *Education of Women in the South*, 59.

<sup>21</sup> Hodgson, *Letters from North America*, I, 144, 269.

<sup>22</sup> Acts of Dec. 18, 1819, and Jan. 1, 1823.

these commissions was vague or non-existent, and their conduct of affairs was a frequent source of complaint.<sup>23</sup>

Even such support as the public schools possessed was menaced when the lure of the State Bank induced the legislature to promote a scheme for selling the sixteenth sections and investing the proceeds in the popular institution. In 1826, the Alabama delegation was instructed by the legislature to secure from Congress permission to sell these lands and devote the proceeds to the maintenance of the schools.<sup>24</sup> In 1827, Congress granted the request, providing that the sale should be made only with the consent of the township concerned.<sup>25</sup> The next year the legislature made provisions for carrying out the plan. The proceeds of the lands were to be invested in the State Bank at six per cent. interest and the income devoted to the purpose for which the grant had been made.<sup>26</sup> Thus the Bank could look forward to a considerable extension of its resources, and the schools could contemplate an uncertain future.

In addition to the public schools, private schools were established from time to time in the larger towns, and by 1823 as many as eight academies had been chartered.<sup>27</sup> Apparently, the first of these to go into actual operation was the *Green Academy*, chartered by the legislature of Mississippi Territory in 1812. Though a grant of five hundred dollars was made to this institution in 1816, and funds provided later brought the total up to about two thousand dollars, nothing had been done toward putting the school in operation before 1820.<sup>28</sup> At about this time, however, the trustees bestirred themselves, raised funds by popular subscription, and had a creditable institution in operation within a year or two.<sup>29</sup>

The first academy for girls was founded at Athens in 1822, and appears to have been a successful enterprise.<sup>30</sup> At about the same time, a private school for girls was opened in Huntsville by a Mr. and Mrs. DeVendel.

---

<sup>23</sup> Huntsville *Democrat*, Feb. 9, May 18, and June 29, 1827.

<sup>24</sup> Alabama, House Journal, 1826, 244.

<sup>25</sup> Statutes at Large, IV, 237.

<sup>26</sup> Act. of Jan. 15, 1828.

<sup>27</sup> Toulmin, Code of 1823.

<sup>28</sup> *Alabama Republican*, Nov. 10, 1820.

<sup>29</sup> Mention of the subscription papers is made in the *Alabama Republican* for Aug. 3, 1821, and the address of the trustees is among the Walker Papers.

<sup>30</sup> Incorporated Dec. 9, 1822; *Southern Advocate*, May 19, 1826.



The subjects usually taught during this period included grammar, history, mathematics, and geography, while the schools for girls included in their curriculum also music, needle-work, painting, and dancing. The academies took up instruction in Latin, some of the sciences, and rhetoric.

The Federal Government had granted two townships to the State of Alabama for the purpose of founding a university, and in 1820 that institution was given a formal existence by the legislature, but nothing more than a name was established at this time.<sup>31</sup> In 1821 a board of trustees was appointed and given power to dispose of the university lands, invest the proceeds and establish the institution as soon as a site should be designated by the legislature.<sup>32</sup> The first meeting of the board was held during the next year and arrangements were made for disposing of the property. It was decided to adopt a credit system of sales, requiring one-fourth of the purchase money to be paid down, and the remainder in three installments.<sup>33</sup> During the first few years there was a good demand for the lands, and by 1828 the total sales amounted to \$285,000.<sup>34</sup>

But the State Bank interfered here also and the establishment of the University was delayed. The trustees could not move until the legislature had decided on the location, and Governor Pickens, being anxious to use the university funds as capital for the Bank, secured the postponement of the location until after his term of office had expired.<sup>35</sup> It was intended from the first that the greater part of the fund should be used as an endowment, and, considering the hopes that were entertained for the success of the Bank, there was nothing morally wrong in the Governor's plan for investment, but his attitude shows where his interest chiefly lay. About \$89,000, or practically all the cash received in payment on the lands sold, was invested by the trustees of the university in the Bank before anything was done to give the institution of learning a practical existence.<sup>36</sup>

Governor Murphy, on coming into office, advised the legislature to locate the university,<sup>37</sup> and in 1827 Tuscaloosa was

---

<sup>31</sup> Act of Dec. 18, 1820.

<sup>32</sup> Act of Dec. 18, 1821.

<sup>33</sup> Alabama, House Journal, 75 *et seq.*; *Cahawba Press*, June 29, 1822.

<sup>34</sup> Alabama, Senate Journal, 1828, 98.

<sup>35</sup> *Franklin Enquirer*, April 21, 1824; Alabama, Senate Journal, 1825,

8.

<sup>36</sup> Alabama, Senate Journal, 1828, 98.

<sup>37</sup> *Ibid.*, 1826, 6.

selected as its site.<sup>38</sup> In 1828 the trustees drew up a plan including the construction of the following buildings: one central building to be used as a chapel, lecture hall, and library; one chemical laboratory and lecture hall; four professors' houses, each accomodating two professors; two or more hotels or boarding houses; and six dormitories. It was proposed that the central building, the laboratory, two of the professors' houses, one hotel, and two dormitories be erected at once, and contracts were let accordingly.<sup>39</sup> A tract of fifty acres adjoining the university site was purchased so that clay for brick and timber for structural purposes could be obtained close at hand.<sup>40</sup> The corner-stone was laid during the same year,<sup>41</sup> and in 1831 the University of Alabama opened its doors, with Dr. Alva Woods, formerly at the head of Transylvania University, as its first president.<sup>42</sup>

In religious matters, the Methodists and Baptists have always held the center of the field in Alabama. The predominance of these two denominations in the old Southwest is an interesting phenomenon, and the development in one State would probably be paralleled by the situation in most of the others.

The period following the American Revolution was a fertile one for the sowing of religious seed. The events of the French Revolution had left the world more or less in doubt concerning its old creeds, and the French philosophers, followed by Jefferson in this Country, gave skepticism a wide vogue. But the coming of the Wesleys and Whitfield had earlier brought a new faith, and at a time when America was beginning to spread westward.

The organization of the Methodist society was peculiarly fitted to frontier conditions. With a central governing body made up of the bishops, a definite policy could be adopted and carried out in an effective manner. With its "free-for-all" ideas regarding the ministry, men could be drawn into the service of the church whose lack of education was atoned for by a zeal which strengthened them to endure the hardships of the forest and to work for the love of their creed with very little compensation in a material way. The institution of the

---

<sup>38</sup> Ibid., 1827, 109-110.

<sup>39</sup> Alabama, Senate Journal, 1828, 13, 100, 207-208.

<sup>40</sup> Ibid., 1828, 98.

<sup>41</sup> *Mobile Register*, Nov. 4, 1828.

<sup>42</sup> University of Alabama, Bulletin, November, 1906.

circuit rider enabled one man to do the work of several, and was a most efficient means of meeting frontier conditions. Finally the development of the "camp meeting" brought the scattered people together under conditions which made a strong emotional appeal to the pioneer, and enabled a few men to exert a powerful influence over many.<sup>43</sup>

In the combination of these means, the Methodists had an advantage over all other denominations in the thinly-settled frontier; but the Baptists, though lacking organization, had a zeal which largely overcame this difficulty. Their appeal, like that of the Methodists, was to the emotions of the plain man, and their ministry was also adapted to frontier conditions. They brought their gospel to the pioneer by much the same means as those employed by the followers of Wesley, and the local independence of their churches seems to have been so agreeable to the free spirit of the West that it enabled them to compete on equal terms with their religious rivals.

In the early part of the Nineteenth Century, religion was neither accepted nor rejected with the indifference that is accorded it today. The average back-woodsman was not by nature inclined to be strictly religious, but he was inclined to be positive. When the question came to him he took his stand either for it or against it, and made a good supporter or an out-spoken antagonist. Neither was he inclined to be theoretical, and in the struggle between the Methodists and the Baptists, he seems to have been more interested in the spirit in which the rivals worked than in their rival creeds.

But all this does not apply to the planters. It was said that the cultivated people never went to the camp meetings,<sup>44</sup> and it is certain that these were attended by a degree of emotionalism which is often repulsive to the more refined. The strongholds of the Methodists and Baptists were in the rural districts,<sup>45</sup> and that the townspeople were more or less unfamiliar with camp meeting procedure is indicated by a description which the editor of the Huntsville *Democrat*, who was a defender of religion, thought it worth-while to print.<sup>46</sup> A

<sup>43</sup> In the *Minutes of Conferences*, Vol. I, may be found lists of all the Alabama Methodist congregations, giving the number of members for each year, beginning with 1820.

<sup>44</sup> Royall, *Letters from Alabama*, 122.

<sup>45</sup> Riley, *Baptists in Alabama*, 64; McDonnold, *Cumberland Presbyterian History*, 162-163.

<sup>46</sup> Huntsville *Democrat*, Oct. 14, 1823; See also *Southern Advocate*, Sept. 9, 1825, and July 28, 1826; Huntsville *Democrat*, Oct. 14, 1823, and Oct. 27, 1826.

favorable spot in the woods was selected as the place of worship, and a pulpit and altar erected in a crude way. Benches were arranged around this, and tents for the accommodation of tables and guests were pitched about the grounds. Two sermons were usually preached in the morning, and then a short recess was allowed for dinner. At this time, the worshippers would repair to the tents where abundant supplies of food were laid out for the benefit of all. People from the surrounding country came on horseback, in carriages, or afoot, as circumstances permitted, and brought their picnic lunches with them. The occasion was one of social as well as religious enjoyment; and crowds of thousands were sometimes assembled to hear favorite exhorters. After dinner, the services were resumed, and they were always concluded by an invitation to repentant sinners to come up to the altar. Large numbers usually went forward, and as the minister prayed for them, the congregation went into a religious ecstasy of praying, moaning, and shouting. But it must not be inferred that these were disorderly gatherings. There was a spirit of sociability and festivity on the part of the people and of gravity on the part of the leaders which gave them a dignity of their own.

The planters usually had at least some latent religious belief. There were Episcopalians among them, but they were not of a missionary spirit and their numbers were too few to found many churches in the early days.<sup>47</sup> Presbyterians were present in larger numbers and a church of that faith was usually established in the leading towns.<sup>48</sup> Here they were active rivals of the Methodists and Baptists, who also established churches and held "protracted" meetings.<sup>49</sup> Bible societies were organized in several places,<sup>50</sup> and Huntsville had an inter-denominational Sunday School.<sup>51</sup> In Mobile the Episcopalians formed the nucleus of an inter-denominational protestant church, which was the only rival of the older Catholic congregation of that place.<sup>52</sup>

---

<sup>47</sup> Whitaker, *Episcopal Church*, 13.

<sup>48</sup> Wyman, *Geographical Sketch of Alabama*, in *Transactions, Ala. His. Soc.*, 1898-1899, III, 118; *Mobile Register*, April 29, 1828, and Nov. 4, 1828; *Franklin Enquirer*, March 20, 1824.

<sup>49</sup> *Huntsville Democrat*, May 16, 1828.

<sup>50</sup> *Southern Advocate*, Aug. 12, 1825; *Tusculumbian*, Apr. 18, 1825.

<sup>51</sup> *Huntsville Democrat*, Sept. 5, 1828.

<sup>52</sup> *Mobile Register*, Jan. 1, 1828, and Feb. 28, 1828.

## CHAPTER XIV.

### SOCIAL CONDITIONS AND SLAVERY

In a newly-settled area to which people have flocked from many places and for many purposes, one would expect to find varied social conditions, and in Alabama they ran all the way from one extreme to the other. To begin at the bottom, the Indian border offered a favorite location for fugitives from justice, traffickers in whisky, and rascals of every description. The State had no jurisdiction within the reservations, and this fact was taken advantage of by all such persons. It worked a great hardship on the natives and gave rise to complaints which were fully justified, but very hard to meet.<sup>1</sup> It was often said that the contact of the red men with the whites was sadly detrimental to the former, and since their associations were usually with the worst of the whites, this is not hard to understand.

But the miscreants were not confined to the borders. New country is attractive to adventurers of every sort; the lonely roads through the forests afforded robbers a choice field of operations, while the towns were alluring to gamblers of various breeds.<sup>2</sup> There is an account of a band of men intercepted on their way to Huntsville whose baggage was found to contain counterfeit notes and gambling devices of every description.<sup>3</sup> Complaint was made that gamesters in that town often assumed an air of importance because they were noticed by men of standing,<sup>4</sup> and the young men seem generally to have fallen an easy prey to the wandering gamblers.<sup>5</sup>

The towns were infested also with a set of people who were not criminals, but who might be included under the term "rowdy."<sup>6</sup> While the young men of the towns appear to have

<sup>1</sup> *Southern Advocate*, April 14, and Dec. 15, 1826; Alabama, Senate Journal, 1821, 11; Birney's *Birney*, 55; Levasseur, *Lafayette en Amerique*, II, 335-339.

<sup>2</sup> Alabama, Senate Journal, 1825; 12; Huntsville *Democrat*, Apr. 6, 1827, and June 30, 1826; Hall Papers, Report of a committee of the legislature appointed to investigate causes of crime.

<sup>3</sup> *Southern Advocate*, July 22, 1825.

<sup>4</sup> Huntsville *Democrat*, June 16, 1826.

<sup>5</sup> Huntsville *Democrat*, June 16, 1826, and May 25, 1827; Saunders, *Early Settlers in Alabama*, 45.

<sup>6</sup> Riley, *Conecuh County*, 93; Saunders, *Early Settlers in Alabama*, 45-46; Yerby, *Greensboro*, 8, 12; *Tusculumbian*, Oct. 22, 1824.

been victims to dandyism, idleness, and gambling rather than to boorishness,<sup>7</sup> the rowdies were apparently visitors from the surrounding country who came in to make a holiday in a boisterous manner. It is stated that in Greensboro horse racing through the main street became such a nuisance that the citizens were provoked to threaten to shoot any one who persisted in the practice.<sup>8</sup>

It was, however, at the cross-roads store, the militia muster, and the barbecue that the rustics mostly congregated. Horse-play was the rule at such places, and assemblies usually ended in drunkenness and fighting. Yet these frays were not blood-thirsty affairs, but merely a hardy form of sport. Those who engaged in them were not brutal, but merely vigorous pioneers who loved a struggle with nature or with man.<sup>9</sup>

The barbecue, like the camp-meeting, was an institution. Its use was largely political and its appeal seems to have been almost irresistible. Before an election, these gatherings were arranged and advertised by men whose interest was primarily financial. Shout and whisky in abundance were always taken for granted, and the candidates were bound to appear to assert their claims and prove their democracy.<sup>10</sup> Sentiment against the barbecues began to be aroused about 1826 and the Huntsville papers instituted a campaign against them. The candidates seem to have been willing enough to drop the practice, and some of them began to refrain from attendance.<sup>11</sup> But whisky was always one of the strongest arguments in a political campaign. A Mobile paper published an ironical offer to furnish any man enough whisky to drown his reason on election day, which was a jibe at the custom of "treating" by the candidates.<sup>12</sup> A Huntsville paper makes the statement that bottles of liquor were arranged in rows with labels on them which the casual observer would take for designations of brand, but which in reality designated the candidate who furnished the drink.<sup>13</sup>

---

<sup>7</sup> *Tusculumbian*, Feb. 28, 1825.

<sup>8</sup> Yerby, *Greensboro*, 14.

<sup>9</sup> Riley, *Makers and Romance of Alabama History*, 584-588.

<sup>10</sup> Royall, *Letters from North America*, 120; *Southern Advocate*, July 8, 1825, and June 1, 1827.

<sup>11</sup> *Southern Advocate*, Aug. 5, 1825, July 13, 1827, April, 18, 1828, Apr. 25, 1828, May 2, 1828, and June 6, 1828; *Mobile Register*, July 19, 1828.

<sup>12</sup> *Niles Register*, XXXVI, 165.

<sup>13</sup> *Southern Advocate*, Aug. 5, 1825.

This is the darker side of a picture which was not all dark. The habit of drinking was almost universal at the time, and the practice of "treating" was looked upon more as hospitality than as bribery. To let this and the other conditions which have been described prejudice one's mind against the people of early Alabama would be to do an injustice to the great mass of them who farmed their patches of cotton and corn; lived a hardy, rugged life close to nature; were friendly toward their neighbors and hospitable toward strangers; made an honest living for themselves and their families; attended to their own business most of the time and only stopped now and then to celebrate.<sup>14</sup>

The planters formed a class to themselves, yet it was neither a closed nor a homogeneous class. The smaller ones lived much as did the farmers, while those with extensive estates sometimes attained an elegance which was impressive. The great majority of them, however, were merely in comfortable circumstances and their pride was based, not upon wealth or display, but upon the sense of independence and authority which their position in society gave them.

Perhaps Montgomery County best represents the planter life of the early days. The soil here was more uniformly fertile than that of most other counties, and consequently it was more uniformly taken up by men of the planter type. Prosperity and independence came to be the rule. Being in easy water communication with Mobile and doing business on a sufficient scale to warrant it, the planters had few dealings with local merchants, but traded directly with the port on the Gulf, generally going down once a year to purchase supplies. The sociability of the people and the law-abiding nature of the community are pictured as ideal, no jail having been maintained and only one duel having been fought during the early period.<sup>15</sup>

It is true that the combination of rural simplicity and native refinement on the plantation at its best furnished the basis for a picturesque and pleasant civilization, but the best is not often attained. In Madison County, for instance, there was a large planting community, but some of the planters were excessively wealthy and used their wealth to secure commercial and political advantages. This aroused the antagonism of

---

<sup>14</sup> Blue MS., St. Clair County, 10; Fayette County, 10; Pickens County, 10.

<sup>15</sup> Robertson, *Montgomery County*, 11-13, 15-16, 36-38, 125, 139-140.

men who were not financially independent, and there was a strong element of Tennessee farmers to wage the fight. In fact there was generally a tendency for the poor to be jealous of the rich, but there was no antagonism against the planters, as such.<sup>16</sup> The plainer people had no political leaders of their own and appear to have been perfectly willing to support planters of means when they made it their business to court popular favor by advocating popular measures.

The social atmosphere of Alabama, as established by the planters, varied from place to place. Where wealth was evenly distributed and notable fortunes and town-life were largely lacking, there does not appear to have been that gaiety of social intercourse which is usually thought of in connection with the plantation. The people spent their time in an unassuming and largely self-sufficient way. But neighborliness and hospitality were not wanting even under these circumstances.<sup>17</sup> Gaiety was the rule, however, in the towns, which furnished the centers of recreation.<sup>18</sup> Dramatic clubs were formed among the younger people, theatres were built in the larger communities, and dances and parties were of frequent occurrence. There was a greater freedom in Western society than in that of the East;<sup>19</sup> calling was more informally done, and women were somewhat less restricted by convention. An Eastern paper criticised the ladies of Huntsville for attending a Fourth of July celebration at the local inn, and a local editor defended them, saying that he saw nothing improper in their having done so.<sup>20</sup> There was a general diffusion of information concerning matters of common knowledge, but though libraries were established in Huntsville and Montgomery, little attention was, as a rule, paid to purely intellectual cultivation. Among the men, horse-racing was a favorite sport and courses were established in the vicinity of the more important towns. Some fanciers had fast horses of English breed and kept race-

---

<sup>16</sup> Huntsville *Democrat*, April 12, 1825, March 17, 1826, July 6, 1827, March 23, 1827; Royall, *Letters from Alabama*, 95, 100.

<sup>17</sup> Saunders, *Early Settlers in Alabama*, 42; Meek, *The Southwest*, 32-33; Blue M.S. Baldwin County, 10, Autauga County, II, 10, Lowndes County, 5, 10, Wilcox County, 10, Lawrence County, 10, Limestone County, 10.

<sup>18</sup> Yerby, *Greensboro*, 17-19; Royall, *Letters from North America*, 48; Hodgson, *Letters from North America*, I, 185; Huntsville *Democrat*, April 13, 1827.

<sup>19</sup> Royall, *Letters From America*, 46.

<sup>20</sup> Huntsville *Democrat*, Sept. 9, 1825.



tracks of their own. Playing for stakes was a common diversion, and drinking was as prevalent among the wealthy as it was among the poorer people. It is stated in the biography of James G. Birney that he, while living in Huntsville, followed the fashion in all these things,<sup>21</sup> and the historian of the Baptist denomination in Alabama asserts that even ministers were often patrons of the bottle and carried potions of their favorite brands in their pockets when they went to meetings.<sup>22</sup> But gentlemen prided themselves on knowing when they had had enough, nor were such practices confined to Alabama at that time. As always, the earliest days were the roughest. A settler of this period who had not attended a trial in many years, was so much impressed by the improved order which he found in the court-room after his long absence, that he said he felt as though he were attending church services.<sup>23</sup>

The conditions under which slavery adjusted itself to a new frontier afford an interesting topic for study, but, since matters of domestic economy were taken for granted, specific information has been difficult to obtain.

Basil Hall gives an excellent description of the plantation system as it existed on a sea-island estate of Georgia in 1828.<sup>24</sup> The hands were rated in accordance with their physical ability and given daily "tasks" in proportion to their strength. The fields were divided into quarter-acre tracts, and one, two, or three of these tracts, depending upon the nature of the work to be done, constituted the task for the day. Diligence enabled the slave to finish his assignment early in the afternoon and he was allowed to spend the remainder of the day at leisure. In this way discipline was maintained and the necessity for compulsion reduced to a minimum.

Hall states that this system was universally employed, saying that the existence of distinct classes in the South discouraged all innovation. Other accounts show that the tasking system existed in South Carolina. Writers of the period stress the necessity for well-defined and clearly-understood regulations in the management of slaves, and the strict enforcement of discipline is insisted upon as a prime necessity.<sup>25</sup> The disgruntled slave had the recourse of running away, and in order

---

<sup>21</sup> Birney's *Birney*, 42, 47-48.

<sup>22</sup> Riley, *Baptists in Alabama*, 61.

<sup>23</sup> Saunders, *Early Settlers in Alabama*, 45.

<sup>24</sup> Basil Hall, *Travels in North America*, 230-239.

<sup>25</sup> *Southern Agriculturist*, II, 575-576.

to prevent this and secure effective organization, regularity, kindness, and firmness were essential.

When the system was transplanted to the new soil of Alabama, differences in spirit, if not in form, would necessarily arise; but the available information is too scant to allow a thorough study of the changes. The provisions for slavery which were incorporated in the constitution of 1819 were of a liberal spirit. The legislature might not forbid the importation of slaves who were the *bona fide* property of their owners, but it was empowered to prohibit the introduction of negroes for sale. Slaves might be freed by their owners with the consent of the legislature, or the legislature might take the initiative in liberating negroes provided the consent of their owners had been obtained, or remuneration made. In addition, slaves were not to be deprived of trial by petit jury when arraigned for crimes more serious than petty larceny; and in the case one were murdered or dismembered, the punishment for the crime was to be the same as though a white man had been the victim. The provisions show a desire to treat the unfortunate race with consideration, but the problem of managing slaves was a delicate one, and difficulties developed. The negroes were irresponsible and often faithless. When they were displeased, they frequently ran away and lodged in swamps to prey upon the surrounding country; when they were allowed to go at large on Sundays, they congregated in the towns and became a public nuisance; when they were allowed to hire out their own time, they often became idlers in the streets; when they were allowed to sell the produce of their leisure hours, they often stole and sold the property of their masters.<sup>26</sup> In order to meet this situation, acts were passed forbidding slaves to sell any articles except such simple things as they could make with their own hands.<sup>27</sup> Passes were required of negroes who wished to visit premises belonging to others than their masters,<sup>28</sup> and in order to prevent slaves from wandering around the country or holding unauthorized meetings where dangerous doctrines might be inculcated, a patrol system was kept up. Military districts were established, all able-bodied men were required to serve in the militia,

<sup>26</sup> *Alabama Republican*, Sept. 13, 1822; *Ibid.*, Aug. 29, 1823; *Alabama Journal*, Jan. 6, 1826; *Ibid.*, May 19, 1826; *Ibid.*, Sept. 15, 1826; *Tusculumbian*, June 28, 1826; *Southern Advocate*, June 22, 1827.

<sup>27</sup> Act of January 2, 1826.

<sup>28</sup> Act of March 6, 1805.

and the captain of each company was required to detail patrols whose duty it was to enforce the law.<sup>29</sup> But the administration of the system was frequently lax, and it, therefore, lacked effectiveness.

Slavery was, at this period, looked upon by Southerners as a necessary evil, and the slave-trader was heartily detested by the planters in general.<sup>30</sup> This spirit found its expression in Alabama through the act of the legislature in 1826 which forbade the introduction of slaves for purposes of sale.<sup>31</sup> It is apparent, too, that this move was assisted by the depressed state of the cotton market which accompanied the panic of 1825, and which caused many to feel that over-production of the staple would result from an increase in the number of laborers.<sup>32</sup> But in this matter, Alabama was merely following the lead of most of the other cotton-producing states.

The question of slavery was open to debate in the South until the activity of the Abolitionists and the Nat Turner insurrection in Virginia convinced the planters that agitation was dangerous to their system and their safety.<sup>33</sup> James G. Birney, who was a resident of Huntsville during these years, was instrumental in the enactment of the lenient provisions in regard to slavery which have been mentioned, and his biographer states that his ideas were not in advance of the sentiment of the planters of that day.<sup>34</sup> Opinions deprecating the existence of slavery were printed by some of the editors who published papers in Alabama,<sup>35</sup> and in 1824 the Tuscaloosa *Mirror* advertised that subscriptions to Benjamin Lundy's pioneer abolitionist paper, the *Genius of Universal Emancipation*, would be received at the office of the local publication.<sup>36</sup> In discussing a memorial from the legislature of Ohio, which advocated general emancipation, the Governor of Alabama spoke mildly and said that an offer of remuneration by the Government might some day be opportune.<sup>37</sup>

---

<sup>29</sup> Act of Dec. 18, 1812.

<sup>30</sup> *Southern Advocate*, Oct. 21, 1826; *Ibid.*, June 23, 1826; Birney's *Birney*, 56; Alabama, Senate Journal, 1823, 15.

<sup>31</sup> Act of Jan. 13, 1827.

<sup>32</sup> Huntsville *Democrat*, Dec. 22, 1826.

<sup>33</sup> Birney's *Birney*, 72.

<sup>34</sup> *Ibid.*, 72.

<sup>35</sup> *Southern Advocate*, Dec. 30, 1825. Speaking of the slave trade, the editor of this paper says: "On one vessel the slaves happily revolted and killed the crew."

<sup>36</sup> Tuscaloosa, *Mirror*, Aug. 7, 1825.

<sup>37</sup> Alabama, Senate Journal, 1825, 13-14.

The first step toward the defensive attitude was taken when the legislature attempted in 1827 to pass an act forbidding the teaching of slaves by free persons. Though receiving the support of a good part of the southern portion of the State, the measure was defeated by the opposition which it encountered in the Tennessee Valley.<sup>38</sup>

This is the only instance where any degree of sectionalism is betrayed in the treatment of a question related to slavery in Alabama during the 'twenties. Even in the vote on the bill to prohibit the further introduction of slaves for sale, there is no alignment of slave-holding against non-slave-holding counties. The Tennessee Valley and the Alabama-Tombigbee Valleys were the principal cotton-producing areas, but this fact would never be discovered by a study of the votes. There were some planters who thought that enough slaves had already been introduced, while there were farmers who expected some day to purchase slaves and become planters themselves. Such a situation emphasizes the point previously brought out that there was no class antagonism between the cotton planter and the small farmer.

In the Tennessee Valley there were a few estates numbering several hundred slaves, but the majority of men who come out to Alabama were in moderate circumstances. It was not those who had made their fortunes, but those who sought to make them, who were willing to sever the old ties and move in to the new country. Twenty or thirty negroes seem to have been a normal force for the average estate, but the majority of men who emigrated to Alabama had, it would seem, not so many as this.

The early history of Alabama appears to have been deeply influenced by the relatively close contact between the planters and the farmers. The frontier conditions which threw men upon their own resources and promoted rapid changes in station; the relatively narrow extent of the cotton-producing areas and the consequent proximity of planting and farming districts; the moderate estates of the planters and the lack of exclusive society outside the largest towns; the relatively small number of planters as compared with the farmers,—all these conditions made Alabama a state where democracy was the rule in spite of slavery.

---

<sup>38</sup> Alabama, House Journal, 1827, 209.

## CHAPTER XV.

---

### CONCLUSION

Having attempted to trace the economic and political development of Alabama during the formative period, it remains to point out those factors which appear to have had special significance. We begin with a country which contained but one white settlement isolated in the midst of Indian tribes. The native had long dreaded the continued intrusion of the white man, and the effects of the unwelcome contact were telling upon him in several important ways. The sturdy self-reliance which the wilderness had instilled in him was being undermined by a state of semi-dependence, while whisky and the sharpers who sold it to him were combining to degrade his natural honesty. But the white man was striking at the roots of his existence in another way. As his land was taken from him bit by bit, the problem of living by the chase became ever more difficult. It was already impossible to rely altogether upon game for subsistence, and all the southern Indians engaged in primitive agriculture, the agents sent among them by the Government doing all they could to promote the industry by the introduction of new crops and improved methods. But the Red Man looked ahead and adopted one or the other of two policies against the future. He either strove to adapt himself to the conditions of civilization, or he assumed an attitude of hostile resistance to the invasion of the whites.

The white men who pushed ahead of civilization into the Alabama region came partly as traders and partly as settlers. Some of the traders took up their abode among the Indians and chose native wives from among them. Those who came for agricultural purposes gathered upon the lower Tombigbee, where the land had been cleared of the Indian title. Some of them used large numbers of slaves in the culture of indigo and cotton, while others raised great herds of cattle which roamed throughout the year in the cane-brakes. English, Scottish, and American blood was mixed with that of the natives in this crude frontier society.

When the War of 1812 was over; when the Creeks had been defeated by Jackson and new lands thrown open to settlement,

squatters rushed in ahead of the Government sales. The best lands were first put on the market, and by the time they were offered at public auction, the high price of cotton had created a feverish demand for these tracts. Currency disorders added to the excitement of speculation, and the result was that the actual settlers, who were men without means, could not compete for possession. It was in the years 1817, 1818, and 1819, during which time the boom rose and fell, that the cotton kingdom was planted in Alabama. The planters from the very first took the river valleys for their own, but the prairie region, passing just south of Montgomery and Tuscaloosa and joining the upper Alabama basin with that of the Black Warrior, was not extensively settled until the period of the 'thirties. With this exception, the cotton producing areas were marked out during the period of first settlement. The men who were not wealthy enough to own slaves or to purchase the most desirable cotton lands took up their abode in the back country, which offered fertile though isolated fields; and here they were usually able to purchase their farms at the minimum price of a dollar and a quarter an acre which prevailed after the speculative period was over. Thus there was not a great deal of active competition between the two agricultural classes in the purchase of lands, and circumstances effected such a distribution of the territory between them that no general readjustment was afterward necessary. It is true that the percentage of slaves in Alabama gradually increased, but the only counties in which the change was marked were those of the prairie region, which had not been extensively settled by men of the farming class.

The outstanding economic factor during the period of settlement was the condition of indebtedness which applied to the community as a whole. Money was in great demand for investment in lands and slaves, and though the production of cotton brought in considerable funds, much was reinvested in agricultural equipment, while a large part went for supplies of flour, corn, and pork. So great was the interest in cotton planting that it was quite difficult to secure capital for other business. The result was that merchandising was left largely to men from the Northern States, while banking had to be carried on either by those who were able to secure special privileges through their operations, or by the State.

While the planter who operated on a large scale could deal directly with Mobile or New Orleans and thereby render him-

self largely independent of country merchants and bankers, the small farmer, dependent upon a local market and a disordered currency, was at a disadvantage in financial transactions. The remoteness of the Tennessee Valley region from New Orleans, and the questionable transactions of the Merchants' and Planters' Bank of Huntsville rendered this situation particularly acute, and promoted a class antagonism between the small farmers, predominantly of Tennessee origin, and the Georgia financiers and their associates. It was out of this antagonism that partisan differences first arose among the people in Alabama; and, though spreading to the rest of the State, the storm-center was always in the north.

Of course there had been political differences from the very first, but these agitated the office-seekers rather than the settlers. It is of much significance for later developments that William H. Crawford, then Secretary of the Treasury under Monroe, controlled the Federal patronage of Alabama during the first years of her existence. Tait, Walker, and the Bibbs were his principal adherents within the State. The jealousy created by this situation cemented the anti-Crawford leaders into a union against the Georgia men. It was probably because North Carolina had sent a number of her prominent citizens to Alabama that she furnished the leading antagonists of the Crawford faction.

Israel Pickens stands out as the first to see the possibilities of the situation and to bring forward an issue which would transform personal differences into real party issues. Provision had been made in the constitution for the establishment of a State Bank and an attempt had been made to found such an institution by private subscription, but the necessary capital was not forthcoming and the plan failed. When Pickens came into office, there was pending a scheme for entrusting the fate of the State corporation to the care of the existing private banks, but Pickens vetoed the bill and proposed a bank the capital of which should consist entirely of the funds of the State. The people needed money, and this was to be a people's bank. Though it was not until the beginning of his second term of office that he was able to put the scheme through, the Bank, which was founded upon democratic rather than upon financial principles, finally went into operation in 1824, to the great delight of all those who had everything to gain and nothing to lose by the experiment.

By this stroke, Pickens had united the anti-Crawford leaders with the men of the small-farmer class, as opposed to the Crawford men from Georgia and the conservative class among the planters and merchants.

In the face of such a combination, the Crawford men had no chance at all and, William Wyatt Bibb and John W. Walker having died, practically all the more desirable offices were wrested from them. The Georgia men had never been strong at general elections, but in the legislature their power had been great, and even now their partisans were able to make a strong fight in that body.

This situation brings out an important point in Alabama politics. The constitution of 1819 is one of the few original frames of State government which lasted without substantial changes until the Civil War. This stability was due, in part at least, to the combination of conservatism with progressiveness in the charter and this character was due to conditions surrounding its origin. In 1819, Alabama had a large number of poor settlers and a small number of wealthy planters and speculators. The former class had little interest in politics, as such, while the latter had many reasons for such an interest. As a matter of course, the men who had the time, the ambition, the ability, and the means to engage in politics were chosen to the convention. Thus the unsuspecting settler sent to represent him a man whose point of view was entirely different from his own. Knowing that they could not afford to antagonize the poorer men who greatly outnumbered them, yet wishing to keep the management of the government in their own hands, the framers of the constitution drew up an instrument which was admirably suited to their purposes. While granting manhood suffrage and apportioning representation according to white population, it gave almost supreme authority to the legislature, which, in the natural course of events, would be made up largely of men of some property.

This arrangement would not have worked as intended had the poorer men ever united to support candidates from among themselves, but this they never did. They accepted their wealthier neighbors as leaders and secured legislation in their favor only when an ambitious politician, such as Pickens, sought popular favor through popular measures.

The lack of consistency in the votes of the legislature proclaims an absence of fixed partisan principles and a prepond-



erance of personal vagaries, but when the people voted, they spoke clearly, and two convictions stand out to show the bent of their minds: there was a strong antagonism between the north and south of the State, and there was a decided preference for Jackson on the part of the plain men. The conservative class showed a strong prejudice against Jackson, but in 1824 they were outvoted in almost every county in Alabama.

It is significant that both sections of the State were carried for Jackson in 1824. It is also significant that the strongest opposition to him was made in the southern cotton-producing area. The percentage of slaves, and hence the strength of the planting interest, was practically the same in the Tennessee Valley as in the Alabama-Tombigbee region. The stronger vote which Jackson received in the former section was due, it would seem, to the greater contrast which existed there between wealth and poverty, and to the class antagonism which the situation engendered. This was aggravated by the fact that, though Tennesseans greatly predominated in the population of the Valley, the planters were largely from other states.

Before the election of 1824, it was generally expected that Adams would carry the southern cotton section of Alabama. The press was strongly in his favor, and the Warrior-Tombigbee section showed a consistent opposition to Jackson in the legislature. The General's unexpected strength in this region may reasonably be taken to indicate the predominance, even in the heart of the cotton belt, of the men whose votes spoke more powerfully than their arguments—the small farmers.

As has been mentioned, the prairie country was the only extensive region where a large proportion of the soil was suitable for cotton culture, and it was only here that the percentage of slaves increased markedly after the first period of settlement was over. Farmers mingled with the planters in all sections of the State, and it is doubtful whether the planters, as a class, could ever have carried more than a few counties of the Black Belt, if even they could have done so much. Their success depended upon their ability to draw support from among their neighbors, and the alliance of the anti-Crawford leaders with the farmers on the bank question shows that there was no aversion to such co-operation.

In the matter of the Presidency, it seems that the farmers and the planters were very clearly divided on the question of Jacksonism, but in 1828 the desire to defeat Adams was strong

enough to unite both classes in support of the General. His old enemies went over with reservations, and their support was but temporary.

Though the Crawford faction had been discredited, and the opposition to Jackson had completely lost its hold by 1828, a movement was already on foot which was fraught with significance for the future, and which was to put a new face upon the political situation.

The belief in a strict construction of the Constitution is as old as the Government, but when Jefferson and his party obtained control, agitation of the point no longer seemed necessary. Possession of power, however, soon changed the point of view of the Republicans, and when the South and the West combined to bring on the War of 1812, the old views seemed to have lost much of their weight with Madison and the slave states. It was at this period of Republican supremacy that John Randolph came forward as the champion of state rights, declaring that his party had forsaken its original principles. Henry Adams says that it was Randolph who forecast the policy of Calhoun by uniting the slave interest with the advocacy of strict construction.<sup>1</sup>

It was not until the free states outstripped the slave states in growth and political power that the South as a whole came to realize that its only hope lay in decentralization. But Randolph looked before him and shaped his policy to the future. There were others who shared his views, however. Among these Nathaniel Macon and John Taylor were prominent. The connection between these men and the Crawford party of Georgia was close, and in a letter to Bolling Hall, Macon urged the point that to give Congress the right to make internal improvements would be to give it the right to free every slave in the United States.<sup>2</sup>

Under these circumstances, it was not strange that Dixon H. Lewis, the nephew of Bolling Hall, was the first advocate of state rights in Alabama, but the movement was not isolated. The election of John Quincy Adams and the enactment of the tariff of 1824 gave the signal for the revival of anti-nationalistic propaganda in the South. South Carolina, under the influence of William Smith and Thomas Cooper, took the

---

<sup>1</sup> Adams, *John Randolph*, 288-289.

<sup>2</sup> Hall Papers, Nathaniel Macon to Bolling Hall, Feb. 13, 1820, and Jan. 6 1825

lead in this movement, while in Congress, Giles and Randolph attacked the Administration from the strict constructionist point of view. But Calhoun did not come out as leader of the state rights movement until after 1828.<sup>3</sup>

Though the Alabama papers took sides with Giles and Randolph or with Adams, according as they were Administration or anti-Administration publications, no state excepting Georgia seems to have influenced Alabama politics directly. Leaders from the Carolinas and Virginia did not form individual groups, but worked in combinations, while those from Georgia formed a distinct faction and thus gave their State a political status in Alabama. Yet, after the fall of the Crawford faction, there was not much sympathy between the two commonwealths. The quarrel between Governor Troup and President Adams over the question of the removal of the Creek Indians from Georgia excited little friendly interest, most of the local editors taking a critical attitude toward the fiery Governor. But in Montgomery County a meeting was held in November, 1826, and here Troup's policy was upheld by some of the leading men of the community.<sup>4</sup> It is natural that such a feeling should have been manifest in this locality, for it was here that the influence of planters from Georgia was strongest. It is also natural that it should have been this County which sent Dixon Hall Lewis to the legislature.

The political ideas of this young man had been shaped by his uncle, Bolling Hall, who was so closely connected with the Crawford faction. Lewis had worked for Crawford in the election of 1824, and now in 1826 he went to Cahawba as a representative in the legislature. His course in opposition to internal improvements and a liberal interpretation of the Constitution was a reflection of a general movement throughout the South. His attitude toward the Troup controversy, and his advocacy of a policy extending the jurisdiction of the State over the Creeks, show his sympathy with the position of the Georgia Governor; while his attack upon the State Bank exhibits his connection with the old Crawford faction.

The majority of men in Alabama at this time were strongly opposed to the Crawford group, strongly in favor of the State Bank, and strongly Nationalistic in their feelings. Yet, by good political management, Lewis succeeded in gaining some

<sup>3</sup> Houston, *A Study of Nullification in South Carolina*, Chap. IX; Boucher, *The Nullification Controversy in South Carolina*, Chap. I.

<sup>4</sup> *Mobile Register*, Nov. 28, 1826.

ground for his ideas. The important point is, however, that this scion of the Crawford party was the first leader in Alabama to advocate state rights, and thus he revived a faction which seemed politically dead by making it the bulwark of the slave power through the policy of strict construction.

The significance of this movement was not to become evident until Jackson's attitude toward South Carolina in the nullification controversy raised up enemies from among his friends. Then Lewis and the men who believed as he did found their numbers greatly strengthened. Then the Whig party grew up in the South and, advocating state rights, it became the mouth-piece of the slave-holders. Thus it was Lewis who formed the transition link between the Crawford faction of 1824 and the Whig party of 1840.

While the slave-holding counties usually came to support the Whigs, those where the small farmer predominated usually remained Democratic. Yet it must be remembered that the slave question never entered directly into partisan divisions. If the farmers had united against slavery, they could still have carried practically the entire State, as they did in 1824; for, even in the strongest slave-holding counties, the planters alone could rarely have commanded a majority of the votes. Their success depended upon their ability to carry their farming neighbors with them, which fact is attested by the great fluctuation in the Whig vote from one campaign to the next.

Other factors, too, are necessary in order to understand the relations between the two parties. The solidly Democratic vote of northern Alabama, in spite of the large number of slaves in the Tennessee Valley, indicates that the rivalry between the two sections of the State had much to do with political alignments. The sectional votes in other States show that local conditions influenced the result, and that slave-holding was not the only important determining factor. For instance, eastern Tennessee and western North Carolina had a much smaller percentage of slaves than did the Tennessee Valley of Alabama, yet the former sections showed a strong Whig tendency, while the latter was uniformly Democratic.<sup>5</sup>

The writer hopes to continue this study in order to trace the influence of early conditions upon later political tendencies and alignments.

---

<sup>5</sup> See maps at the end of *The Whig Party in the South*, by A. C. Cole

## BIBLIOGRAPHY

---

### I. MANUSCRIPT LETTERS AND PAPERS.

- William W. Bibb MS.** This collection of letters, in the possession of the Alabama Department of Archives and History, is invaluable because of the light which it throws upon the relations existing between the first political leaders of Alabama and their friends in Georgia and Washington.
- Biddle MS.** This extensive collection of letters, in the Library of Congress, contains instructions written by Nicholas Biddle to the presidents of some of the Southern branches of the Bank of the United States. These afford some insight into the financial aspects of the cotton trade.
- Blue MS.** The Alabama Department of Archives and History possesses this collection of papers brought together by Mr. M. P. Blue. It consists of information concerning the early history of the several counties of Alabama, various men having contributed from their personal knowledge.
- Bolling Hall MS.** This collection of letters supplements the Bibb papers and gives an inside view of political affairs. It is in the possession of the Alabama Department of Archives and History.
- Jackson MS.** This voluminous collection of the letters of Andrew Jackson contains scattered information concerning Indian affairs, public lands, and politics in Alabama. It is in the Library of Congress.
- Jackson-Coffee MS.** About two hundred letters written by Andrew Jackson to General John Coffee, of Florence, Alabama. They contain scattered information such as that in the above mentioned collection. Typewritten copies of the originals are in the Library of Congress.
- A. B. Meek MS.** Papers brought together by Mr. Meek with the idea of publishing a history of Alabama. In Alabama Department of Archives and History.
- Mississippi Transcripts.** Transcripts made by Dr. Thomas M. Owen from the original records of Mississippi Terri-

tory, which material is preserved by the Mississippi Department of Archives and History.

Pickett MS. Certain unpublished papers of A. J. Pickett, author of the *History of Alabama*. They are preserved by the Alabama Department of Archives and History.

Charles Tait MS. These letters, copied from the originals, are in Alabama Department of Archives and History. They supplement the Bibb, Hall, and Walker papers, and are especially valuable because they contain letters from such men as William H. Crawford and John C. Calhoun, giving an insight into the political affiliations of the leaders in Alabama.

J. W. Walker MS. Containing letters dealing with the most important events in the early history of Alabama.—Alabama Department of Archives and History.

Yancey Papers. Collection in the Alabama Department of Archives and History; contains the manuscript of an obituary notice of Dixon Hall Lewis, which gives the best available account of the early life of that important man.

## II. DOCUMENTARY MATERIAL.

The published documents of the Federal Government, especially the *American State Papers* and the *Statutes at Large*, have been used extensively in this work. In addition, the records of the General Land Office and of the Indian Office have been searched. The local and special documents used are listed below:

Alabama—*Journal of the Constitutional Convention of 1819.*  
*Acts of the Legislature of Alabama Territory,*  
1819.

*Acts of the General Assembly of Alabama, 1819-*  
1828.

*Journal of the Council of Alabama Territory, 1818.*

*Journal, of the Senate of Alabama, 1819-1828.*

*Journal, of the House of Representatives of the*  
*State of Alabama, 1819-1828.*

Aiken, John G.—*Digest of the Laws of the State of Alabama,*  
Philadelphia, 1833.

Brickel, R. C.—*Digest of the Decisions of the Supreme Court*  
*of the State of Alabama,* Montgomery, 1874.

Hitchcock, Henry—*The Alabama Justice of the Peace,* Cahawba, 1822.

- Holmes, David—Executive Journal of Governor Holmes, of Mississippi Territory, 1814-1817, MS.
- Morse, Jedidiah—*Report on Indian Affairs* (1820), New Haven, 1822.
- Owen, Thomas M.—*Alabama Archives*, Washington, Government Printing Office, 1905.
- Snedecor, V. Gayle—*A Directory of Greene County for 1855-6*, Mobile, 1856.
- Tharin, W. C.—*A Directory for Marengo County for 1860-61*, Mobile, 1861.
- Toulmin, Harry—*A Digest of the Laws of the State of Alabama*, Cahawba, 1823.
- United States, House Documents, 26. Cong., 1 Sess., Doc. 172, p. 1348. Table showing condition of Alabama banks, 1819-1838.
- University of Alabama, *Historical Catalogue, 1821-1870*, Tuscaloosa, 1870.

### III. CONTEMPORARY SOURCES.

- Breckenridge, Richard, *Diary*, 1816, in Alabama Historical Society, Transactions, III, 142-153. A good first-hand account of Alabama as seen by one who came out upon the first wave of settlement.
- Commons, J. R., *Documentary History of American Industrial Society*. Vols. I and II, by U. B. Phillips, deal with Southern agriculture, but Alabama receives little attention. Cleveland, 1910.
- Cummins, E. H., *A Summary Geography of Alabama, one of the United States*, Philadelphia, 1819. Inaccurate, but interesting.
- Darby, William, *A Geographical Description of the State of Louisiana, the Southern Part of the State of Mississippi and Territory of Alabama, with a Map*, New York, 1817.
- Darby, William, *Emigrant's Guide*, New York, 1818. Contains interesting information for this early date.
- Fessenden, Thomas G., *The Complete Farmer*, Philadelphia, 1839.
- Gaines, George S., *Letters Relating to Events in South Alabama, 1805-1814*, Alabama Historical Society, Transactions, III, 184-192.
- Garrett, William, *Reminiscences of Public Men in Alabama for Thirty Years*, Atlanta, 1872. Contains excellent first-

hand information of men and events during the period under consideration.

Thwaites, Reuben Gold, *Early Western Travels*. A large collection of accounts by travelers and explorers. The Tennessee River region is touched upon, but there is nothing for the southern part of Alabama.

Hall, Basil, *Travels in North America in the Years 1827 and 1828*, Philadelphia, 1829. Being a captain of the British Navy, Hall has a point of view different from that of any other traveler of that period, and his discussion of scenes in Alabama is instructive.

Hawkins, Benjamin, *A Sketch of the Creek Country, 1798-1799*, in Collections of Georgia Historical Society, III, Pt. I. Published at Savannah, 1848. Hawkins was agent among the Creeks for many years, and this is the best available account of that Nation at the time when the pressure of the white immigration into the southwest was beginning to tell.

Hodgson, A., *Letters from North America*, London, 1824. These letters written in 1820 by a studious observer, form an important source of information.

Holland, Edwin C., *A Refutation of the Calumnies Circulated Against the Southern and Western States Respecting Slavery*, Charleston, 1822. This account of slavery is based upon conditions in South Carolina, but it is the best available Southern treatise on the subject for the period under discussion in this paper.

Levasseur, A., *Lafayette en Amerique en 1824 et 1825*, Bruxelles, 1829. The author was secretary to Lafayette during his tour of America. The account is more interesting than instructive.

Lincecum, Gideon, *Autobiography*, in Mississippi Historical Society, Publications, VIII, 443. An interesting account of his journey by one of the early immigrants to Alabama.

Macaulay, Zachary, *Negro Slavery in the United States and West Indies*, London, 1823. This gives an English view of the subject, and is violently critical.

Methodist Episcopal Church, *Minutes of the Annual Conferences, 1773-1828*, Vol. I, New York, 1840. Here can be obtained statistics of the various congregations throughout the Country.

Morse, Jedidiah, *Geography*, Charleston, 1819.



- Owen, John, *Journal*, 1818, in Southern Historical Association Publications, I, 90-97. Another account written by an early immigrant of his journey to Alabama.
- Price, T. W., *The Life of T. W. Price, Written by Himself*, Selma, 1877. There is little information of a public nature in this book.
- Raymond, James, *Prize Essay on the Comparative Economy of Free and Slave Labor in Agriculture*, published by the Frederick County Agricultural Society, Frederick, Md., 1827. This view is too superficial to be of value to the student.
- Robertson, W. G., *Recollections of the Early Settlers of Montgomery County*, 1892. This is an interesting account of an interesting community, written by one who says that "the writer was personally acquainted with every one of them."
- Royall, Anne, *Southern Tours, or Second Series of the Black Book*, Washington, 1830. These letters, written on a second tour of Alabama, are interesting because they indicate the contrast produced by ten years of development in the new State.
- Royall, Anne, *Letters from Alabama on Various Subjects, 1817-1822*, Washington, 1830. Written by an erratic woman, there is a good deal that is personal and a good deal that is pertinent in these letters.
- Saxe-Weimar, Duke Bernhard of, *Travels Through North America During the Years 1825 and 1826*, Philadelphia, 1828. Traveling the same route between New York and New Orleans that was followed by most of the foreign tourists, and passing through Montgomery and Mobile, this author gives us still another point of view.
- Stuart, James, *Three Years in North America*, New York, 1833. Another and later account by one who passed along the same route followed by Saxe-Weimar and others.
- Townes, S. A., *The History of Marion*, Marion, 1844. This is a good account of the establishing of a new community in Alabama.
- Terry, Jesse, *A Portraiture of Domestic Slavery in the United States*, Philadelphia, 1817. A good Northern view.
- Warden, D. B., *A Statistical, Political, and Historical Account of the United States of North America*, Edinburgh, 1819.

- Welsh, Mary, *Reminiscences of Old St. Stephens*, in Alabama Historical Society, Transactions, III, 208-226. This is a retrospective account by one who had known the place long since.
- Woodward, Thomas S., *Reminiscences of the Creek or Muscogee Indians*, Montgomery, 1859. There is much here that does not concern Indians, and, since the author knows the ground, the information is of value.
- Wyman, Justus, *A Geographical Sketch of the Alabama Territory*, in Alabama Historical Society, Transactions, III, 107-127. Only a part of the original account is published here, the unpublished manuscript being in the possession of the Woburn, Massachusetts, Public Library.

#### IV. SPECIAL WORKS AND ARTICLES

Excepting in the case of Pickett's work and the local histories, little reliance has been placed upon the secondary material dealing especially with Alabama. This is for the reason that most of it touches but scantily upon the early period discussed in this monograph.

- Ball, T. H., *Clarke County and Its Surroundings*, title page missing, 1882. This contains good information of local character.
- Betts, E. C., *Early History of Huntsville, Alabama*, Montgomery, 1909. This is one of the best of local histories, and, because of the importance of the community, is of especial value.
- Birney, William, *James G. Birney and his Times*, New York, 1890. Though only a small part of this book deals with the Alabama period of Birney's life, it contains some worth-while information.
- Blue, M. P., *History of Montgomery*, Montgomery, 1878. The author was a diligent collector of local information, and his account is of value.
- Blue, M. P., *Churches of the City of Montgomery*, Montgomery, 1878. This account goes back to beginnings.
- Brant and Fuller, Compilers, *Memorial Record of Alabama*, Madison, Wisconsin, 1893. Too biographical; good for reference only.
- Brewer, W., *Alabama: Her History, Resources, War Record, and Public Men, 1540-1872*, Montgomery, 1872. This book does not give a good general account, but the discus-

sion of the separate counties contains desirable information.

- Brown, W. G., *A History of Alabama*, University Publishing Company, 1900. A textbook, based upon insufficient material.
- Burnett, E. C., *Bourbon County*, in *American Historical Review*, XV, 66-111, 297-353.
- Claiborne, J. F. H., *Mississippi as a Province, Territory, and State*, Jackson, 1880. This contains valuable information on the question of the division of Mississippi Territory.
- Claiborne, J. F. H., *Life and Times of General Sam Dale*, New York, 1860. A good biography of an interesting man.
- Clarke, Willis G., *History of Education in Alabama*, Washington, 1889. Contains but little relative to the formative period.
- Cobbs and Whittaker, *Statistics of the Protestant Episcopal Church of Alabama*,—Alabama Historical Society, Transactions, II, 83-89.
- Denson, John V., *Slavery Laws in Alabama*; in Alabama Polytechnic Institute Historical Studies, Auburn, 1908.
- Dewey, D. R., *Financial History of the United States*, New York, 1915.
- Donnell, E. J., *Chronological and Statistical History of Cotton*, 1879. Exhaustive statistics.
- DuBose, Joel C., Ed., *Notable Men of Alabama*, Southern Historical Association, Atlanta, 1904. Little of general interest.
- DuBose, Joel C., *Sketches of Alabama History*, Philadelphia, 1901. This contains good information on special topics.
- Flint, Timothy, *The History and Geography of the Mississippi Valley*, Cincinnati, 1833. Little information for Alabama.
- Hall, J. H. B., *The History of the Cumberland Presbyterian Church in Alabama Prior to 1826*; in Alabama Historical Society, Transactions, IV, 365-394. This gives some idea of religious conditions during the early period.
- Hamilton, P. J., *Early Roads in Alabama*; in Alabama Historical Society, Transactions, II, 39-56. Information incomplete.
- Hamilton, P. J., *Some Southern Yankees*, American Historical Magazine, III, 303-312. Personal, but interesting.

- Hamilton, P. J., *St. Stephens: Spanish Fort and American Town*; in Alabama Historical Society, Transactions, III, 227-234. Not satisfying.
- Hamilton, P. J., *Colonial Mobile, 1519-1821*, Houghton Mifflin, 1910. A work signifying much research and containing much information.
- Hammond, M. B., *The Cotton Industry*, New York, 1897. Valuable.
- Hardy, John, *Selma, her Institutions and her Men*, Selma, 1879. A good local history.
- Harper, Roland M., *Economic Botany of Alabama*, bulletin of the Geographical Survey, 1913. Valuable for topographical information.
- Harper, Roland M., *A Preliminary Soil Census of Alabama and West Florida*, Reprint from *Soil Science*, IV, No. 2., Aug. 1917.
- Harvey, Meriwether, *Slavery in Auburn, Alabama*; in Alabama Polytechnic Institute Historical Studies, Auburn, 1907. A limited view.
- Haskins, Charles H., *The Yazoo Land Companies*, New York, 1891. Important for an understanding of the situation in regard to the public lands.
- Hodgson, Joseph, *The Cradle of the Confederacy*, Mobile, 1876. An important work, but contains little information for the early period.
- Jack, Theodore H., *Sectionalism and Party Politics in Alabama, 1819-1842*, Banta Pub. Company, Menasha, Wisconsin, 1919. This is the only scientific political study for this period, but little space is devoted to developments previous to Jackson's administration.
- Jones, Charles C., *Antiquities of the Southern Indians*, New York, 1873.
- Jones, Charles C., *The Dead Towns of Georgia*, Savannah, 1878.
- Leftwich, Geo. J., *Cotton Gin Port and Gaines' Trace*, in Mississippi Historical Society, Publications, VII, 263. This article throws light upon one of the earliest transportation developments in the Alabama-Mississippi region.
- Little, John Buckner, *The History of Butler County, Alabama*, Cincinnati, 1885. Scant and unreliable for the early period.
- Love, Wm. A., *General Jackson's Military Road*, in Mississippi Historical Society, Publications, XI, 403-417.

- McDonnold, B. W., *History of the Cumberland Presbyterian Church* Nashville, 1888.
- Martin, W. E., *Internal Improvements in Alabama*, in Johns Hopkins University Studies, Series 20, No. 4, Baltimore, 1902. This account is made up of undigested statistics.
- Meek, A. B., *Romantic Passages in Southwestern History*, Mobile, 1857. This contains a good treatment of certain phases.
- Monette, John W., *History of the Valley of the Mississippi*, New York, 1846.
- Mooney, James, *Myths of the Cherokee*, in the Nineteenth Annual Report, Bureau of American Ethnology, Pt. 1, 11-548.
- Owen, Thomas M., *History of Alabama and Dictionary of Alabama Biography*, IV Vols., Chicago, 1921. An encyclopedic work containing exhaustive information, and invaluable to the student of Alabama history. Published since the writing of this monograph.
- Phillips, U. B., *American Negro Slavery*, New York, 1918. A most helpful treatise, covering all phases of the subject from the agricultural point of view.
- Phillips, U. B., *The Economics of the Plantation*, in the South Atlantic Quarterly, II, 231. A suggestive study.
- Phillips, U. B. *The Southern Black Belt*, American Historical Review, XI, 798. This is an interesting study of the segregation of the slave interest.
- Phillips, U. B., *The Slave Labor Problem in the Charleston District*, Boston, 1907.
- Phillips, U. B., *The Plantation as a Civilizing Factor*, Sewanee Review, XII, 257. An original view.
- Phillips, U. B., *A History of Transportation in the Eastern Cotton Belt to 1860*, New York, 1908. Helpful and suggestive.
- Phillips, U. B., *Georgia and State Rights*, in American Historical Association, Report, 1901, II, 15-224, Separate, Government Printing Office, 1902. Owing to the close relation between Georgia and Alabama politicians during the period covered by this study, this work has been of great value.
- Pickett, A. J., *History of Alabama*, Birmingham, 1900. Though somewhat involved in details, this book represents careful research by a man who also had wide personal knowledge in his field; on many points, therefore, it is an orig-

- inal source. Though not without error, it is the only solid work covering Alabama history previous to the period of Statehood.
- Pitkin, Timothy, *Statistical View of the Commerce of the United States*, Hartford, 1816.
- Powell, George, *History of Blount County*, in Alabama Historical Society, Transactions, 1855. This gives valuable information for the period of early settlement.
- Reeves, Jesse S., *The Napoleonic Exiles in America*, in Johns Hopkins University Studies, XXIII, 525-656.
- Riley, B. F., *History of Conecuh County, Alabama*, Columbus, Georgia, 1887. Gives vivid pictures of the pioneer period.
- Riley, B. F., *History of the Baptists of Alabama*, Birmingham, 1895.
- Riley, B. F., *Makers and Romance of Alabama History*, Birmingham, 1914. This book is made up of chapters on various unrelated topics, some of which are illuminating. Its biographical sketches are good for reference.
- Riley, F. L., *Location and Boundaries of Mississippi*, in Mississippi Historical Society, Publications, III, 167-184.
- Saunders, J. E., *Early Settlers of Alabama*, New Orleans, 1899. Contains good general information, and the biographical portion is sometimes useful for reference.
- Shakelford, Josephus, *History of the Muscle Shoals Baptist Association, 1820-1890*, Trinity, Ala., 1891. The point of view is so local that the work is not of much service.
- Shea, J. G., *History of the Catholic Church in the United States*, Akron, Ohio, 1890. Contains a good account of the activities of the Catholic Church in Alabama during the period under review.
- Smith, Nelson F., *History of Pickens County, Alabama*, Carrollton, Alabama, 1856. This is one of the best local histories, giving a good idea of the early development of one of the counties in the back country.
- Smith and DeLand, Publishers, *Northern Alabama*, Birmingham, 1888. Scattered information of general interest; but valuable principally for biographical reference.
- Somerville, H. M., *Trial of the Alabama Supreme Court Judges in 1829*, in report of the twenty-second annual meeting of the Alabama State Bar Association, Montgomery, 1899. A good brief account.

- The South in the Building of the Nation*, Richmond, 1909. This is a co-operative work. The portions relating to Alabama are too general to be of value for the period under discussion.
- Sparks, W. H., *The Memories of Fifty Years*, Macon, Ga., 1872. Good material for Georgia and Mississippi, but little of value for Alabama.
- Stone, Alfred H., *The Cotton Factorage System of the Southern States*, in *American Historical Review*, XX, 557-565. This is a scientific and suggestive article.
- Street, O. D., *Marshall County One Hundred Years Ago*, Gunter'sville, Ala., 1903. Contains some good information.
- Teeple and Smith, Publishers, *Jefferson County and Birmingham*, Birmingham, 1887. Too biographical to be of real service.
- Thomas, William H., *The Birth and Growth of the Constitution of Alabama*, an address delivered before the Alabama State Bar Association, Montgomery, 1890. Some good points are made in this paper.
- Tompkins, Alma Cole, *Charles Tait*, in *Alabama Polytechnic Institute Historical Studies*, Auburn, 1910. A good brief account.
- United States Department of Agriculture, *Atlas of American Agriculture*, Part V, Section A—Cotton, Washington, 1918. Contains valuable statistics and historical information.
- Wallace, J. H., *The Alabama State Capital*, Montgomery, 1911. Contains nothing of value for the early period.
- Watkins, J. L., *Production and Price of Cotton for a Hundred Years*, U. S. Dept. of Agriculture, Washington, 1895.
- Weeks, Stephen B., *History of Public School Education in Alabama*, Washington, Government Printing Office, 1915. Though touching but lightly upon the early period, this is a reliable work.
- West, Anson, *A History of Methodism in Alabama*, Nashville, 1893. This is not a scholarly work.
- Whitaker, Walter C., *History of the Protestant Episcopal Church in Alabama*, Birmingham, 1898. Contains little for the early period.
- Whitfield, Gaius, Jr., *The French Grant in Alabama*, in *Alabama Historical Society, Transactions*, IV, 321-355. This is a fairly satisfactory account of the founding of Demopolis by the Napoleonic refugees.

- Williams, Thomas M., *Dixon H. Lewis*, in Alabama Polytechnic Institute Historical Studies, Auburn, 1912. Considering the available material, a satisfactory work.
- Yerby, W. E. W., *History of Greensboro, Alabama*, Montgomery, 1908. This account contains some useful information.

## V. NEWSPAPERS AND PERIODICALS.

- Alabama Journal*, Montgomery; in the Library of Congress, Dec. 9, 1825—July 7, 1826, Nov. 28, 1828; in Alabama Department of Archives, Sept. 8, 1826—July 27, 1827.
- Alabama Republican*, Huntsville; in the Library of Congress, Jan. 5, 1819—April 22, 1825; in Alabama Department of Archives, Sept. 15, 1820—Sept. 13, 1822.
- Alabama Sentinel*, Tuscaloosa; in the Library of Congress, Dec. 30, 1825.
- American Mirror*, Tuscaloosa; in the Library of Congress, Jan. 3, 1824—Feb. 26, 1825.
- Cahawba Press and Alabama State Intelligencer*, Cahawba; in the Library of Congress, Dec. 30, 1820—July 22, 1826.
- Democrat*, Huntsville; in Alabama Department of Archives, Oct. 14, 1823—Dec. 29, 1826.
- Franklin Enquirer*, Tuscumbia; in Alabama Department of Archives, March 13, 1824—June 9, 1824.
- Halcyon*, Greensboro; in the Library of Congress, April 24, 1823—Dec. 30, 1823.
- Halcyon and Tombeckbee Public Advertiser*, St. Stephens; in the Library of Congress, Jan. 9, 1819—Dec. 20, 1819; Jan. 10, 1820—Nov. 27, 1820; Feb. 12, 1821—Dec. 22, 1821; Jan. 5, 1822—Nov. 2, 1822.
- Mobile Argus*; in the Library of Congress, Dec. 5, 1822—Nov. 6, 1823.
- Mobile Commercial Register*; in Alabama Department of Archives, Nov. 17, 1827—Dec. 5, 1828, and following; in Association Public Library, Mobile, Dec. 17, 1821—Dec. 7, 1824; Dec. 9, 1825—Dec. 9, 1826; June 4, 1828—May 29, 1829, and following; in the Library of Congress, Feb. 18, 1825—Dec. 21, 1826.
- Mobile Mercantile Advertiser*, in the Library of Congress, May 10, 1825—Dec. 18, 1824.



*Southern Advocate*, Huntsville; in the Library of Congress, May 6, 1825—Dec. 24, 1828; in Alabama Department of Archives, May 6, 1825—April 27, 1827; May 18, 1827, and following.

*Tuscumbian*, Tuscumbia; in Alabama Department of Archives, Sept. 1, 1824—Jan. 17, 1827.


*Washington Republican*, Washington, Mississippi Territory; in Mississippi Department of Archives, April 13, 1813—Dec. 27, 1817.

*American Farmer*, Baltimore, 1820-1828.

*Niles Weekly Register*, Baltimore, Vols. 11-36.

*The Southern Agriculturist*, Charleston, Vols. 1 and 2, 1828-1829.

Chap. I.—Plate 1.



See Maps, Bureau of Ethnology, 18 Annual Report.




Geological Map of Alabama. From R. M. Harper, *Preliminary Soil Census of Alabama*, p. 93.



Roads—Based on map of U. S. by John Melish, 1818.


Chap. III.—Plate 4. Origin of Population (approximate).





House Journal, 1819, 37.

Chap. V.—Plate 6. To Disapprove Act of Certain Members of Congress in Censuring General Jackson. House, 1819.



House Journal, 1819. 45.

(166)

Alabama


FROM A SURVEY BY JOHN W. HARRIS

Chap. V.  
Plate 7.

(167)




Chap. V.—Plate 8. To Reduce Judicial Tenure to Six Years.  
Constitutional Convention, 1819.




Journal of Constitutional Convention, 1819.  
(168)

Chap. V.—Plate 9. To Make Majority of Members Elected to Legislature Sufficient to Establish Branch Bank or Renew Bank Charter. Constitutional Convention, 1819.




Chap. VI.—Plate 10. Indian Cessions.



Bureau of Ethnology, 18 Annual Report, Plate I.  
(170)

Chap. VI.—Plate 11. Value of Lands Sold in Alabama.  
In \$100,000's.



Land Office at

St. Stephens = ———

Huntsville = - - - - -


Cahawba = . . . . .

American State Papers, Lands, V, 384-385.

(171)

Chap. VII.—Plate 12. Average Yearly Price of Middling Upland Cotton.

In cents.




New York Price = —

Liverpool Price = ----

J. L. Watkins, *Production and Price of Cotton*, U. S. Department of Agriculture, Statistics, Miscellaneous Bulletins, No. 9, 8-9, 1895. Also used by later writers.


Chap. VII.—Plate 13. Average Valuation of Slaves in Mobile.

In dollars.



DeBow, *Industrial Resources*, II, 79.

Chap. VII.—Plate 14. Cotton Crop of South Alabama, 1818-1830.  
In 1,000 bales.




Computed increase in crop proportionate to increase in number of  
slaves indicated by — — — — —

Hazard, *U. S. Commercial and Statistical Register*, III, 272.

(From Mobile Letter Sheet.)


Chap. VII.—Plate 15. Slave Population. Census, 1818



Walker Papers.  
(175)




Chap. VII.—Plate 16. Slave Population, 1824.




Huntsville Democrat, Nov. 22, 1824. LaTourette Map.


Chap. VII.—Plate 17. Slave Population, 1830.




See U. S. Census, 1830.



Chap. IX.—Plate 19. Imports and Exports at Mobile.  
In \$100,000.




Chap. XI.—Plate 20. Presidential Election of 1824.



Huntsville Democrat, Nov. 22, 1824. Cahawba Press, Nov. 22, 1824, et seq.


Chap. XI.—Plate 21. On Motion Proposing Jackson for Presidency.  
Senate, 1823.




Senate Journal, 1823, 82.

(181)

Chap. XI.—Plate 22. On Motion Proposing Jackson for Presidency.  
House, 1823.



House Journal, 1823, 77.  
(182)




House Journal, 1822, 83.

(183)




Chap. XI.—Plate 24. Election of United States Senator, 1822.



House Journal, 1822, 80.


(184)

Chap. XI.—Plate 25. Election of United States Senator, 1824.



Senate Journal, 1824, 60.


Chap. XII.—Plate 26. Vote on Bill to Extend Jurisdiction of State  
Over Creeks. House, 1828.




House Journal, 1828, 263.


(186)

Chap. XII.—Plate 27. House Vote in Election of United States Senator, 1826.






Chap. XII.—Plate 29. Vote on Bill Fixing the State Capital at Tuscaloosa. House, 1825.



House Journal, 1825, 75.

(189)

Chap. XII.—Plate 30. Vote on Lewis Report Proposing Jackson for  
 Presidency. House, 1827.



House Journal, 1827, 182 et seq.

Chap. XIII.—Plate 31. From La Tourette Map, 1838.




UNIVERSITY OF THE STATE OF ALABAMA, TUSTALOOSA, AL.

Chap. XIII.  
Plate 31.



Chap. XIV.—Plate 32. Vote on Bill to Prohibit Import of Slaves to State. Senate, 1826.





FEB 28 40

7.



**ALDERMAN LIBRARY**

The return of this book is due on the date  
indicated below

DUE	DUE
<del>MAY 2 1965</del>	
<del>OCT 1 8 1965</del>	
<del>OCT 4</del>	
10-1494 9/70/96	

Usually books are lent out for two weeks, but there are exceptions and the borrower should note carefully the date stamped above. Fines are charged for over-due books at the rate of five cents a day; for reserved books there are special rates and regulations. Books must be presented at the desk if renewal is desired.

L-1

CX 002 529 982

